Swarm User Guide

Swarm Development Group

Paul Johnson
University of Kansas
Department of Political Science

pauljohn@ukans.edu

Alex Lancaster
Santa Fe Institute

alex@santafe.edu

Swarm User Guide

by Swarm Development Group
by Paul Johnson and Alex Lancaster

Published 10 April 2000
Copyright © 1999-2000 by Swarm Development Group

A User's Guide for the Swarm Simulation System

This document began with the Swarm Tutorial presented at SwarmFests 1998 and 1999 by Benedikt Stefansson of CASA Inc. (formerly of UCLA Department of Economics). The Swarm Toolkit is discussed in three stages of increasing detail. The first part provides an introductory treatment and description of Swarm. The second part provides a deeper survey of the anatomy of a swarm program. The third part goes into significantly greater detail on some elements of programming in Swarm that users are likely to enounter as they build programs with Swarm. Users are encouraged to explore the Swarm sample programs and to visit the Swarm home page (http://www.swarm.org), where they can find out the latest news and join the Swarm e-mail community.

Paul Johnson's effort on this project was supported in part by a grant from the National Science Foundation (SBR-9709404). Paul is the primary author of the main bulk of the *Guide* material.

Alex Lancaster is responsible for most of the SGML-"smithing" and markup issues in DocBook (see Colophon) and supplied additional material and text.

Licence terms for Swarm User Guide

Reproduction of this documentation requires prior copyright release in writing, from the copyright holder (the Swarm Development Group); *except* for reasonable personal use or educational purposes. Reproduction for mass distribution or profit, is not permitted. The SGML source and associated utilites needed to generate this documentation can be found in the package: userbook-0.9.tar.gz (ftp://ftp.swarm.org/pub/swarm/userbook-0.9.tar.gz). Permission to use, copy, modify and distribute both the swarmdocs package *and* the documentation it generates (that is the HTML, TeX, dvi, PostScript and RTF output), must be in accordance with the GNU General Public Licence (http://www.gnu.org/copyleft/gpl.html) (GPL).

Table of Contents

About this Guide **9**

Part I. Basic Concepts **11**

1. Introduction 12
    - 1.1. Basic Facts About Swarm 12
    - 1.2. Swarm is a Dynamic Platform 13
    - 1.3. Prerequisites for Success with Swarm. 14
2. Programming and Simulation 16
    - 2.1. What is an Object? 16
    - 2.2. The Variety of Objects 18
    - 2.3. The Advantages of Object Oriented Programming 18
        - 2.3.1. Encapsulation 18
        - 2.3.2. Inheritance 19
    - 2.4. Discrete Event Simulation 20
3. Nuts and Bolts of Object-Oriented Programming 21
    - 3.1. Multilanguage support and Swarm 21
        - 3.1.1. Objective C 21
        - 3.1.2. Java 21
        - 3.1.3. Why is Swarm Written in Objective C? 22
    - 3.2. Objective C Basics 22
        - 3.2.1. The `id` Variable Type 22
        - 3.2.2. Interface File: Declaration of a Class 23
        - 3.2.3. Implementation File: Defining a Class 25
        - 3.2.4. C Functions vs. Objective C Methods 26
    - 3.3. Java Basics 27
    - 3.4. Giving Life to Classes: Instantiation 28
        - 3.4.1. Instantiation: Objective C Style 29
        - 3.4.2. Instantiation: Java Style 30
    - 3.5. A Brief Clarification: Classes and Protocols in Objective C 30
4. The notion of a Swarm 33
    - 4.1. Primary and Auxiliary Agents 33
    - 4.2. The (Swarm) OOP way 33
    - 4.3. Managing Memory in Swarms 34
    - 4.4. What goes on in the **`buildObjects`** method? 34
    - 4.5. What goes on in the **`buildActions`** method? 35
    - 4.6. Merging Schedules in Swarms 36
5. The Graphical User Interface 38
    - 5.1. Elements of the Swarm GUI 38
    - 5.2. GUI Probe Displays 40

5.3. Using the GUI Probe Display 42
Part II. Swarm Applications: Examples and Illustrations 44
6. The Swarm Tutorial: Reprise 45
6.1. Tutorial Progression 45
6.2. What Are You Supposed to Learn from the Tutorial? 46
6.3. After the Tutorial: What now? 48
7. Creating Objects In Swarm 49
7.1. Begin at the Beginning 49
7.2. Detailed Look at **createBegin/createEnd** 49
7.3. Swarm Zones and Recursive Objects Creation 51
7.4. Using Swarm Library Objects and Header Files 53
7.5. Variations on a Theme 55
7.6. How Do You Kill Off Those Poor Little Devils? 56
8. Doing the Chores: **set** and **get** 59
8.1. Get and Set Methods 59
8.2. Using Set Methods During Object Creation 60
8.3. Passing Information Around 61
8.4. Circumventing the Object-Oriented Guidelines 63
9. Building Schedules 64
9.1. Building `Schedule`s 64
9.2. What's that **M()** Thing? 65
9.3. `ActionGroup`s 68
9.4. Activating Swarms 69
9.5. What is an `Activity`? 70
9.6. Dynamic Scheduling 71
10. Working with Lists 73
10.1. The `List` Class 73
10.2. Basic `List` Syntax 73
10.3. Lists: Managing Objects in the Model Swarm 74
10.4. Lists: Passing Information Among Levels in a Swarm Model 76
10.5. Lists: Organizing Repetitive Chores inside Objects 77
11. Checking on a Swarm's progress: The Observer 81
11.1. Monitoring a Swarm 81
11.2. Making a clickable `ZoomRaster` 81
11.3. Displaying Results in Graphs 86
12. Probing and Displaying the Contents of Swarm Objects 88
12.1. What's a Probe? 88
12.2. Managing Probe Displays 89
12.3. How to Customize Probe Displays 91
12.4. Controlling Precision of Display 93

12.4.1. Global setting of precision 94
12.4.2. Setting Precision for Individual Probes 95
Part III. Advanced Topics 97
13. Anything C can do, Swarm Can Do Better 98
13.1. Managing command line parameters 98
13.2. Using C Functions in Swarm 101
13.3. Examples of Useful Functions: **`getInt`** and **`getDouble`** 103
13.4. Dynamic Memory Allocation and Swarm Zones 104
13.5. Dropping Unused Objects 106
14. The Swarm Collections Library 109
14.1. Overview: the `List`, `Map` and `Array` Protocols 109
14.2. Choosing between `List`s, `Map`s, and `Array`s 110
14.3. Using Swarm `Array`s 111
14.4. Swarm `Map`s 112
14.5. Accessing Collections with Indices 117
15. Using the Random Library 119
15.1. Built-in Random Number Distributions 119
15.2. Overview of the Random Library 120
15.3. The Random Number Generators 122
15.3.1. How to use the default random generator 122
15.3.2. A list of generators in Swarm 123
15.3.3. A note on starting seeds 124
15.4. The Distributions in Swarm 125
15.4.1. Classes that adopt the ProbabilityDistribution Protocol 125
15.4.2. Matching generator and distribution objects 125
15.4.3. Setting numerical parameters of distribution objects 126
15.5. How to Create Other Random Number Distributions 127
16. Serialization 129
16.1. Using the `LispArchiver` to manage simulation parameters 129
16.1.1. Using the Standard *`lispAppArchiver`* 129
16.1.2. Using Custom `LispArchiver` Instances 132
A. Swarm Tools 135
A.1. Web Resources for Object-Oriented Languages 135
A.2. Debugging Tips for Swarm 135
A.2.1. Finding bugs 136
A.2.2. Preventing Bugs: Objective C 136
A.2.3. Preventing Bugs: Java 137
A.3. Emacs and Swarm 137
A.3.1. Objective C 138
A.3.2. Java 138

B. Objective C - Swarm Style 139
B.1. Non-Conventional Techniques, And The Libraries In Which They're Used 139
B.2. Zones 139
B.2.1. Zones in Principle 139
B.2.2. Zones in Practice 139
B.3. Create Phase 140
B.3.1. The Create Phase in Principle 140
B.3.2. The Create Phase in Practice 141
B.4. Collections and Defobj 142
C. Random Library Appendix 144
C.1. Supplemental comments on random number generators 144
C.2. Usage Guide 144
C.2.1. Usage Guide for Generators 144
C.2.1.1. Simple generators 146
C.2.1.1.1. the lazy way 146
C.2.1.1.2. using a single seed value 146
C.2.1.1.3. using a vector of seed values 147
C.2.1.1.4. antithetic values 148
C.2.1.1.5. generator output 148
C.2.1.2. Split generators 149
C.2.1.3. Saving and Resetting State 151
C.2.2. Usage Guide for Distributions 152
C.2.2.1. Creating distributions 152
C.2.2.1.1. the lazy way: 152
C.2.2.1.2. Without default parameters, using a simple generator 153
C.2.2.1.3. Without default parameters, using a split generator 153
C.2.2.1.4. With default parameters, using a simple generator 154
C.2.2.1.5. With default parameters, using a split generator 154
C.2.2.1.6. You may reset the default parameters this way, as often as you like 154
C.2.2.1.7. You can obtain the current values of parameters 154
C.2.2.1.8. You can reset the variate counter and other state variables this way 155
C.2.2.1.9. Finally, we have the InternalState protocol methods 155
C.2.2.2. Saving And Restoring State 156
C.3. Advanced Usage Guide 156
C.3.1. Choosing a Generator 156
C.3.1.1. Choosing A Generator 156
C.3.1.2. Strategy For Using Random Generators 157
C.3.1.3. Generator Quality 158
C.3.1.4. More generator data 161
C.3.2. Default Generators for the Distributions 163

C.3.2.1. Random Library: Default Generators 163
C.3.2.2. Utility Generator And Distributions 164
C.3.3. Random Library Test Programs 164
C.4. Resources for random number generation 166
C.4.1. Generators 166
C.4.2. Distributions 166
C.4.3. Useful Web Sites 167
Bibliography 167
Bibliography 170
Index 172
Colophon 175

List of Tables

C-1. Random Library: Generator Statistical Tests....158
C-2. Random Library: Generator Data....161
C-3. Random Library: Default Generators....164

List of Figures

2-1. Agent-based modeling....16
2-2. Interface vs. Implementation....19
3-1. Objective C Basics....23
4-1. Nested hierarchy of Swarms....36
4-2. Swarm virtual computer....37
5-1. Line graphs (in this case, a time series)....38
5-2. Histograms....38
5-3. Rasters of discrete two-dimensional data....39
5-4. Example `ProbeMaps` for the **tutorial** `ModelSwarm` and `ObserverSwarm` 39
12-1. Combining two `VarProbe` and one `MessageProbe`s on a `ProbeDisplay`....88
B-1. Schematic of proto-object creation....140

List of Examples

3-1. Objective C class....24
3-2. C vs Objective C....27
3-3. Java class....27
12-1. Generating a *probeMap*....91
12-2. Non-verbose *probeMap* creation....93
12-3. Global setting precision in `HeatbugObserverSwarm.m`....94
12-4. Setting precision for individual probes in `HeatbugModelSwarm.m`:....95
14-1. Maps and keys....112
16-1. Using a standard *lispAppName* instance....130
16-2. Creating a Lisp parameter file with an alternate name....132

About this Guide

This Guide presents an overview of the Swarm simulation toolkit. It is intended to be used in conjunction with other materials, which include the sample programs and tutorials provided by the Swarm team and the *Swarm Documentation Set*. Since this is a user guide, it is intended to be less formal and not so encyclopaedic as the *Reference Guide to Swarm* (http://www.santafe.edu/projects/swarm/swarmdocs/refbook/refbook.html). When there is any doubt, the *Reference Guide* (and the source code itself) is the final, most appropriate, authority.

- **Part I.** An overview of Swarm and a brief primer on Swarm object-oriented programming using Objective C and Java.

At the time of writing only Part I has been written from a joint Objective C/Java perspective, subsequent Parts assume you are using the Objective C version of Swarm, a limitation we hope to rectify in future versions of this *Guide*

- **Part II.** A reprise on the Swarm tutorial package, explaining in-depth various non-obvious features of Swarm coding. As previously noted, the present this only covers the Objective C version
- **Part III.** Advanced Topics: as you might guess, not for the uninitiated, these are important topics you will need to know to become a competent in using the Swarm libraries.

The inspiration for this Guide was provided by Benedikt Stefansson <benedikt@post.com>, who prepared a series of lectures for the 1998 and 1999 SwarmFests. Benedikt generated a series of slides and illustrations and many of them have been adapted for this Guide. He has also provided help in the form of sample code and advice about many topics.

Conventions used in this document:

Note

Interesting fact(s), not necessarily of vital significance to the user.

Tip

A coding tip, a suggested convention to adopt or suggested usage.

Important

Important fact(s) you should know before proceeding to the next section.

Caution

A note of caution, generally regarding a changed usage, deprecated functionality or other compatibility issue.

Warning

Vital information that a user needs to be aware of before proceeding.

Part I. Basic Concepts

Chapter 1. Introduction

The Swarm project was started in 1994 by Chris Langton, then at Santa Fe Institute (http://www.santafe.edu) (SFI)in New Mexico. It is currently based at the non-for-profit organization, Swarm Development Group (http://www.swarm.org) also based in Santa Fe, New Mexico. The aim was to develop both a vocabulary and a set of standard computer tools for the development of multi-agent simulation models (so-called ABMs, short for Agent-Based Models). Armed with this framework, researchers are able to focus on the substance of the modeling task, avoiding some of the complicated details of computer coding.

The Swarm project has benefitted from the contributions of many programmers, including Roger Burkhart, Nelson Minar, Manor Askenazi, Glen Ropella, Sven Thommesen, Marcus Daniels, Alex Lancaster, Vladimir Jojic, and Irene Lee.

1.1. Basic Facts About Swarm

Swarm is a collection of software libraries which provide support for simulation programming. Among the most prominent features are the following.

- **Swarm Code is Object-Oriented.** The swarm libraries are written in a computer language called "Objective-C", a superset of the C language. Objective-C adds the ability to create software "classes" from which individual instances can be created. These instances are self-contained entities, and the terminology of object-oriented programming turns out to be very well suited to discussions of agent-based models.
- **Swarm Programs are Hierarchical.** Most swarm applications have a structure that roughly goes like this. First, a top level–often called the "observer swarm"–is created. That layer creates screen displays and it also creates the level below it, which is called the "model swarm". The model swarm in turn creates the individual agents, schedulestheir activities, collects information about them and relays that information when the observer swarm needs it. This terminology is not required by Swarm, but its use does facilitate it.
- **Swarm Provides Many Handy Tools.** As we shall see in later sections, the Swarm libraries provide a number of convenient pieces of code that will facilitate the design of an agent-based model. These tools facilitate the management of memory, the maintenance of lists, scheduling of actions, and many other chores.

Users build simulations by incorporating Swarm objects in their own programs. Users are encouraged to study a number of tutorial examples in order to make full use of the Swarm libraries and the strategy of modeling that inspires them.

1.2. Swarm is a Dynamic Platform

Swarm is *free software* (http://www.gnu.org/philosophy/free-sw.html) [1]. The current Swarm distribution is effectively [2] released under the GNU General Public License (GPL (http://www.gnu.org/copyleft/gpl.html)). The free software model of software development is particularly effective for a tool like Swarm, for both theoretical and practical reasons:

- **Complete Observability.** With full source available, if necessary, the modeller can always track the execution of the simulation right down to the operating system level. This is very important for reproducibility, and ultimately allows you to go about proving (in an abstract mathematical sense) a simulation's 'correctness'.
- **Developer Mind-Share.** More practically, Swarm is open source so that we can harness developer mind-share: more technically minded users can identify bugs, write patches, implement new features generally contribute to the evolution of Swarm. These are all identical to the reasons that the GNU/Linux operating system has grown so fast (and is so robust) [DiBona et. al. 1999]. As Swarm grows, more programmers, and technically curious modellers are becoming involved in the project.

The development work is being done by the Swarm Development Group (http://www.swarm.org), located in Santa Fe, New Mexico. (The Swarm project relocated from the SFI at the end of October 1999). Their results are periodically released on the Internet and users have access to the source code. The creators fully intended for users to take the code, experiment with it, and propose changes and enhancements. This open source strategy is designed to capture the contributions of a lively research community. When users make improvements in the libraries, they are encouraged to announce them to the community and make them available. As a result of the interaction of the community and the Swarm team, the Swarm libraries are constantly being revised.

To get an idea of how much things change, consider the brief history of the project. Swarm was originally intended for Unix operating systems that support the X Windows System. The first beta version of Swarm was released in 1995. In January 1997, version 1.0 was released to the public. It would run on Solaris and Linux operating systems. Quickly after that, minor releases followed that opened up Swarm to the DEC Alpha platform and other flavors of Unix. In April 1998, the reach of Swarm again broadened, as version 1.1 was released and, with the help of the Cygnus Win32 package, Swarm could be used on the Microsoft Windows 95/NT (and now 98) operating systems. In late 1999 the Swarm

1. sometimes referred to as "open source" source software, see the Open Source Definition (http://www.opensource.org/osd.html)

2. The core Swarm libraries are currently released under the LGPL (http://www.gnu.org/copyleft/lgpl.html), but the standard binary distributions generally include many GPLed support components, which effectively mean that Swarm is GPLed.

releases 2.0 and 2.0.1 introduced a Java layer for Swarm to enable Java programmers to access Swarm libraries and enabled the export of data through the HDF5 binary data format from NSCA.

Because Swarm does grow and change as a result of the complex interaction within a research community, its precise path for development is not predictable. Current priorities for the Swarm team at the SDG include the further generalization of Swarm to be useful on a broader array of platforms and in conjunction with additional computer languages. Prototype XML and Scheme layers for Swarm have been tested, for example.

1.3. Prerequisites for Success with Swarm.

Swarm was originally conceived as a set of standardized methods for the design of multi-agent simulation models. One need not be a highly accomplished computer program to user the Swarm libraries. In fact, as the installation process for Swarm becomes increasingly streamlined, it is quite easy for anyone with suitable hardware to test some of the sample applications. For people who have Windows 98/NT or Linux operating systems, compiled versions of the Swarm libraries are available and installation is quite painless

However, it is not easy to create new Swarm applications. Doing so requires the creation of a computer program. While one need not be an expert programmer, one must have a rudimentary understanding of vital computing concepts. The required knowledge will vary with the sort of model that one is intending to create, of course, but, *at the bare minumum*, users must have:

- a basic understanding of computer programming
- and, at the time of writing, either of the two object-oriented programming languages, Java or Objective C [3]

Java is a straightforward language to learn, and has the advantage of being a mainstream, well-supported language in terms of both tools and documentation. Objective-C is, well, truly elegant and fun to use and people who know C say it is fairly easy to learn (C is also a highly useful language and it is relatively easy to learn).

People who have not done computer programming will thus need to do some background preparation before they try to make a serious effort at building a Swarm model.

If you choose to implement your models in Objective C, we suggest that the first step is to find one of the many elementary guides to computing with C, such as *The C Programming Language*, [Kernighan &

3. in the Objective C case, an understanding of the C computer language, is also helpful, since Objective C is a superset of the C language

Ritchie, 1988]. Written by the authors of C, Brian Kernighan and Dennis Ritchie, it is a truly readable and informative manual that all users ought to investigate.

If you choose to implement your models in Java, there are literally thousands of introductory programming-in-Java resources on the market, both in paper and electronic form (see Section A.1 for some starting points).

A manual with examples and exercises is vital. These will teach the basics about writing code and compiling it into programs.

The Objective-C language is best learned from the online book *Object Oriented Programming and the Objective C Language* [NeXT, 1993].

Chapter 2. Programming and Simulation

Swarm is designed to help researchers build models in which low-level actors interact (often called "complex systems"). The researcher has to give content to "agents," possibly by thinking of them as honey bees, investors, trees, or (the ubiquitous) "bugs." One research goal is to discern overall patterns that emerge from these detailed behaviors at the individual level.

Figure 2-1. Agent-based modeling



Object oriented programming is ideally suited to represent models of this sort. As we shall see, the objects are self-contained. Objects may be designed to convey information (answer questions) from other objects and also they can retain, categorize, and summarize information.

2.1. What is an Object?

A careful study of either of the object-oriented programming languages (Java or Objective-C) is required before any significant progress can be made in building a Swarm model. The material presented here is intended as a summary or reminder of such a study, rather than a substitute.

An object consists of two kinds of information

- **Variables.** The list of variables summarizes the "state" of the agent–its age, wealth, its ability, and so forth. These variables may be of any type that is allowed in C, such as integer (`int`), floating-point number (`float`), an array, a pointer, and so forth. These variables might also be of type `id`, which means they might also be instances of classes, and;
- **Methods.** Methods determine what the object can do. Typically, there will be methods that receive information from the "outside world", methods that send messages to the outside, and methods that process information.

Variables and methods are given meaningful names, so code is easier to read. The custom is to run words together to make meaningful tags, such as **`goToStore`** or **`goHome`**.

Objects are created through a process called "instantiation." Put tersely, code is written in "classes" and then objects are created as instances of their classes. The varibles that an instance, or object, keeps inside itself are called "instance variables". The information contained inside instance variables is available to all methods inside that object. If one of the methods in an object needs to have "private" information that is not available to other methods in the object, then "method variables" can be created to hold that information.

In both Objective-C and Java, the term *message* is often used to refer to an instruction that tells an object to carry out one of its methods. (For readers more familiar to C++, the term *member function*, refers to the same thing as the term method). Here is an example of a message that tells an object known as *`bobDole`* to execute its method **`runForPresident`**.

Objective C example	Java example
`[bobDole runForPresident];`	`bobDole.runForPresident();`

In Objective C, some methods have parameters that specify details and they are added with colons (`:`) after the name of the method to be executed. In Java, the entire method name is listed *before* the parameters are given [1]. For example, if the method **`runForPresident`** required additional parameters, such as the year and the name of the runningmate, then the message might look like so:

Objective C example	Java example

1. In our Java example we use a dollar sign (`$`) inline between the parts of the method that are separated in the Objective C case. This is purely a convention introduced to stay as close to conventions adopted by the Java Swarm libraries. This is in no way enforced by the Java language itself.

Objective C example	Java example
`[bobDole runForPresident:2000 with: RossPerot];`	`bobDole.runForPresident$with (2000, RossPerot);`

We will have plenty of additional examples in the rest of the Guide.

2.2. The Variety of Objects

In a Swarm model, there can be many types of agents (see Figure 2-1) Obviously, if a model is going to describe honey bees, it has to have honey bee agents. It will also have objects that represent other actors in the model, and not all other actors are animate. There might be other insects and bears, but there will also be objects that represent the environment (trees, rainstorms, etc). The model will typically also have objects that facilitate the modeling process and collect information about the simulation and relay it to the researcher.

2.3. The Advantages of Object Oriented Programming

Object oriented programming (OOP)is well suited to describe autonomous agents,so it should have appeal to scientists and modelers on that basis alone. However, that is not the end of the subject. OOP it has virtues that are equally important to computer programmers. OOP, as it is found in Objective-C, is not exactly the same as OOP in C++ or Java, but these languages have some significant features in common. The features we emphasize here are encapsulation and inheritance.

2.3.1. Encapsulation

> The values of the variables inside an object are private, unless methods are written to pass that information outside of the object.

This has both substantive and practical implications. The substantive importance is that the representation of an individual actor now presumes that the actor is a self-contained entity and that other actors do not automatically have access to all information inside that actor. Like humans, objects have to take effort to convey information to each other about their internal states. The practical advantages of encapsulation, however, are just as important. Computer projects can be broken down into separable components (code for the classes) and when the code is finished, the details of what goes on inside each object may not be important to the programmer. For example, if an object *`groceryStore`* can respond to an message **`takeMoney`**, and it gets the job done, we might not care how it does it.

Figure 2-2. Interface vs. Implementation



This is commonly referred to as the separation of "interface" from "implementation." While the interface declares what methods the object can execute, the implementation may remain hidden (see Figure 2-2), the user only has to be familiar with the interface of an object, not it's implementation

2.3.2. Inheritance

> Each subclass inherits all variables and methods of its superclass.

Inheritance works because code for each class designates that class as a subclass of a superclass. For example, in the GNU Objective-C compiler used in the Swarm project, there is a most basic class, "object". From the object class, the Swarm libraries create subclasses, and subclasses are created from them, and so forth until the programmer in a swarm project wants to create a new class of actors that is subclassed from `SwarmObject`. If the programmer needs to create several varieties of that class, there is no need to totally rewrite each one. Subclasses can be created that have as a base all variables and methods of the class but then new methods and variables can be added as well.

When a method, say **`takeMoney`**, exists in a class `Store`, and then a subclass is created, say `GroceryStore`, then all objects instantiated from the subclass will respond to **`takeMoney`**. If the programmer wants to rewrite the **`takeMoney`** method for `GroceryStore`s, however, then the method can

be revised inside the code for the subclass and then all instances of the `GroceryStore` class will respond to **`takeMoney`** in that specialized way. The method inside the `GroceryStore` subclass will override the super-class's definition of the method.

2.4. Discrete Event Simulation

A Swarm simulation proceeds in discrete time steps. Objects are created and then interact according to a scheduling mechanism. As the simulation proceeds, the agents update their instance variables and they may be asked to report their state to the observer swarm layer of the simulation.

The modeling process in Swarm, then, is quite different from simulation modeling in a non-object oriented language, such as Fortran or Pascal. These so-called "procedural languages" do not allow the modeler to take advantage of reusable classes through inheritance or the preservation of data allowed by encapsulation. Here's an example of a simulation in a procedural language:

Procedural language pseudo-code

1. **get parameters**
2. **initialize**[2]
3. **for 1 to timesteps do:**
    a. **for 1 to num_agents do:**
        i. **agent-i-do-something** [3]
    b. **show state** [4]
4. **quit**

2. Generally sets up data structures and support for output.

3. Here must provide data structure to save agent's state and implement behavior

4. Implementation of output often left to the programmer

Chapter 3. Nuts and Bolts of Object-Oriented Programming

3.1. Multilanguage support and Swarm

Swarm is not a single application that is 'turned on'. Swarm is a set of libraries that you can pick and choose features from. In order to use the Swarm libraries, it is necessary to create or use code that calls Swarm features.

3.1.1. Objective C

Until recently, there was one way to use Swarm features: write and compile a program in Objective C. This is a flexible and way to write a model using Swarm. Objective C models tend to have good performance because they are compiled by a native code optimizing compiler, namely **GCC**.

Objective C was created by Brad Cox [NeXT, 1993]. The aim was to create an elegant, object-oriented extension of C in the style of the Smalltalk language [Goldberg & Robson, 1989]. Objective C was used most intensively in the design of the NeXT computer operating system, which is now owned by Apple and is basis of Apple's runtime environment WebObjects.

3.1.2. Java

Since Swarm 2.0, modellers can use Java. For new users of Swarm, writing models in Java is considerably harder to get wrong. Java is also a more attractive languages for new users to learn since it is a popular language that has benefits outside of Swarm modelling.

Java was created by Sun Microsystems, initially to provide a platform-independent layer or interface for embedded devices (such as set-top boxes for digital television) and was originally known as *Oak*. With the advent and growth of the world wide web from 1992 onwards, Oak was renamed *Java* and redirected at the market created by the web. "Write once, run anywhere" was the motto of the original Java developers, the idea being to create an abstraction layer between the programmer and the underlying chip architecture (ix86, Sparc, Alpha) known as a *virtual machine* (or interpreter)[1]

1. In theory all programmers needed to do was to write so-called "pure Java" code that targeted the virtual machine, whilst the virtual machine itself only needed to ported once to each new architecture or chip, by the maintainers of the language itself (rather than the applications programmer). With certain caveats, this has been largely realized, and Java is now a robust platform that is used in both web client GUI programming (applets) as well as server applications (servlets). Use of Java does come at a cost, the extra step of translating the virtual machine instructions into the native machine instructions at run-time does have a performance penalty at run-time, but with the advent of so-called *native compilers* which do this translation at

The purpose of the Java layer of Swarm (actually it is a system that is potentially extensible to other languages such as Scheme or C++) is to mirror the *protocols* of the Swarm libraries as Java *interfaces*.

For more details on the ongoing work of integrating Swarm with other languages and simulation technologies such as XML and Scheme, see the paper *Integrating Simulation Technologies With Swarm* [Daniels, 1999].

3.1.3. Why is Swarm Written in Objective C?

Since Objective C is not currently a mainstream programming language, it is natural to ask why the Swarm project chose Objective C. There are a number of reasons:

- **Objective C is easier to learn.** Objective C takes the familiar C language and adds a few simple elements. Objective C does not allow overloading or multiple inheritance of classes (although the use of protocols enables this, to an extent)
- **Objective C allows run-time binding.** In contrast to other languages which check the match between the receiver of a command and its ability to carry out the command when a program is compiled, Objective C leaves that matching exercise until the program is running. This means, for example, that one can have a program that builds a list of objects and then sends a message to each one. In Objective C, the compiler won't worry about which type of object is in the list. The advantage, conceptually, is that one can put commands in their code without knowing the precise identity of the receiver, so code can be written to allow an environment and set of objects to change and evolve. The disadvantage, as critics of run-time binding will quickly point out, is that programs crash when an object recieves a message and it does not have the method that it is being told to execute. The organization of Swarm into protocols reduces the risk of these crashes, however, because the compiler does check and issue a warning if a method is not implemented in a class that advertises a certain protocol.

3.2. Objective C Basics

3.2.1. The `id` Variable Type

compile-time (rather than at run-time), many applications can, in principle, run much faster than they currently do.

The variable type that is added by Objective C is `id`. It is the default type for objects in Objective C. Think of this as a special variable type (which is actually a pointer to a special data structure - namely the object)

All objects can refer to themselves by using the label *`self`*. This is necessary if, in the code that defines the object, the programmer wants to make the object execute one of its methods. For example, suppose an object has a method called **`updateRecords`**. If a command

```
[self updateRecords];
```

is received, then the **`updateRecords`** command will be executed, presumably to cause the updating of instance variables.

All objects can refer to superclass by the name *`super`*. For example:

```
[super updateRecords]
```

3.2.2. Interface File: Declaration of a Class

If you look in a directory where some Objective C Swarm code resides, you will see files in pairs, such as `ObserverSwarm.h` and `ObserverSwarm.m`, ModelSwarm.h and `ModelSwarm.m`, and so forth. The "h" files are the interface files (commonly called *header files*), while the "m" files are the *implementation files*

Figure 3-1. Objective C Basics



As illustrated in Figure 3-1, the interface declares the name of the class and the name of its superclass. Then it gives a list of variable types and names enclosed by braces ({}), and then the names of the methods that the class can implement are listed. The variables defined in this list can be used by any of the methods defined for the class. (These are often called "ivars", short for instance variables.)

Example 3-1. Objective C class

```
(1)@interface Bug(2) : SwarmObject(3)
{
  int xPos, yPos;
  int worldXSize, worldYSize;(4)
  id foodSpace;
}
- setX: (int) x Y: (int) y;(5)
- step;(6)
- (return_type)look: (direction_type) d;(7)

@end
```

(1) Declarations of instance variables and methods

(2) Sub class

(3) Super class

(4) Instance Variables

(5) declares method called **`set`** that takes two arguments

(6) declares a method called **`step`**.

(7) declares a method called **`look`** that takes one argument of type `direction_type` and returns an argument of type `return_type`.

3.2.3. Implementation File: Defining a Class

Each implementation file–the `.m` that parallels the `.h` – must import its header file. For the header file described above, called `Bug.h`, for example, the implementation looks like:

```
#import "Bug.h"
@implementation  Bug
- setX: (int) x Y: (int) y
{
 xPos = x;
 yPos = y;
 return self;
}
- step
{
 // body
 return self;
}

- (return_type)look: (direction_type)d
{
  return_type returnval;
  // body of method
  return returnval;
}
```

This example shows a number of important features. First, note that the method **`look`** specifies a return type, (`return_type`). In this example, *`return_type`* would have to be replaced by a variable type, such as `int`, `float`, or whatever, and *`returnval`* would have to be a variable of that type. When that method is called, the receiving code must be able to accept a return of that type. In contrast, the method **`step`**

does not specify a return type. That means the default type, `id`, is returned. The code that calls this method must be consistent with that return type.

The `return self` command is used for two types of situations. Suppose the method is not intended to create any output, but rather it changes some instance variables. For example, suppose there is some program that creates an instance of `Bug` called *`aBug`*. Then that object is sent this message:

```
[aBug step]
```

In such a case, the code that calls that method does not expect anything back from it (except itself). Rather than fuss with `void` as the return type, as one might in C, one can simply return *`self`*.

In another case, one might actually intend to return the object to a list or another object. In such a case, return self will also be appropriate. If one is making a list of collected bugs, for example, then the usage of `return self` in that method will give back *`aBug`* `id` to the calling program. To be perfectly concrete about it, suppose the calling code has a list called **`collectedBugs`**. Then using the **`addLast`** notation from the Swarm collections library, the command to add *`aBug`* to the list after being collected might look like this:

```
[collectedBugs addLast: [aBug look:
aDirection]];
```

3.2.4. C Functions vs. Objective C Methods

For readers who are already familiar with C, perhaps a comparison of C functions against Objective C methods is in order. Since Objective C is a superset of C, an Objective C method can include any valid C commands. A method can return any type that a C function can return, and in addition it can an id (which, strictly speaking, is a pointer to an object).

In the abstract, an Objective C method has this structure:

```
- (type)name: (type)arg1 argName2: (type)arg2
{
 (body)
 return returnval;
}
```

In comparison, a C function would look like this:

```
(type)name((type) arg1,(type) arg2))
{
 (body)
 return returnval;
}
```

The code in body of an Objective C method can be exactly the same as in C. The two languages are compared side-by-side in the following example, which describes how a function **`rand_move()`** might compare to a method **`rand_move:`**. Of course, each of these assumes there are other functions and variables that can be accessed, but the contrast in style should be informative.

Example 3-2. C vs Objective C

C	Objective C
`void rand_move(int i) { int tmp_loc; do{ tmp_loc=get_rand_loc(); } while(val[tmp_loc]!=0); val[location[i]]=0; val[tmp_loc]=i; }`	`- rand_move: p { id loc; do{ loc=[self getRandLoc]; } while([world at: loc]!=nil); [p moveTo: loc]; return self; }`

3.3. Java Basics

One of the most obvious and immediate differences between Objective C (and incidentally C++) and Java, is that Java does not partion classes into "declarations" (header files) and "implementations" (implementation files). All information for any Java class is contained in a single `.java` file.

Perhaps the best way to illustrate this is to consider the Java equivalent of the previous Objective C Example 3-1.

Example 3-3. Java class

```
(1)public class Bug(2) extends SwarmObject(3)
{
  int xPos, yPos;
  int worldXSize, worldYSize;(4)
  FoodSpace foodSpace;

 public Object setX$Y (int x, int y)(5)
  {
    xPos = x;
    yPos = y;
    return this;
  }
 public Object step()(6)
  {
    // body of step() code
```

```
    return this;
  }
 public return_type look(direction_type d)(7)
  {
    return_type returnval;
    // body of look() code
    return returnval;
  }
}
```

(1) Complete class defintion

(2) Sub class

(3) Super class

(4) Instance Variables

(5) declares method called **`set$Y()`** that takes two arguments

(6) declares a method called **`step()`** takes no arguments.

(7) declares a method called **`look()`** that takes one argument of type `direction_type` and returns an argument of type `return_type`.

One important distinction to notice is that Java does not have a notion of an `id` or "generic" data type. All variables must be assigned a type, in the above example the *`foodSpace`* instance variable is declared as being of type `FoodSpace`. This is because Java is a *strongly typed* language. The compiler checks all types of all variables to ensure all receiver objects respond to the messages that are sent to them by the programmer. Most of the rest of the other differences between the Objective C and Java examples given, lie almost purely in deviations of syntax. Here are a few obvious ones (this list is by no means exhaustive and the reader is encouraged to consult their Java or Objective C reference manual for all the detailed syntax):

- In Objective C, method names and the parameters are interspersed, whilst in Java, the entire method name is given before the parameters.
- In Java *`self`* is referred to as *`this`* (*`super`* retains its meaning and syntax in both languages).

3.4. Giving Life to Classes: Instantiation

After the code is written to implement the class (with `.h` and `.m` files for Objective C and `.java` in the Java case), there is still work to be done. Instances of the class must be created. The creation of instances

of a class is one of the specialized features of Swarm. Since the instantiation process can be sometimes different from the that described in the Objective C and Java literature, it is worth some special attention.

The creation of the substantively important objects is often handled in the model swarm. This process uses the specialized memory management and object creation code in the Swarm library.

3.4.1. Instantiation: Objective C Style

The objects that represent the actors in a simulation–the substantively important entities–are usually subclassed from the `SwarmObject` class. The "inheritance hierarchy" that leads to the class `SwarmObject` passes through classes that allow the creation and deletion of objects from a simulation. Objects are often created by a pair of "bookend" commands, **`createBegin`** and **`createEnd`**. This is not part of the Objective C syntax. Rather, it is unique to Swarm.

Suppose the `Bug.h` and `Bug.m` files from previous exist, and one wants to create an instance of that class. In a file `ModelSwarm.m`, one would typically have a method called **`buildObjects`**, which is usually a method that houses all object creation. For example:

```
// Excerpt from ModelSwarm.m that creates a Bug instance
#import "Bug.h"
// {other imports and code that defines schedules, etc}
- buildObjects
{
    id  aBug;
    bug = [Bug createBegin: self];
    // commands that set permanent features of the agent can apppear here
    bug = [Bug createEnd];
}
```

The class's "factory object", `Bug`, is told to create an object in a memory zone that is provided by `ModelSwarm` (`ModelSwarm` is the *`self`*.). Then the object *`aBug`* is instructed to finish the creation process, after optional commands are added to define the features of the object (typically, to set permanent structural aspects of the class). Many of these subtleties are explained in depth in later sections (see also Appendix B).

Object instances need not be created by the **`createBegin`**/**`createEnd`** pair. Objects can often be created by a simple create command [2].

```
aBug = [Bug create: self];
```

In code written for older versions of Swarm, one will often see a slightly different syntax in `ModelSwarm.m`:

2. For example, the Swarm collections library includes a class called `List`, which is most often created this way.

```
aBug = [Bug create: [self getZone]];
```

In Objective C, this usage is still valid, although it is deprecated. Since now the objects of type `Swarm`, like the model swarm itself, are memory zones, there is no need to get a zone in which to put the bug. Rather, the bug can be put in the zone that is provided by the model swarm itself.

3.4.2. Instantiation: Java Style

For most stock objects created in application Java code (including user-created Java classes), the entire **`createBegin/createEnd`** apparatus can be dispensed with. Java uses the term *constructor* for the method that creates an instance of a class. The Java interface to the Swarm libraries have "convenience" constructors which essentially bracket the entire set of create-time messages in a single call to the constructor (or call the constructor with no arguments as in the present case). The simplest method to create a Java `Bug` object is to invoke the following:

```
aBug = Bug (this.getZone());
```

This is equivalent to the final Objective C example given in the last section. In summary here is the comparison:

Objective C example	Java example
`aBug = [Bug create: [self getZone]];`	`aBug = Bug (this.getZone());`

Note that the explicit **`create:`** method in the Objective C case, is made implicit in the Java case.

It is still possible to use the **`create`** and **`createBegin/createEnd`** apparatus in Java, but due to Java's strongly-typed nature, it can require considerably more coding overhead than in Objective C, and will be left to later version of the Guide.

3.5. A Brief Clarification: Classes and Protocols in Objective C

There is one additional complication that readers should be aware of. Objective C allows the creation of entities called protocols. A protocol, as readers will recall from their study of Objective C, is a list of methods that an object is able to execute. Swarm is structured by protocols, which means that there are lists of methods assigned to various names and classes inside the library "adopt" those protocols and then implement the methods listed in the protocols. Hence, in the Swarm Reference materials present the libraries as a collection of classes, each of which adheres to a given set of protocols.

To the Swarm user, the distinction between class and protocol is not vital most of the time. The most important Swarm protocols, such as the type `Swarm` (from `objectbase/Swarm.h`) or `SwarmObject` (from `objectbase/SwarmObject.h`), can be used as if they were classes. In the Swarm Reference Guide, there is a list of all protocols. The protocols that adopt the `CREATABLE` protcol are the ones that users can use as if they were factory objects. For example, the `EZGraph` protocol adopts the CREATABLE protocol, so when the user needs to create an instance, so the observer swarm file can use the EZGraph to create graphs.

Almost all of the Swarm protocols adopt the CREATABLE protocol, so they can be used as if they were classes from which users subclass to make model swarms or individual agents. It should not matter to the user that these are abstract defined types that have adopted protocols (taken on the obligation to implement methods listed in protocols). The class `SwarmObject`, for example, adopts protocols `Create` and `Drop` as well as CREATABLE. This means that the user can act as if there is a class called `SwarmObject`, and that the SwarmObject will be able to respond to class methods like **`createBegin`**, and that instances created by SwarmObject will be able to respond to **`createEnd`**, **`drop`**, or any other method that is listed in a protocol listed by SwarmObject.

One of the principal advantages of protocol usage is that there will be compile-time warnings if the user's code tries to send a "bad message" to an object. If a message tells an object to **`goOutside`**, and none of the protocols adopted by that agent have a method called **`goOutside`**, then the compiler will warn the user about it. In a crude way, adopting a protocol is like advertising that a class can do certain things, and the compiler enforces a 'truth in advertising' policy. If the compiler flags include -WERROR, causing all warnings to be treated as errors, then these warnings will stop the compilation.

The fact that many of the important components of the Swarm library are organized as protocols can, however, be important in some notation. Early versions of Swarm had less emphasis on protocols than the current version. As a result of the introduction of protocols, usage conventions have changed. In Swarm, there is a class `List` that can be used to create collections. In the "old days" of Swarm, one would create a statically typed object of class `List`, as this code indicates:

```
List * listOfPuppies;
listOfPuppies=[List create: [self getZone]];
```

Swarm no longer allows users to statically allocate objects in this way. This code will make the compiler crash, because there is no class inside Swarm called List, there is only a protocol. The compiler will fail, and the user will get a vague warning about a parse error in the vicinity of the List usage.

We know from the Swarm Reference Guide that the `List` protocol advertises that it adopts the `CREATABLE` protocol, so the mistake is not in the usage of List to create the listOfPuppies. Rather, the mistake is in the declaration of the listOfPuppies itself. If one needs to define a variable *`listOfPuppies`* that has the properties of a `List` class item, the recommended approach is to create a variable of type `id` and indicate the protocols adopted by that object in brackets:

```
id < List >  listOfPuppies;
listOfPuppies=[List create: [self getZone]];
```

It is also legal to define listOfPuppies as a generic object, as in

```
id listOfPuppies;
listOfPuppies=[List create: [self getZone]];
```

This usage is legal, and the program should compile without difficulty. The only shortcoming is that the user will not be warned if the listOfPuppies object is sent any inappropriate messages within the program. When these inappropriate messages are sent during the run, then the program will crash, possibly with a message that the object listOfPuppies does not respond to the message it was sent.

Since almost all of the important pieces of functionality in the Swarm library are now written in the protocol format and are CREATABLE, these details may be important. However, these details do not significantly change the way applications are designed. Swarm entities can still be treated as classes.

Chapter 4. The notion of a Swarm

As explained in an earlier section, Swarm is designed for hierarchical creation of computer objects. The observer swarm object is created first, and it creates a user interface and it also instantiates the model swarm, and the model swarm then creates levels below and schedules their activities.

One of the original intentions of the Swarm project was to give users the ability to create high quality code with a minimum of fuss. The Swarm library creates a sequence of classes that accumulate and refine the ability to create simulation objects, manage memory for them, and schedule their activities.

4.1. Primary and Auxiliary Agents

Terminology can cause confusion because computer programmers may use the term "agent" in a way that befuddles scientists. To the scientist, the term agent refers to a theoretically important entity that is modeled by a simulation. To a programmer, the term agent is usually broader, something like object. As a result, there is sometimes slippage in a discussion of "agent-based modeling" because an understanding of the term agent is not shared.

We intend to finesse this (big surprise!) by creating terminology for two kinds of agents. This separation of agents into primary and auxiliary groups is created solely for discussion in this manual. The idea is that primary agents are the ones that the research sets out to model in the first place. They are described in a theory, they have substantive importance. Usually in this sense we have representations of important "actors" and one or more objects to represent the world in which they interact.

To the surprise of most new users, it is often also necessary to create auxiliary agents that facilitate the work of the primary agents. For example, in a model of majority rule voting, one can have primary agents like voters and candidates. There may be a need for an auxiliary class called `Counter`, a class that can spawn objects that can be used to tally the votes that are cast.

In most cases, when we talk about multi-agent systems, we are referring to the primary agents.

4.2. The (Swarm) OOP way

Swarm models follow a common syntax that helps users to understand the way their parts interact. The observer swarm and the model swarm are typically designed in a similar way. Methods that will appear in many classes, for example, include:

Objective C example	Java example
`+ createBegin; - createEnd; - buildObjects; - buildActions; - activateIn;`	`createBegin (); createEnd () buildObjects (); buildActions (); activateIn ();`

There are also methods that allow the input and output of information from the object. By custom, these

are usually prefaced by the words **get** and **set**. For example:

Objective C example	Java example
`-setParameterValue: (int) value; -(int) getParameterValue;`	`Object setParameterValue (int value); int getParameterValue ();`

These methods can be written to so that **setParameterValue** causes an object to set some internal parameter equal to a value, and **getParameterValue** will cause the agent to report back the value.

In addition,there will be methods that carry out the specialized actions dictated by the substance of the research problem.

The model swarm object is usually subclassed from Swarm and it is the primary object that is responsible for telling subclasses to build their agents. The model swarm also give those agents a place in memory, and schedules their activities.

4.3. Managing Memory in Swarms

The allocation and deallocation of memory is a necessary feature in any simulation project. Allocating and deallocating memory is one of the most troublesome elements of designing software and Swarm is well equipt to deal with that problem. Swarm provides libraries for this purpose which make the process transparent to user.

In Swarm, objects are created and dropped using a notion of memory zones, and the "dirty work" of allocating memory is handled inside the libraries. In the next sections, we discuss the way objects are created and given a place in memory. When those objects are no longer needed, the program can send that object the **drop** message, which removes it from memory.

4.4. What goes on in the `buildObjects` method?

If the reader inspects just a few of the sample Swarm programs, the importance of the building objects should become apparent. Objects are named and memory is set aside for them in this stage. In the **buildObjects** method, one typically finds commands that not only create the objects being used in the current class, but there will also be a command which instructs the next-lower level of agent to create its objects.

Consider the rich example provided by the code from the **Arborgames** model. In the **buildObjects** method of the observer swarm, one finds a large number of commands that create graphical display objects (objects subclassed from the graph library). One also finds commands that create the simulation control panel, which will appear on the screen and offer the user the ability to start and stop the simulation.

It is vital to note also that the **`buildObjects`** method in the observer swarm file triggers the creation of the next lower level of agents. It creates a memory zone and creates a model swarm in that memory zone. Using the current style, the code would look like so:

Objective C example	Java example
`forestModelSwarm = [ForestModelSwarm create: self]; [forestModelSwarm buildObjects];`	`forestModelSwarm = ForestModelSwarm (this.getZone()); forestModelSwarm.buildObjects ();`

In the Objective C case only, users may find older versions of this code which accomplish the same purpose, but are slightly more verbose and do not take into account the fact that the observer swarm object is itself a memory zone.

```
modelZone = [Zone create: [self getZone]];
forestModelSwarm = [ForestModelSwarm create: modelZone];
[forestModelSwarm buildObjects];
```

Note the importance of the last line in either of these excerpts. The first line of the code creates the model swarm object (in this case, it is called *`forestModelSwarm`*), but the last line tells that object to create its own objects by telling the *`forestModelSwarm`* to execute its own **`buildObjects`** method. To find out what that implies, one must go look in the implementation file (or `.java` file in the Java case) for the `ForestModelSwarm` to see what objects it creates.

4.5. What goes on in the `buildActions` method?

In the standard case, the **`buildActions`** method has two important components. It creates objects of these two classes.

- `ActionGroup`: an ordered set of "simultaneous" events and
- `Schedule`: controls how often the elements in the action group are executed

In the **`buildActions`** methods of the Arborgames model, there are plenty of interesting examples. In the observer swarm, for example, there are commands that schedule the updating of the graphical display and also there are commands that instruct the lower level classes to execute their own **`buildActions`** methods.

In the `ModelSwarm`'s **`buildActions`** method, one typically finds the heart of the substantive action of the simulation. Commands tell agents, or lists of agents, that they should carry out their methods. These commands are placed into instances of the `ActionGroup` class, which means that they will all be repeated whenever the group is repeated. The repetition is controlled by commands that create schedules and indicate how often those schedules will be repeated.

4.6. Merging Schedules in Swarms

As mentioned above, there can be **`buildActions`** methods in many different classes. Since each one can create action groups and schedules, it is important that all of these activities are coordinated in a logical way. One of the strengths of the Swarm toolkit is that it maintains a coherent, master schedule. The schedules of each sub Swarm are merged into the schedule of next higher level. Finally all schedules are merged in the top level Swarm. This synchronization is managed by the Swarm Activity library when the **`activateIn:`** method is called in each successive element of the hierarchy.

This multi-level integration of swarm schedules means that the model can indeed be thought of as a nested hierarchy of models.

Figure 4-1. Nested hierarchy of Swarms



A Swarm as a Virtual Computer

Figure 4-2. Swarm virtual computer



At an even more abstract level, the Swarm libraries can be thought of as a layer on top of the operating system's kernel. This notion is especially relevant when the user can pause a simulation and individually interact with agents, reviewing and changing their internal values.

Chapter 5. The Graphical User Interface

5.1. Elements of the Swarm GUI

Swarm provides a number of classes and protocols which generate a graphical user interface (GUI) to the user running a Swarm simulation, including:

Figure 5-1. Line graphs (in this case, a time series)



Figure 5-2. Histograms



Figure 5-3. Rasters of discrete two-dimensional data



Figure 5-4. Example `ProbeMaps` for the tutorial `ModelSwarm` and `ObserverSwarm`



All except the last (probes) are fairly self-explanatory and will be dealt with in subsequent chapters. This section describes how probes appear to the user running a Swarm simulation, and how the user can manipulate them. Probes also serve purposes *other* than assisting graphical widgets that the user can manipulate. However, in this section we will focus only on their role in the context of the GUI of a running simulation. The construction of the probes using the Swarm libraries is also left to a subsequent chapter.

5.2. GUI Probe Displays

Graphical *probes* allow a user to view a snapshot of any object in a Swarm simulation in a graphical form. There are two distinct kinds of displays the user might see:

- **DefaultProbeMaps.** If an object to be probed is specified *without* any particular `ProbeMap` being specified, then the `ProbeDisplay` generated will provide a window of class `DefaultProbeDisplay`, which displays all the variables resident in that class structure.

Figure 5-5. Default ProbeMap (also showing the superclass)



- **CustomProbeMaps.** If a `ProbeMap` *is* specified then the `ProbeDisplay` follows exactly the specification as represented by the contents of a `ProbeMap`. When used in this manner, `ProbeDisplays` can generate tailored interfaces to objects (so for example, we have purposefully hidden certain instance variables in the `MousetrapModelSwarm` class, and have shown only one of the methods which the class understands).

Figure 5-6. Custom ProbeMap



5.3. Using the GUI Probe Display

Common to both the standard `ProbeDisplay` and the `CompleteProbeDisplay`:

- The different fields in the `ProbeDisplay` can be updated by typing in new values and pressing **Return**. However, certain fields (containing pointers or `id`s, for example) cannot be modified and will generate a beep if such a modification is attempted.
- If an instance variable/argument slot is defined to hold an object, then that object can be drag&dropped into another variable/argument slot by clicking on it with the `first mouse button` (a small rectangle with the name of the object will appear - simply drag it to another object-typed variable/argument slot and release the mouse button).
- Also, if an instance variable/argument slot is defined to hold an object, then that object can be inspected by clicking the entry for that variable/argument slot with the `third mouse button` (a `ProbeDisplay` for that object will be generated).

Available Only on the Customized `ProbeDisplay`:

- Note that the sunken label at the top of the `ProbeDisplay` is also active. By clicking on it with the first mouse button you get a drag&drop'able representation of *`self`*. By clicking on it with the third mouse button you get a `CompleteProbeDisplay` to *`self`*.

Available only on the `CompleteProbeDisplay`:

- The green superclass button can be used to display the succesive superclasses of the object being probed.
- The red hide button can be used to hide classes which are irrelevant thus reducing clutter.
- The hide button on the lowest class in the hierarchy has a special meaning since clicking on it dismisses the entire `ProbeDisplay`.

Part II. Swarm Applications: Examples and Illustrations

Chapter 6. The Swarm Tutorial: Reprise

Most Swarm users share terminology and perspective that allows them to communicate with each other about modeling projects. These shared elements are first introduced to most users in the Swarm Tutorial, a series of exercises prepared by Christopher Langton. The Tutorial exercises are distributed on the SDG web site in the **swarmapps** package.

Do Your Homework!

There is no way to get anywhere with Swarm unless you are willing to get your hands dirty. The **Swarmapps** package provides some examples of swarm programs that deserve study. That package also provides the bug tutorial, a series of exercises that all Swarm users must read, edit, compile, study, test, explore, and investigate.

If you are new to Swarm, and don't know much about programming in general, and possibly less about Objective-C in particular, the tutorial series is a perfect place to start. Even if you are an expert programmer, a study of the tutorial is the right place to start. Many of key terms in Swarm model building are introduced in the tutorial and there is simply no substitute for a careful analysis of the material.

Java Stops Here!

From hereon in, the *Guide* will only refer to examples in Objective C. The *Guide* is in the process of being updated to include Java examples of the basic Swarm concepts covered in the following chapters. That said, although many of the concepts described are described in Objective C terms, most of the concepts carry over intact into the Java context, and (mostly!) only differ in fairly trivial syntactical ways, so it possible that Java users can benefit from the following sections

6.1. Tutorial Progression

The tutorial gameplan is as follows: Begin with a program written in C that is little more than a basic "hello world" program about a "bug" creature that wanders. Through a series of steps which first introduce Objective-C and then the Swarm hierarchical modeling approach, one can gain a good grounding in Swarm modeling.

The tutorial outline is as follows:

1. **simpleCBug.** Simple C code about a bug

2. **simpleObjCBug.** Bug is now Objective-C class
3. **simpleObjCBug2.** Adds FoodSpace object
4. **simpleSwarmBug.** Introduces the `ModelSwarm` as the central organizing element. From the class `Swarm` in the Swarm library, this code creates subclass `ModelSwarm`, and the instance of `ModelSwarm` is created and called *`modelSwarm`* (in `main.m`). In the class `ModelSwarm`, one finds an implementation of the `Schedule` class, the workhorse that keeps the Swarm train moving on time.
5. **simpleSwarmBug2.** Introduces the *`bugList`*, an instance of the `List` class, and illustrates some ways in which simulations with many agents can be organized.
6. **simpleSwarmBug3.** Introduces the Swarm class `ObjectLoader` that the can grab data from a file and read it into an object (in this case, the *`modelSwarm`*).
7. **simpleObserverBug.** Subclasses from the Swarm class `SwarmGUI` to create a new class `ObserverSwarm`, an instance of which is created and called *`observerSwarm`*. This is the first example with a complete Swarm hierarchy which begins with main.m and translates actions from `ObserverSwarm` to `ModelSwarm` to individual agents.
8. **simpleObserverBug2.** This example adds probes that allow users to click on graphics to reveal information inside them.
9. **simpleExperBug.** Introduces the possibility that a simulation might be run over and over in "batch" mode while the graphical interface reports summaries of the runs to the user.

6.2. What Are You Supposed to Learn from the Tutorial?

So, after you worked on the tutorial for 20 hours or so, what then? You should know all kinds of details about how Swarm can be used, of course, but there are some bigger themes.

It is not vital to know how to model bugs (although, perhaps for an entomologist...), rather, it is vital to understand that Swarm is a toolkit that provides a housing for a modeling exercise. Swarm imposes no inherent limitations on the nature of agents that can be represented within its framework.

Don’t read much further in this user guide until you work on the tutorial. You will know if you have worked on it long enough when you understand clearly each of the following points.

- **Swarm has many classes to make the modeling job easier.** There are workhorse classes like `Swarm`, `SwarmGUI`, and `SwarmObject`, but also there are many "little helpers" like `List`. Getting to know the

ins-and-outs of these little helpers is extremely important.

- **Swarm handles memory details.** Did you note that there are no **`malloc`** and free and other standard C memory-managing commands in Swarm code? Those commands exist, but they exist inside the Swarm library, and they are accessed on behalf of users who use **`create`** or **`createBegin`** and **`drop`** to access memory for objects and get rid of them. To create objects (instances of classes) in Swarm, there must either be a **`create`**message sent to a class or there must be a **`createBegin`/`createEnd`** pair that serves as bookends for commands that create an instance, set its internal state, and complete the instantiation.
- **Case is important.** Including the right header files may give you access to "factory objects" like `List` or `Schedule`. You can use any name you like for the objects that are created as instances. By custom, an instance of a class–an object–is named in small letters, such as *`bugList`* as an instance of `List` or *`modelSchedule`* as an instance of `Schedule`. In the tutorial, when there is a single instance of a class to be created, by convention, it is typically named the lowercase version of the class name, such as the *`foodSpace`* object which is an instantiation of `FoodSpace`.
- **Neatness counts.** As in any kind of programming task, neatness counts. Classes in Swarm are created with methods that group together their jobs by functions. One will often find, in `ObserverSwarm` for example, commands that create a *`modelSwarm`* instance and then issue it these commands:

```
[modelSwarm buildObjects];
[modelSwarm buildActions];
```

The **`buildObjects`** method creates objects and **`buildActions`** creates schedules. If one wanted to, one could build a gigantic method in the `ModelSwarm` class called **`doStuff`** and then call that method with:

```
[modelSwarm doStuff];
```

Programs written with this approach are hard to proofread and manage. It is much better to write small methods, each of which accomplishes a relatively specific task.

- **There is often a need for "record keeping" classes.** In order for data to be displayed meaningfully in a graph, for example, it must be provided to the graph object in a format that the graph object can handle. The class `World` in simpleObserverBug is subclassed from Swarm's `Grid2d` class.
- **Graphics are optional, but nice.** Commands in the Observer Swarm control the graphical display. There are many kinds of graphs and ways to alter their appearance. It is not necessary to design a Swarm program to make pretty pictures, however. One might just as well run in a "batch" mode that prints numbers into files for later inspection. There is a useful example of the batch mode in the Heatbugs code.
- **Open Source means open the source.** To find out what messages an instance of a class will respond to, you should first consult the *API* [1]: the *Swarm Reference Guide*. In most cases the average user will

1. Application Programmers Interface

encounter, consulting the API is sufficient, but when you really need to know how something is implemented (either to understand the efficiency implications of using a certain method in your program or if a particular method appears to not behave as documented), you can go look in the Swarm source code itself. That's what the members of the Swarm team do when users ask questions.

6.3. After the Tutorial: What now?

After the tutorial exercises are finished, one can then proceed to study the example applications in **swarmapps** and others that are available (for free!) on the web. The application called **Heatbugs** in the **swarmapps** package gives a rich and workable example of a simulation that builds on the ideas in the tutorial.

Chapter 7. Creating Objects In Swarm

The way in which objects are created depends on a computer's compiler and the software libraries available to the user. The implementation of Objective C on a system using the GNU compiler will not be exactly the same as the implementation on a Next system. While most of the points made in the literature on Objective C easily carry over to Swarm modeling, the commands needed to create objects are an exception. In the Objective C manual for Next systems, for example, one finds a syntax methods **`init`** and **`alloc`** that are not used in Swarm. That's why a brief study of object creation is important.

7.1. Begin at the Beginning

Pick any Swarm application you like, such as Heatbugs. Look in `main.m`. What do you find? There's a check to see if the GUI mode or batch mode is to be run, and depending on that choice, either the `ObserverSwarm` or the `BatchSwarm` is designated as *`theTopLevelSwarm`*.

Suppose we have do not do anything special when compiling and running the **heatbugs** executable, so the GUI mode is used. In that case, the relevant code in `main.m` is this:

```
if (swarmGUIMode == 1)
  {
  theTopLevelSwarm = [HeatbugObserverSwarm createBegin: globalZone];
  SET_WINDOW_GEOMETRY_RECORD_NAME (theTopLevelSwarm);
  theTopLevelSwarm = [theTopLevelSwarm createEnd];
}
```

The first command inside the brackets tells the class `HeatbugObserverSwarm` to execute its **`createBegin`** method and return an object which is to be named *`theTopLevelSwarm`*. In this example, the `HeatbugObserverSwarm` is the class and also serves as a "factory object", an object that can build instances of its class. The second command is a macro that saves window positions on subsequent runs of the program. It is set between the **`createBegin`** and **`createEnd`** methods because it is setting permanent features of the object *`theTopLevelSwarm`*. The last command "seals" off the creation phase by telling the recently created object `theTopLevelSwarm` to run its **`createEnd`** method.

In the Swarm Reference guide, many of the protocols have methods that are divided between three phases. The phases are "Creating", "Setting", and "Using". It is important to pay attention to the phase in which a method is listed. Methods or macros listed in the Creating phase must only be used between the **`createBegin`** and **`createEnd`** messages. If such a method is used after the createEnd, it will cause the program to fail. Similarly, a method in the Using phase must be used only after the createEnd method has finished. Methods in the Setting phase can be used at any time in an object's life cycle.

7.2. Detailed Look at `createBegin`/`createEnd`

Now take the next step and look at the **`createBegin`** and **`createEnd`** methods that are called by the code in `main.m`. Follow the steps into `HeatbugObserverSwarm.m`. Here you find the methods **`+createBegin`** and **`-createEnd`**. The plus sign on **`createBegin`** indicates that this method cannot be executed by an instance of the class `HeatbugModelSwarm`, but rather only by the factory object. Here is a portion of the method **`createBegin`**:

```
+ createBegin: aZone
{
  HeatbugObserverSwarm *obj;
  id <ProbeMap> probeMap;
  obj = [super createBegin: aZone];
  obj->displayFrequency = 1;

  // [Code that creates "probemaps" omitted here]
  return obj;
}
```

This a good example of how the Swarm toolkit handles the creation of objects. The pointer to the class `HeatbugObserverSwarm` named `obj` is defined. Since `HeatbugObserverSwarm` is subclassed from `GUISwarm`, it is important to be sure that all of the important variables of a `GUISwarm` object are initialized and inherited by `HeatbugObserverSwarm`. This is done in one step by telling the superclass to execute its **`createBegin`** method. Since the classes are linked together in a hierarchy, each higher level class in turn executes its **`createBegin`** statement. That is how the instance of the class ends up setting values for all the variables that it inherits.

The **`createBegin`** method of its superclass is called to put the created objects in `aZone`, which is the name of the space passed in from `main.m`. The memory zone that is created is returned and set equal to *`obj`*. Then the `return obj` command gives back the created object to the calling code, in this case `main.m`, which then treats it as *`theTopLevelSwarm`*.

The reader can investigate in the Swarm source code to see that `GUISwarm` inherits through a hierarchical chain the ability to create memory zones and objects. `GUISwarm` is subclassed from Swarm, which in turn inherits from `CSwarmProcess`. That class is defined in the activity directory of the source code in a file called `SwarmProcess.m`. This is the first place where you will find **`createBegin`** and **`createEnd`** methods as you move up the inheritance tree, so it must be that these are the methods that are executed when *`super`* is told to do something in this code.

The **`createEnd`** method in `HeatbugObserverSwarm.m` is quite simple:

```
- createEnd
{
  return [super createEnd];
}
```

In a case like this, when the super class is inside the Swarm library, it may be hard to figure out exactly why this command is needed. As a matter of fact, it is not necessary in this case at all, but it does not do any harm. If it were omitted from this class, then this class would just inherit **createEnd** method from the somewhere above in the family tree. By using it in this way, we make sure that the commands of the super class's createEnd method are executed, and this may be important because those steps might initialize some variables that this class inherits.

There are cases in which the **createEnd** statement may be more substantial. In the **createBegin** phase, we typically find commands that set permanent features of objects. Some methods that initialize instance variables can also be included. In the example above, the variable *display frequency* inside **obj* is set equal to 1. These variables are set at the first possible opportunity because other variables may depend on them. After `main.m` calls the **createBegin** method, `main.m` may include statements that further tailor the state of the object and those commands may depend on values set in **createBegin**. Finally, when `main.m` calls **createEnd**, a new slew of commands may be executed that define further elements of the object.

The **createEnd** statement may be a convenient place to put any code that completes the initialization of an object. For example, suppose inside there is a variable called `age`. In **createEnd**, one might find this:

```
- createEnd
{
  [super createEnd];
  age=0;
  return self;
}
```

The super class's **createEnd** method is executed, which will assure that any variables initialized there are set properly. Then the instance variable age is set equal to 0. (Sometimes you will find examples in which **createEnd** is a "garbage can" that collects a large number of commands that set initial values for variables inside the object. These commands might as well be regrouped and put into a new method inside the object that might be called `setInitialValues` that would be executed after the **createEnd**. The readability of the code is enhanced that way.)

The **create** message causes the receiver to carry out both its **createBegin** and **createEnd** methods. Why didn't we always use **create**? Well, sometimes we need to define variables between the **createBegin** and **createEnd** steps, as seen in `main.m`. If there is no need to set values in that way (no methods are listed in the Creating phase in the Swarm Reference Guide are used), then **create** is enough.

7.3. Swarm Zones and Recursive Objects Creation

One of the most troublesome exercises in computer programming is the management of dynamically allocated memory. The correct usage of dynamic memory requires a great deal of care, and when a portion of memory is no longer needed, is must be "freed," made available to the central processor. If memory is allocated and then forgotten, a "memory leak" is said to exist because the program does not tell the operating system to reclaim unused memory addresses.

The Swarm libraries are designed to handle memory allocation with a minimum of user intervention. The **`createBegin`** and create commands allocate memory and the user is not expected to think about where the RAM comes from to store an object. Similarly, when a program is finished with an object, that object can be sent the **`drop`** message and that should take care of freeing the memory that the object used.

The create statements used in Swarm typically have this flavor:

```
someUserCreatedObject = [SomeSwarmLibraryObject  create: someMemoryZoneHere];
```

(The method **`create`** can be replaced by a **`createBegin`**/**`createEnd`** pair as described above.) More specific examples are discussed below and are of course scattered throughout the Swarm examples. The important thing is that an object in the Swarm library is able to respond to a method that creates an instance of itself and that instance lives in a memory zone that is managed by the Swarm library.

In the `main.m` file, the top level Swarm is created and it is allocated into an instance of `Zone` called *`globalZone`*.

```
theTopLevelSwarm = [HeatbugObserverSwarm createBegin: globalZone];
```

This *`globalZone`* is created when the initSwarm function is called at the beginning of a swarm program. The top level Swarm is told to create itself in that space. Any Swarm objects of type `Swarm` or `GUISwarm` are able to serve as memory zones. Inside the `ModelSwarm` one sees a command such as:

```
probeMap = [EmptyProbeMap createBegin: self];
```

This tells the `EmptyProbeMap` class in the Swarm library to create an instance of itself in the memory zone allocated by the `ModelSwarm`, and that allocated object is to be named *`probeMap`*.

The objects at the top level of the swarm hierarchy (whether Swarm or GUISwarm) have the power to "create space" for objects that live inside them. As the code in `main.m` proceeds through the creation of *`theTopLevelSwarm`*, it is allocating memory and setting other important creation-state variables. Then, that newly created object is told to go through its paces:

```
[theTopLevelSwarm buildObjects];
[theTopLevelSwarm buildActions];
[theTopLevelSwarm activateIn: nil];
[theTopLevelSwarm go];
```

When you go look at the **`buildObjects`** method executed by the *`theTopLevelSwarm`*, what do you find? Depending on what edition of the Heatbugs source you have, you will find something like this:

```
heatbugModelSwarm = [HeatbugModelSwarm create: self];
```

In this code, the *self* is the observer level, meaning that the `HeatbugModelSwarm` class is told to create an instance of itself in the memory zone provided by the observer, and that allocated object is named *heatbugModelSwarm*.

If you then follow the code into the `HeatbugModelSwarm.m` file, you find it has **createBegin** commands that initialize a number of instance variables and objects. Unless you have a pretty old piece of code, those objects will be created in the memory zone *self*, the space provided by the model swarm itself.

Objects that are of type `SwarmObject` are not memory zones, and so when objects are created inside classes that inherit from `SwarmObject`, a command to allocate memory must be used.

```
bugPixmap = [Pixmap createBegin: [self getZone]];
```

The *bugPixmap* object is created inside `Heatbug.m`, but the name of the memory zone where that object "lives" has to be retrieved with the `[self getZone]` command. The [self getZone] method returns the name of the zone in which the bug exists, which in this case is heatbugModelSwarm.

7.4. Using Swarm Library Objects and Header Files

It often seems as if objects appear by "magic." It is more reasonable to say they are provided by the Swarm library in a way that is not entirely obvious. For example, suppose you want to create a list of objects. One can declare an object *listOfFriends* and then create it, like so:

```
id listOfFriends;
listOfFriends = [List create: self];
```

You see little bits like this all over example code from Swarm projects. Where does this `List` class object come from? Why are you able to use it even though there is no import statement for List.h at the top of the program? It seems as though, if you want to make a call on the List class, you ought to include `List.h` at the top of your file, right?

To use many of the Swarm classes, it is not necessary to use such an explicit import statement since you are not subclassing. Instead, it is necessary to include one of the "general purpose" header files that corresponds to the major sections of the Swarm library. To create List instances, for example, one needs to import the "general purpose" collections.h, which declares not only List, but other collections classes as well.

The general purpose header files can be found in the include directory of your swarm installation. They are:

- activity.h

- analysis.h
- collections.h
- collections.h
- gui.h
- objectbase.h
- random.h
- simtools.h
- simtoolsgui.h
- space.h

As you browse the Swarm Reference Guide, you will find many protocols that adopt the CREATABLE protcol, which means that you can use them to create objects in your code. When you use them, import one of these library headers. For example, to create List objects, import `collections.h`. That header file should be included in any file that refers to a List, Map, Set, or any of the other creatable collections objects.

Should the general purpose header file be included in the .h (header) file or the .m (implementation) file of your class? Generally speaking, it is only necessary in the .m file, since that is where you are doing the work of creating the object. The only exception to this rule arises if you refer to the protocol protocol in your header file. It is necessary to include the collections.h in your header file if you want to declare an object that will adopt a protocol, as in

```
id <List> aList;
```

If you forget to import collections.h, the compiler will fail and say there was a parse error. This happens because it does not have a class or protocol List in its purview, and so it assumes you have made a typographical error.

On the other hand, if your header file uses a general declaration, as in

```
id aList;
```

then there is no need to include collections.h in the header file. It should only be included in the implementation file for your class.

Explicit importing of a class-specific header file is only required when you need to subclass from that file. Since your header file declares that you are creating a class, and it defines the superclass, then the import statement must be included in your header file. SwarmObject is the most frequently used superclass, so consider it for example. Your class's header file should import *both* the general purpose library header objectbase.h as well as `objectbase/SwarmObject.h`

We will summarize this by offering two rules of thumb:

- if you use a class that conforms to a protocol (such as `List`) to create objects in your own program, you need to include one of the general Swarm library headers.
- if, however, you are *subclassing* from a class that adheres to a protocol, you need to import the header file for that class.

We hasten to point out that not all of the Swarm protocols will allow you to subclass from them. To avoid some serious complications, the List type cannot be used to create user-specific classes. One can create Lists and use them as intended, but one cannot create variants of the Swarm List class to customize their behavior for a specific project.

As good coding practice, you should try to keep your files clean. Each file should only include imports for header files that you actually reference in that particular interface/implementation file pair. Don't adopt a "include everything" mentality when importing files.

7.5. Variations on a Theme

Once you have seen how an object can be created, you should start thinking about how your simulation will be organized. Within the standard Swarm approach, you begin with `main.m` allocating space for the top level swarm, which may be either a gui or batch swarm. Then the model swarm object is created in that top level, and the model swarm in turn creates the substantively important objects that embody the model you seek to investigate.

There are a number of different ways in which the creation of objects can be managed. Some are more intuitive than others, some are more "reusable" than others. Since the first Swarm exercise for most people involves bugs, it is not surprising that many examples of Swarm code follow the convention of the bugs project. As found in SimpleSwarmBug3, for example, the `ModelSwarm.m` file creates the bug objects in this way:

```
- buildObjects
{
  Bug *aBug;
  int x, y;
  [some lines omitted here]
  bugList = [List create: self];

  for (y = 0; y < worldYSize; y++)
    for (x = 0; x < worldXSize; x++)
     if ([uniformDblRand getDoubleWithMin: 0.0 withMax: 1.0] < bugDensity)
      {
      aBug = [Bug createBegin: self];
      [aBug setWorld: world Food: food];
      aBug = [aBug createEnd];
      [aBug setX: x Y: y];

      [bugList addLast: aBug];
      }
```

```
  reportBug = [bugList removeFirst];
  [bugList addFirst: reportBug];
  return self;
}
```

This code cycles over the spaces in a lattice, and if the conditions are right, it causes the `Bug` class to create an instance of itself, called *aBug*, and then that instance is added to the *bugList*.

Some changes can be made to make this code a little more versatile. For example, create a new method called **spawnOneBug** that moves out the bug creation steps.

```
- buildObjects
{
  Bug *aBug;
  int x, y;
  [some lines omitted here]
  bugList = [List create: self];

  for (y = 0; y < worldYSize; y++)
  for (x = 0; x < worldXSize; x++)
  if ([uniformDblRand getDoubleWithMin: 0.0 withMax: 1.0] < bugDensity)
   {
    [self spawnOneBug];
   }

  reportBug = [bugList removeFirst];
  [bugList addFirst: reportBug];
  return self;
}

- spawnOneBug
{

  aBug = [Bug createBegin: self];
  [aBug setWorld: world Food: food];
  aBug = [aBug createEnd];
  [aBug setX: x Y: y];
  [bugList addLast: aBug];

  return self;
}
```

Why is this more versatile? By isolating the steps necessary to create a bug and add it to the *bugList* in the **spawnOneBug** method, we make it much easier to add new bugs to the simulation as time goes by.

7.6. How Do You Kill Off Those Poor Little Devils?

If you look at Swarm examples for any amount of time, you can't help but run into objects that get dropped. Little "helper objects" like indexes for lists are created and just as readily discarded with the command:

```
[someIndexName drop];
```

If everything goes the way it is supposed to, this should take the object out of memory and free that memory for the program to reuse.

What if the objects inside your simulation are supposed to be born and killed through time? The Swarm bug tutorial mainly focuses on models in which a population of actors is created at the outset and those individuals remain in existence throughout the length of the program. What if we wanted code to model a world in which the happy HeatBugs could reproduce themselves, or what if the unhappy ones could die and be freed from their never ending search for a place neither too cool or too hot?

The Swarm **SugarScape** model provides an excellent example of a way to manage the birth and death of agents in an on-going model. The **sss** model's `ModelSwarm.m` file contains the critical ingredients. It has a method **addNewRandomAgent** which does what **spawnOneBug** does–it includes all the commands that create an instance of a `SwarmObject` and initializes it. **sss** also provides a handy structure to kill off agents and replace them with new ones. This is managed in a three stage process. The model swarm creates a Swarm list object called *reaperQueue*. When an event occurs that forces an object below the survival threshold, then that object is added to the *reaperQueue* by the **agentDeath** method. Then the model Swarm's schedule includes a command that removes the dead agents from the *reaperQueue*. The **reapAgents** method transverses the list of agents who are to die, it removes them from the list of active agents and then tells them to drop themselves from memory.

```
- agentDeath: (SugarAgent *)agent
{
  [reaperQueue addLast: agent];
  if (replacement)   // Replacement rule R (p.32)
    [self addNewRandomAgent];
  return self;
}

// remove all the agents on the reaperQueue from the agentList
// This allows us to defer the death of an agent until it's safe to
// remove it from the list.
- reapAgents
{
  id index, agent;

  index = [reaperQueue begin: [self getZone]] ;
  while ((agent = [index next])) {
    [agentList remove: agent];
    [agent drop];
  }
  [reaperQueue removeAll];
  [index drop];
```

```
  return self;
}
```

Chapter 8. Doing the Chores: `set` and `get`

Object-oriented programming organizes the way programmers think about information in a new way. The objects maintain their variables (the "instance variables", or IVARs for short) and the information contained in those variables is private, self-contained within the object. This has benefits in the design of code and it also captures some intuitions the autonomy of individual agents in a simulation exercise.

Objects are thus insulated, more or less, and although this makes some things easier to code, it also makes some things more difficult. For example, in C a variable can be set and its value can be changed anywhere in the program. In object-oriented languages like Objective-C, an object can hold several variables and those values can only be changed by the object itself if we remain within the recommended limits of good programming habits. Some ways to go outside those bounds will be discussed below, but generally speaking it is a good idea to respect the fact that objects maintain their own data.

If objects are maintaining their own data, how do we manage information in a Swarm project. Early on in the development of Swarm, the coders adopted a convention (common to Objective C, Java, Smalltalk and numerous other object-oriented languages) that the term **`set`** starts a method name that sets a value inside an object, such as **`setIdealTemperature`** or **`setAge`**. The term **`get`** is used as the beginning of a method that causes the agent to return some value, such as **`getIdealTemperature`** or **`getAge`**.

8.1. Get and Set Methods

Get and set methods are needed to pass information among objects. For example, consider **Heatbugs**. In the `Heatbug.m` code, one finds a methods that set information inside the bug and also methods that retrieve information from it. Consider the method **`setIdealTemperature`**

```
- setIdealTemperature: (HeatValue)i
{
  idealTemperature = i;
  return self;
}
```

The `Heatbug` object has an instance variable called *`idealTemperature`*, and this sets the value of that variable.

If some other object needs to know the heatbug's ideal temperature, what has to be done? We would have to add a method to the `Heatbug.m` that returns the value of *`idealTemperature`*. Something like this might suffice:

```
- (double) getIdealTemperature
{
  return idealTemperature;
}
```

As much as possible, it is recommended that information be exchanged in this way. Hence, when the observer swarm needs a list of all the agents in a simulation in order to create a graph, the model swarm should have a method, such as **`getAgentList`**, that returns a list of agents that the observer swarm can use.

8.2. Using Set Methods During Object Creation

Consider the way the model swarm level of a simulation can be designed. If the values of many variables are set inside the `ModelSwarm.m` file, and those values are to be passed to the individual agents at the time of creation, then the code that creates individual objects might be designed like this:

```
aBug = [Bug createBegin: globalZone];
aBug = [aBug createEnd];
[aBug setWorldSizeX: xsize Y: ysize];
[aBug setFoodSpace: foodSpace];
[aBug setX: xPos Y: yPos];
[aBug setIdealTemp: [uniformDblRand getDoubleSample]];
```

This code presupposes that the `ModelSwarm.m` file has pre-existing variables (probably integers) *`xsize`*, *`size`*, *`xPos`*, and *`yPos`*, as well as an object *`foodSpace`* and an object *`uniformDblRand`* that can give back a random number. This code also presupposes that set methods exist for the `Bug` class that can get these jobs done.

There are some matters of "taste" and "judgment" that affect model design. One might ask, for example: “why does this code set the ideal temperature in this way?” Why not create a method inside the `Bug.m` file, such as **`initializeValues`** like so:

```
- initializeValues
{
  idealTemperature= [uniformDblRand getDoubleSample]
  return self;
}
```

If this method existed, then the code that creates the bug and sets values in it could have the command

```
[aBug setIdealTemp: [uniformDblRand getDoubleSample]];
```

replaced with this:

```
[aBug initializeValues];
```

This would achieve the purpose of setting the *`idealTemperature`* variable inside the object called *`aBug`*. And, from the information-hiding perspective of object-oriented programming, it seems better because the value drawn for the variable *`idealTemperature`* is never exposed to any other object.

There are a few practical reasons why the first way of setting the ideal temperature might be preferred. First, for the programmer's convenience, it is nice to have as many of the "parametric" changes in a single file as possible. The Bug class can be written and never edited again if all of the changes needed are kept in the `ModelSwarm.m` file. Second, you might save memory dealing with these things in the `ModelSwarm.m` file. Suppose that the object *`uniformDblRand`* has to be created in order to draw a random number. If you insist on writing a method like **`initializeValues`** inside the `Bug.m`, then you need to worry about how that random number generator object is created inside each bug object. It certainly saves memory to create just one random generator in the `ModelSwarm.m` file and then draw numbers from it inside the model swarm itself. There are some good arguments for this approach in the literature on random number generation. The issue seems somewhat esoteric, but the argument is that one is better off making repeated draws from the same random number generator than making one call against each of the many random number generators. For reasons like this, Swarm examples tend to have information translated into objects from the model swarm level, even though it is technically allowable to have that information-creation process completely isolated within the object.

8.3. Passing Information Around

In order to send messages to objects from another class, it is necessary not only to use the correct message, but also to import that class's header file into the code. The `ObserverSwarm.m` file can only tell the `HeatbugModelSwarm` to run its **`createBegin`** method if `ObserverSwarm.m` includes the header file for the `HeatbugModelSwarm`. In `HeatbugObserverSwarm.m`, we find this:

```
#import "HeatbugModelSwarm.h"
```

The inclusion in the "m" file is sufficient if no reference to the `HeatbugModelSwarm` is necessary in the `HeatbugObserverSwarm.h` file. It may be necessary to move the import statement into the header file (the "h" file), however, if any references to a class are contained in the "h" file. In `HeatbugModelSwarm.h`, for example, one finds these import statements:

```
#import "Heatbug.h"
#import "HeatSpace.h"
```

Since these are included, the variable and method definitions can refer to elements of these classes. The variable list declares a pointer to an object of type `HeatSpace`:

```
HeatSpace *heat
```

and there is a method that has an object of type `Heatbug` as an argument:

```
-addHeatbug: (Heatbug *)bug;
```

Many Swarm programmers have run into the following problem. As we have seen, It is not difficult to have the model swarm level create an object. Through the set methods, various values can be set inside the object by commands in the model swarm. However, the programmer wants the agent to be able to access variables inside the model swarm as the simulation progresses. Suppose the `HeatbugModelSwarm` has an instance variable called *`numberOfBugsAlive`*, and inside HeatbugModelSwarm we define a method **`getNumberOfBugsAlive`** that returns that number. Suppose further we want any heatbug to be able to find out how many bugs are alive at any instant. It is tempting to write inside `Heatbugs.m` something like:

```
[heatbugModelSwarm getNumberOfBugsAlive];
```

to access that information. That construction will not work, however, unless we take some special precautions. First, each `Heatbug` has to be made "aware" of what model swarm it belongs to. Inside `Heatbug.h`, a variable would have to be defined:

```
id heatbugModelSwarm;
```

To set the value of this variable, the `Heatbug.m` file needs to have a method like this:

```
- setModelSwarm: (id) nameOfSwarm
{
heatbugModelSwarm = nameOfSwarm;
return self;
}
```

The value of the instance variable *`heatbugModelSwarm`* has to be set in the model swarm when other values are set. When the `HeatbugModelSwarm` is creating bugs, it sets the other values like the ideal temperature and the position, but further it would set itself as the model swarm to which that bug belongs, like so:

```
aBug = [Bug createBegin: globalZone];
aBug = [aBug createEnd];
[aBug setWorldSizeX: xsize Y: ysize];
[aBug setFoodSpace: foodSpace];
[aBug setX: xPos Y: yPos];
[aBug setIdealTemp: [uniformDblRand getDoubleSample]];
[aBug setModelSwarm: self];
```

This assures that, inside aBug, the value of the instance variable *`heatbugModelSwarm`* is defined.

The final precaution is that the header file `HeatbugModelSwarm.h` must be imported into `Heatbug.m`. It is very important that the import statement is added to `Heatbug.m`, not `Heatbug.h`. If it is added to `Heatbug.h`, then the program will not compile because the inclusion causes a circularity: `Heatbug.h` is included in `HeatbugModelSwarm.h`, but `HeatbugModelSwarm.h` is also included in `Heatbug.h`. Putting the import statement in the "m" file avoids that ciruclarity. And, since the import has to be in the "m" file, the

definition of the variable *heatbugModelSwarm* in `Heatbug.h` uses the generic type `id`, rather than a specific type, such as `HeatbugModelSwarm`.

Many swarm examples are designed to avoid the need to allow objects created by model swarm to also access information directly from it. This is usually done by creating a "space" object that keeps records on the model swarm. Individual agents report their positions to the space and the space calculates any necessary statistics about the swarm. The code for the space object can include get methods that the individual agents can execute when they need information about their environment. This approach has the added advantage that additional methods can be inherited from the general space objects in the Swarm library.

8.4. Circumventing the Object-Oriented Guidelines

If one wants to avoid treating objects as containers that hold both data and methods, one can do so. The C language allows the creation of global variables, ones that can be accessed in any part of the code. These `external` variables exist outside a particular class and are thus available to it. The names used for external variables must be unique. One cannot have a global variable called *temperature* as well as a temperature variable defined as an instance variable for each object. There are some occasions in which a program can be made to run more quickly if the whole **get**/**set** exercise is circumvented by creating a global variable.

Another way in which the object-oriented guidelines can be circumvented is the use of the `->` operator. Suppose we have an object called *dog* and it has instance variables *numberOfBones* and *timeSpentSleeping*. Ordinarily, within the object-oriented paradigm, the *numberOfBones* would have to be set by a method such as *setNumberOfBones*. However, the language does allow a shortcut of the following sort. The syntax `dog->numberOfBones` refers to the value of the instance variable *numberOfBones* inside the object named *dog*. Hence, one could have a statement:

```
dog->numberOfBones = 3;
```

that sets the *numberOfBones* to 3 inside the dog. This kind of code is considered to be heavy-handed and brutish because it does not use the methods written for the dog class with which it can set that value and update it. A mistake made with the `->` operator can corrupt the values inside an object.

Even though the usage of `->` is discouraged, one does find examples of this syntax in Swarm code. Almost all Swarm examples use this kind of shortcut in the **createBegin** phase of the model swarm file, for example. This is done, however, because there is no alternative. We want the GUI probe display to allow the user to adjust parameter values before the simulation commences. It is thus necessary to set values inside some objects even before those objects have finished their createBegin/createEnd routine.

Chapter 9. Building Schedules

The core of the Swarm system is the set of features that enhance the design process of simulation projects. The scheduling apparatus is one of the truly important elements of the Swarm system because it offers a way to integrate the actions (and responses) many different agents in many different levels of a simulation.

The actions that go on in a simulation are orchestrated by a objects that respond to the `Schedule` protocol. `Schedule`s are generally built in the **`buildActions`** method of an object. A `Schedule` is something like a calendar in which one might put a red letter X when an important event is supposed to occur. The user then defines what the important events are and integrates them into the `Schedule`. Then the `Schedule` must be activated within the larger Swarm hierarchy of the object.

9.1. Building `Schedule`s

Here is an example of some code that makes a simple `Schedule`. This sort of `Schedule` might appear in the *`ModelSwarm`* level of the bug tutorial, for example.

```
- buildActions
{
  modelSchedule=[Schedule createBegin: self];
  [modelSchedule setRepeatInterval: 1];
  modelSchedule = [modelSchedule createEnd];

  [modelSchedule at: 0 createActionTo: aBug message: M(step)];

  return self;
}
```

The first three lines in the method create the `Schedule` named *`modelSchedule`*. It might as well be *`aBugsLife`* or any other name the user chooses. Between the **`createBegin`** and **`createEnd`** methods, the only detail that this `Schedule` sets is the repeat interval, which is one. That means that all of the actions assigned to the *`modelSchedule`* will be executed at each time step.

Once the code has created a `Schedule` object and set the repeat interval, then that object can be told to insert actions into its `Schedule`. These actions cause the *`modelSchedule`* to build commands that make the desired actions happen. No two simultions are exactly the same, of course, and so there are no hard-and-fast rules. Generally, however, the *`modelSchedule`* is usually told to do either of two methods, **`at:createActionTo:message`** or **`at:createActionForEach:message`**. The first is used when the action of a single object must be `Schedule`d, while the second is used to `Schedule` activities for whole lists.

In this simple example, the *`modelSchedule`* has only a single action, which instructs the one bug in the simulation, whose name is *`aBug`*, to carry out its method called **`step`**. It might be that there is a

whole list of bugs, *bugList*, and each bug has to be instructed to carry out its **step** action. In such a case, the command would be:

```
[modelSchedule at: 0 createActionForEach: bugList message: M(step)];
```

Some additional scheduling topics are discussed, but first the abstract question of selectors and the M operator must be addressed.

9.2. What's that M() Thing?

The commands that tell a Schedule to add actions usually have notation like like **M(someMethodName)** at the end. **M()** is a macro used in Swarm to mean that the selector for the message "step" is returned. Selector, or SEL, is a variable type in Objective C which refers to the abstract name used in the compiler to refer to a method, in this case **step**. **M** is short for message (or method) and was "created to save the time of typing **@selector(myMethod)**," in the words of Nelson Minar. Many of the methods available in the Swarm library want input in the form of a selector, an symbolic reference to a method name, and the **M()** notation is one shorthand way of giving it what it wants.

Some of the methods in the Swarm library will also want a list of parameters that go with the selector. Suppose, for example, you have a psychologist agent that has this method:

```
- dealWithProblemBetween:anObject And: (id) anotherObject;
```

Presumably, you have some code in which there are objects, perhaps named *bill* and *susan*, and when you are not needing the Swarm libraries for anything, you just tell your psychologist agent to carry out that method with a command such as:

```
[yourShrinksName dealWithProblemBetween: bill And: susan];
```

The name of this method is **dealWithProblemBetween:And:** and its input variables are two objects.

Now suppose you have a whole list of psychologists, and that you want each one of them to deal with the problem between bill and susan. Furthermore, you want them to do it over and over again. To do that, you need Swarm to schedule the job, so you run into that selector problem again. Notice in the Swarm documentation that the Schedule protocol can respond to a method called **createActionForEach**, which has a prototype like this:

```
- at: (timeval_t)tVal createActionForEach: target message: (SEL)aSel : arg1 : arg2
```

At the end of this definition, we see this method wants to be given a selector, and then the two arguments that go with it. We know we can grab the selector of the command we want with

M(dealWithProblemBetween:And:), so when we tell the schedule object to make each psychologist look into the *bill* and *susan* problem, we need a command like this:

```
 [modelSchedule at: 0 createActionForEach: listOfShrinks mes-
sage: M(dealWithProblemBetween:And:):bill:susan];
```

Admittedly, this notation seems ungainly, but it works.

It is a difficult understand the reason why the selector is needed in the first place. If one is not well versed in Objective C, it may be best just to follow the form of the examples provided with Swarm and not worry about the **M()** until it is absolutely necessary. [1]

You can go look in the Swarm libraries to see many examples to show why selectors are so vital. Just by coincidence, we happened to be looking at the `Object2dDisplay.m` file, where there is a particularly clear example of how these selectors come into play. The `Object2dDisplay`'s **display** method is often scheduled in the observer swarm level of projects that draw on `ZoomRaster` grids. In order to make this possible, the selector is required.

When an instance of `Object2dDisplay` is created, one of the first thing the user does it tell that object what the display message for its members is. The `Object2dDisplay` is passed a selector by the "setDisplayMessage" method.. This bit of code is from SwarmSugarScape's `ObserverSwarm.m` file.

```
 agentDisplay = [Object2dDisplay createBegin: [self getZone]];
 [agentDisplay setDisplayWidget: worldRaster];
 [agentDisplay setDiscrete2dToDisplay: [sugarSpace getAgentGrid]];
 [agentDisplay setObjectCollection: [modelSwarm getAgentList]];
 [agentDisplay setDisplayMes-
sage: M(drawSelfOn:)];   // note the draw method passed as selector
 agentDisplay = [agentDisplay createEnd];
```

The `Object2dDisplay` is told which widget it is addressed to **setDisplayWidget** and which agent list (*[modelSwarm getAgentList]*). Note how the object *agentDisplay* is told to set inside it the value of the selector **M(drawSelfOn:)**. It does not ask for the additional information of the input variables that would ordinarly follow **drawSelfOn:**. It only wants the selector.

1. On the off chance that you have reached a point of necessity, and that is why you are reading this guide, consider this explanation of the problem. Many jobs happen inside the swarm library. If you want each member of a certain list to receive a message every time period, you need to give Swarm a way to keep track of the members and the message. Since the objects at which you want the messages aimed already exist and are objects, it is quite straightford to pass a Swarm object that object's name. Passing a Swarm object a method name is, however, more difficult. You need to give the Swarm object something symbolic if it is to receive and remember it. You wouldn't want the Swarm library to be built around the passing of character strings, right? (Well, maybe you would, but pretend your answer is no!) If you pass the selector, you are passing a variable type that the Swarm libraries can remember and use when they need it.

Each item in the list of agents, which is retrieved by the command *[modelSwarm getAgentList]*, has the method **drawSelfOn:**. Here is the method **drawSelfOn:**, which can be found in SugarAgent.m:

```
- drawSelfOn: (id < Raster > )r
{
  [r drawPointX: x Y: y Color: 100];
  return;
}
```

If the agent gets the message **drawSelfOn:r**, then the agent in turn tells the object *r* to use its **drawPointX:Y:Color:** method to put the agent on the picture.

The importance of the selector becomes apparent after a study of the file Object2dDisplay.m in the Swarm space library. In Object2dDisplay.m, we find this method:

```
- setDisplayMessage: (SEL)s
{
  displayMessage = s;
  return self;
}
```

This takes the selector and puts its value into an instance variable called *displayMessage*. The other set methods in Object2dDisplay have already set the variable *objectCollection* and *displayWidget*. So, floating around inside the Object2dDisplay instance, are instance variables that can be put to use in scheduling the actions.

When the **display** method of Object2dDisplay gets scheduled by the ObserverSwarm, this method from Object2dDisplay.m is called:

```
- display
{
  [...some irrelevant lines omitted...]
  // if we have a collection to display, just use that.

  [objectCollection forEach: displayMessage: displayWidget];
}
```

The **forEach:** method in the Swarm library takes a selector as its first argument, and any parameters needed by the selector follow, separated by semicolons. So, in this example, the *displayMessage* variable has been set as **drawSelfOn** and the *displayWidget* has been set as the *worldRaster*. So when the **display** method executes, it passes to each object in the list a message that tells it to draw itself on the *worldRaster*.

Almost all uses of the selector type in Swarm allow a variable number of arguments. It is important to note, however, that these arguments are generally required to be objects. We would have some trouble if the arguments were floating point values, for example. When such a case arises, one if usually forced to write "wrapper" objects around floats in order to pass them to the Swarm library. For example, consider a

change in the problem faced by the hypothetical psychologists discussed above. Suppose instead of dealing with *bill* and *susan*, they are instructed instead to set some variables inside themselves, such as *idealTemperature* or *setLengthOfFeelers* (these are buggish psychologists, say). The method in the psychologist class might have this interface:

```
- setTemperature: (float)temp And: (float)feeler;
```

Now, if you wanted the Swarm to schedule this **setTemperature:And:** method to happen every time step, perhaps to "reinitialize" the objects to a "fresh" state, then you would be in a world of hurt. If you need the temperature to be set at 37.3 and the feeler to be 54.1, you would be tempted to write this, but you would be making a big mistake:

```
[modelSchedule at: 0 createActionForEach: listOfShrinks mes-
sage: M(setTemperature:And):37.3:54.1];
```

The **createActionForEach:** method is looking for something like **SELECTOR:id:id** at the end, but this command instead gives it **SELECTOR:float:float**.

When you need to pass float values in this way, you may have to redesign your methods so that they can take objects. For example, you might make a new kind of object to hold the values of those floating point numbers. This new class is often called a "wrapper" class. If that new class, call it the `ParameterHolder` for discussion, is able to respond to methods like **getTemp** and **getFeelr**, then this problem could be tackled by rewriting the **setTemperature:And:** method into something like:

```
- setParameters: holdingObject;
```

If you have an instance of `ParameterHolder`, called *aHolder* for short, then the psychologist can be told to **setParameters** by a command like this:

```
[aShrink setParameters: aHolder];
```

Presumably, inside the **setParameters** method there are actions that get the values from the *aHolder* which is passed in, as necessary.

If you need to schedule a whole list of psychologists to reset themselves, the schedule command could be written as:

```
[modelSchedule at: 0 createActionForEach: listOfShrinks message: M(setParameters):aHolder];
```

9.3. ActionGroupS

An `ActionGroup` is a set of actions that are supposed to happen in sequence. The **buildActions** method is often designed to first create an `ActionGroup` and then to schedule that is be repeated every now and then.

Consider the Swarm **SugarScape** again. Its model swarm has this **buildActions** method [2]:

```
- buildActions
{
  [super buildActions];

  // One time tick, a set of several actions:
  //   randomize the order of agent updates (to be fair)
  //   update all the agents
  //   kill off the agents who just died
  //   update the sugar on the world
  modelActions = [ActionGroup create: [self getZone]];
  [modelActions createActionTo: sugarSpace message: M(updateSugar)];
  [modelActions createActionTo: shuffler message: M(shuffleList:) : agentList];
  [modelActions createActionForEach: agentList message: M(step)];
  [modelActions createActionTo: self message: M(reapAgents)];

  // The schedule is just running our actions over and over again
  modelSchedule = [Schedule createBegin: [self getZone]];
  [modelSchedule setRepeatInterval: 1];
  modelSchedule = [modelSchedule createEnd];
  [modelSchedule at: 0 createAction: modelActions];

  return self;
}
```

`ActionGroup`s group together events at same timestep. `Schedule` then executes the actions. If there is only one `ActionGroup` in a schedule, then one might as well not create a group and just add the actions to a schedule one at a time. The use of `ActionGroup`s is most valuable when several sets of separate actions are considered and they need to be scheduled to start at different times or repeat at different intervals.

9.4. Activating Swarms

The **buildActions** method is intended to be the place in which one creates Swarm schedules, but that does not make the simulation carry out the scheduled actions. In order to put the object's schedule into the "grander scheme of things" in Swarm, it is necessary to activate it. Through the activation mechanism, the Swarm library integrates the many diverse actions of the different objects that exist in the simulation. It is done through a hierarchical series of **activateIn** methods. The `main.m` tells the top level swarm to activate itself (after it has been told to create its objects and schedules, of course). Then the top level swarm activates any schedules it might have created and (here's where the hierarchy comes into play) it tells the next lower level to activate itself. That next level activates its schedules and tells the level below to activate itself. This is how the activities of many different levels are synchronized.

2. Note: the use of shuffler to mix the agents in the list has been integrated into the Swarm libraries and by the time you read this there may be some new syntax involved.

Virtually any Swarm program will offer a sufficient example of the progression of **activateIn** methods from top to bottom. The `main.m` in **Heatbugs** has this:

```
[theTopLevelSwarm activateIn: nil];
```

The top level swarm is told to activate itself in *nil*, which is a way of telling the top level that it is in fact at the top of the hierarchy. It is not told to activate itself within the zone of any other swarm, in other words. When the time comes, the lower levels are told to activate themselves in the zone of the swarm that is one step above it (as we shall see).

Assuming we are doing a graphical model, the **activateIn:** method of the top level is found in `HeatbugObserverSwarm.m`. In the `HeatbugObserverSwarm.m`'s **activateIn:** method, we find commands that both activate schedules within the observer swarm and also activate schedules in the next lower level of the simulation:

```
- activateIn:  swarmContext
{
  [super activateIn: swarmContext];

  [heatbugModelSwarm activateIn: self];

  [displaySchedule activateIn: self];

  return [self getActivity];
}
```

It is important to recognize that the **activateIn** methods of each class within the hierarchy fulfill a vital role in synchronizing the schedules of the levels. These are typically written so that, first, the activateIn method of the superclass is executed. Then the schedules of the current class are told to activate themselves in the current context, and then the **activateIn** method of the next lower level Swarm is told to activate itself.

The **activateIn:** method returns an object of class Activity, which is a sufficiently important concept that it is treated on its own in the next section.

9.5. What is an `Activity`?

The `Activity` class is a vital element of the Swarm approach. It's fundamental purpose is to merge all the subjective points of view of agents at different levels into a single objective time sequence. Somehow, the name `Activity` does not seem powerful enough. Perhaps perhaps it would be better called an `ActivityManagerAndIntegrator`, or something grand. Of course, on a practical level, it responds to messages like **run**, **stop**, **next**, **terminate**, and so forth.

If you have an object subclassed from `Activity`, you can tell it to make the simulation run, stop, terminate, or respond to a number of other commands. Swarm programs are designed hierarchically, so that if you tell an activity from one level to stop, you stop all lower levels of the simulation as well. Many Swarm programmers do not come face-to-face with the Activity class because it sits behind the scenes. The control panel, in particular, allows users to start and stop their simulations, and all the while the `Activity` class objects are behind the scenes, doing the actual work.

It is easy to "grab" the activity object of a given Swarm. The method which returns the activity of a Swarm is **`getActivity`**. If one needs to tell the object modelSwarm to stop, for example, then the command:

```
[[modelSwarm getActivity] stop];
```

will get the job done. This first grabs that object's activity, and tells that activity to stop. To make that object start up again, it can be sent the **`run`** message.

The ability to start, stop, and terminate an activity is particularly handy when designing a program that repeats a Swarm experiment. These methods are used in the Swarm tutorial's "SimpleExperBug2" model as well as the "RepeatingHeatbugs" application that is available at the Swarm ftp site.

9.6. Dynamic Scheduling

The schedules described so far are of a particular static sort. Each agent, or each agent in a list, is told to execute some action at some particular time. What if the simulation is designed so that the activation of a certain agent is conditional on events within the model? The need to create a flexible schedule gives rise to an important feature of Swarm that is referred to as a *dynamic schedule*. The **Mousetrap** application is a fully worked out example that shows the power of dynamic scheduling.

The idea behind dynamic scheduling is so simple that one can be in danger of confusing it by explaining it too much. Simply put, the strategy is as follows. First, create an object from the Swarm `Schedule` class. Don't put any actions in the schedule, just let it sit there in the **`buildActions`** method, doing nothing (yet). Second, write a method that tells that schedule to add things that are to be executed at particular times. It is as simple as that.

The concept is quite simple, but, as the **Mousetrap** application illustrates, it can be quite complicated in the implementation. The simplest possible dynamic scheduling project of which we are aware was made available in the package **Swarmfest99-demos** (in the swarm ftp site, it should be available in the `users-contrib/anarchy` section). The application is called **simpleObserverBug-growth**. It begins with the familiar exercise from the Swarm tutorial and then models the regeneration of the food supply.

In the **simpleObserverBug-growth** example, the `ModelSwarm.m` file has all of the usual ingredients. The dynamic schedule is created in the **`buildActions`** method, like so:

```
growthSchedule = [Schedule createBegin: self];
```

```
  [growthSchedule setAutoDrop: 1];
  growthSchedule = [growthSchedule createEnd];
```

The *growthSchedule* is created and the **setAutoDrop** feature is set, so that actions are executed one time and then dropped from the *growthSchedule*. Otherwise, once we add an action into the schedule, it will repeat itself forever.

In the ModelSwarm.m, one also finds the method that has the power to add items to the schedule. It is called **scheduleGrowthAtX:Y:**. When this method is called, it grows more food at a particular spot.

```
- scheduleGrowthAtX: (int)x Y: (int)y
{
  long time;
  time=[[self getActivity] getCurrentTime];
  [growthSchedule at: time+growthInterval
      createActionTo: foodSpace
             message: M(putValue:atX:Y:):1:x:y];
  return self;
}
```

As you can see, this method retrieves the current time, and then it tells the growth schedule to create an action to the foodspace at a time in the future. And the ungainly **M()** notation appears, which we described in greater detail in Section 9.2. Note that the putValue:atX:Y: method requires 3 integer parameters, which represent the value being put in the space and the two coordinates.

The preceeding steps are the essence of creating the dynamic schedule. The empty schedule is created, and a method is created that can tell that schedule to add an item. The only remaining step is to design the simulation so that this method actually gets executed during the course of the program. That means that some class has to have a method that can tell the *modelSwarm* to execute its **scheduleGrowthAtX:Y:** method. In this example, it is done by making the *foodSpace* object aware of the *modelSwarm* and the, when a piece of food is consumed, the dynamic scheduling process is put to use. From the FoodSpace.m class, here is the relevant method:

```
- eatX: (int)x Y: (int)y
{
  [self putValue: 0 atX: x Y: y];
  [model scheduleGrowthAtX: x Y: y];
  return self;
}
```

Chapter 10. Working with Lists

Programmers who have worked primarily in non-object-oriented languages like Fortran, Pascal, or C, are sometimes perplexed at the way Swarm programs manage repetitive tasks. While there is no hard rule that iterative chores have to be managed in a certain way, one will find a fairly common approach that uses a Swarm object called `List`. Since this usage is both widespread in Swarm and different from the usual strategy in other languages, it deserves some discussion.

10.1. The `List` Class

This section is not intended as a comprehensive review of Swarm's Collections library. That job is left to a later chapter. Instead, the purpose of this section is to introduce some popular usages of the `List` class and discuss the implications for simulation modeling.

The concept of a "linked list" may be familiar to C programmers. The motivating idea of a linked list is that one can develop a collection of entities by defining a series of structures that refer to each other. The first structure contains not only the information needed to describe a single entity a pointer to the next entity in the series. A linked list has a major advantage that it is flexible. Unlike an array that is allocated to allow N members, a linked list can grow indefinitely as members are added and it can shrink as members are deleted. The complicated problem is to make sure that the structures always correctly refer to each other as entities are added and removed.

The Swarm Collections library provides a protocol called `List` that provides the swarm program with all of the benefits of a linked list and none of the hassles. The usage of `List` objects seems rather informal. A list can be told to add an object at the end or the beginning, or to retrieve an object that is in a certain position in a list. Working together with another Swarm protocol, the `Index` protocol, the `List` object has a great deal of power and many uses. It should be noted that Swarm provides other, more structured "container" classes as well (`Array`, `OrderedSet`, `Map`, and so forth), but a treatment of them is left to a later chapter.

10.2. Basic `List` Syntax

A list is created by making a call to the `List` class object. Since there are probably not going to be any creation-time variables to set, the method used is typically create, rather than a **`createBegin/createEnd`** pair. In order to use method calls against the `List` object, one can import the header file `collections.h` from the Swarm library, and then this command will create a `List` object:

```
id nameOfSomeList;
nameOfSomeList = [List create: self];
```

Recall from the discussion of object creation that *self* refers to the memory zone in which the list is created. This is appropriate in a Swarm or GUISwarm instance, while other classes would use [self getZone] in place of *self*.

Once a list object exists, it can carry out many instructions. In the List protocol, methods that can add and remove either the first or last object in a list are defined. For example, to add an object called *fred* at the end of a list called *listOfDogs*, one could write:

```
[listOfDogs addLast: fred];
```

and, if it were necessary to remove the last object in the list, one could write:

```
[listOfDogs removeLast];
```

The object of type List is able not only to carry out the **addFirst:**, **addLast:**, **removeFirst:**, and **removeLast:** methods, it can also inherits methods from the Collections protocol. Some of the useful methods in the Collections protocol are:

- **getCount**: Use this to find out how many items are already in the list
- **begin: aZone**: This creates an Index object that can be used to traverse this list.
- **remove: aMember**. This will search through a list to find aMember and it will remove that object (and return it).
- **removeAll**: This take all elements out of the list, but it will not destroy the list or the elements in the list.
- **deleteAll**: Be careful: this removes the elements from memory as it clears the list

Lists have many uses in Swarm projects. The following sections discuss them, in turn. First, lists are used to manage collections of objects and schedule their activities in the model swarm layer of a simulation. Second, lists are used to pass information back and forth between levels of a simulation. Third, lists can be used by individual agents to keep track of their experiences and manage their information

10.3. Lists: Managing Objects in the Model Swarm

In the **swarmapps** package, one can find the **Hello World** example exercises. This exercise provides a good example of the way in which lists are used to organize the agents in a model swarm. In section three of the **Hello World** package, a list of people called *pplList* is created. Here is a skeleton

showing the important commands that create and use the `List` protocol in the model swarm level. The file is called `PplModelSwarm.m`.

```
@implementation PplModelSwarm

- buildObjects
{
  //...
  // build the list to keep track of the ppl
  pplList = [List create: [self getZone]];
  for (inci = 0; inci < numPpl; inci++)
   {
    Person * person;
    id name;
    // allocate memory for a temporary person
    person = [Person createBegin: [self getZone]];
    //...
    [person setWorld: pplList Room: room Party: self];
    //...
    person = [person createEnd];

    // add the person to the list of people
    [pplList addLast: person];
  }
}
- buildActions
{
  //...
  modelActions createActionForEach: pplList message: M(step)];
  //...
}
```

As in most Swarm examples, the list is created in the **`buildObjects`** method. The `List` class object is a "factory object," it can create instances that can answer to the `List` protocol. In this case, the list is called *`pplList`*.

In order to instruct the factory object `List` to manufacture an object that acts like a `List`, one would ordinarily have to import the `collections.h` header file. However, as in many Swarm examples, the `collections.h` file has already been included in a file that has been included in this file, and so an explicit import statement is not needed.

After an object that responds to the `List` protocol is created, then objects can be added onto that list. In this example, after *`pplList`* is created, then the **`buildObjects`** method proceeds into a for loop that creates the people objects. At the end of that loop, each person is added to the *`pplList`* by the command:

```
[pplList addLast: person];
```

The Swarm libraries take care of allocating memory and all the other details.

Once this list of people is created, what happens? In this case, the list of people becomes the central organizing element of actions that are to be scheduled. The object *modelActions* is told to go through the people list, one at a time, and cause each person to carry out its **step** method. The ins-and-outs of activity and schedule design are discussed elsewhere. This **createActionForEach** method works because the target is a Swarm collection item, the *pplList*, and the Swarm library knows how to traverse through the list of people.

10.4. Lists: Passing Information Among Levels in a Swarm Model

Simplified scheduling is not the only usage for lists. It is equally important that list objects can be used to quickly communicate a great deal of information between objects. This is done by creating methods that can get a list and pass it to another object.

In the PplModelSwarm.m file, for example, one finds this method:

```
- getPplList
{
  return pplList;
}
```

When another object needs a list of people, the PplModelSwarm is able to supply it.

This design is extremely convenient when it comes time to consider the observer swarm level of the simulation. The PplObserverSwarm.m file gets the list of people from the PplModelSwarm and uses that list to collect data in order to construct graphs. Consider the *avgFriendGraph* object, for example, which charts the average number of friends per person. The **buildObjects** section of PplObserverSwarm.m has this command:

```
[avgFriendGraph createAverageSequence: "avgNumFriends"
        withFeedFrom: [pplModelSwarm getPplList]
         andSelector: M(getNumFriends)];
```

The method **createAverageSequence:withFeedFrom:andSelector** is equipped to take a list of objects, ask each one to supply a piece of data (the **getNumFriends** returns an integer from the person object), and builds an average that is plotted. This powerful, easy method of passing information for presentation is possible because the various Swarm libraries are designed to work together. While the user could certainly ignore the List protocol and design her own setup for managing collections, doing so would indeed be costly because one would be forced to forfeit the convenient features of the other libraries that can handle Swarm List objects.

The ability to pass a list to the observer swarm in order to create a graph is just one benefit of Swarm `List` protocol. Note in the `PplModelSwarm` example that when people are created, one of the set messages (**`setWorld:Room:Party:`**) tells the individual person in which list it is currently residing. When that method executes, it sets the value of an instance variable called *`pplPresent`* inside the person. (Look at the code in `Person.m` to verify it!) Since each individual person has that list available, it can ask the list for information. For example, to find out how many other people are still in the list, the `Person` object can do this:

```
[pplPresent getCount]-1
```

which returns an integer equal to the number of objects in the *`pplList`* minus 1. The `Person` object does not have to do anything to update the *`pplPresent`* variable to reflect current conditions. Since the *`pplPresent`* variable is actually a pointer to the *`pplList`* as it currently exists in the `PplModelSwarm`, this is always "up to date". Some additional usages that the `Person` class might include require the creation of `Index` objects, which are introduced in the next section.

10.5. Lists: Organizing Repetitive Chores inside Objects

In the **Hello World** example, each instance of the `Person` class is aware of the *`pplList`* that exists in the `PplModelSwarm`. Inside the individual person, the name used to refer to that list is *`pplPresent`*. Because *`pplPresent`* refers to an object that conforms to the `List` protocol, and all `List` objects follow the `Collections` protocol, then a number of interesting features can be put to use.

Suppose the we want to have the person go through the list of people in the list and make a new list that includes all of the people in that list who have a lot of friends, say more than 3. In order to carry this out, code has to be designed to traverse through the *`pplPresent`* list, ask each one how many friend it has, and then if that person has more than 3, then add that person to another list.

One of the most interesting protocols in Swarm is the `Index` protocol. In mathematics, one might have seen a variable X_i, and the index variable i can range from 1 through the number of possible values. In Swarm, `Index` means much more than that. A Swarm `Index` is a "living, breathing" object that can be moved around in a list, and the `Index` can also respond to requests for information.

For new Swarm users, the most puzzling thing about the usage of `Index` is the creation process. `Index` objects are not created with the standard swarm **`createBegin`**/**`createEnd`** pair. Instead, any object from the `Collections` class, such as a `List`, can spawn an index by using the **`begin:`** method. In one step, the **`begin:`** method will create an object that conforms to the `Index` protocol and positions that index object before the first element of the collection. Here is an example of how the *`pplPresent`* list might create an index called *`pplIndex`*:

```
id <Index> pplIndex;
```

```
pplIndex = [ pplPresent begin: [self getZone]];
```

The first line declares the instance variable that will be the index. It is not necessary to include the protocol name <`Index`> in the declaration, so it might as well have been just `id pplIndex`. Some programmers prefer to include the extra information in the declaration because it clarifies the code and also may help to catch programming mistakes.

After it is created, the *`pplIndex`* can respond to messages. Many of the methods that `Index` objects can carry out will do two things at the same time: the `Index` will be positioned and the identity of the object at which the index currently resides will be returned. For example, consider this code that sets a variable called *`elementFromList`* equal to the next one, as provided by the index:

```
elementFromList = [pplIndex next];
```

When it is first created, the *`pplIndex`* is positioned at the edge of the collection, just before the first object in the collection. If we want the index to move to the next object, and give us a pointer to the next object in the list, it is done with that command. (As in C, collections are numbered beginning with the number zero).

It is common in Swarm examples to use the **`next`** method of the `Index` object in a while statement that cycles through the elements of a list. Here is a bit of code that would go through the list of people in **Hello World** and ask each one how many friends it has. And, if the number is larger than 3, then that object is added to a list *`popularPeople`* (which we assume is created somewhere else in the code).

```
id <Index> pplIndex = nil;
id         element  = nil;
int numberOfFriends;

pplIndex = [pplPresent begin: [self getZone]];
while ((element = [pplIndex next]) != nil)
{
  numberOfFriends = [element getNumFriends];
  if (numberOfFriends > 3)
    [popularPeople addLast: element];
}
[index drop];
```

This example uses a number of convenient features from the C language. One is that the conditions evaluated in logical statements are actually calculated. Hence, the conditional in the while statement causes the *`pplIndex`* to move to the next element, in the process setting the variable element equal to that object. As a result, inside the curly braces, the variable element can be used to refer to that particular element from the list. In this case, that object is asked to give us its number of friends.

The index object, *pplIndex* plays a vital role in this example. The index index is accessed inside the **while** statement so that we can cycle through the elements in a list. The while statement in the previous example will begin with the first element of the list, and one-by-one it will move through the *pplList*. What happens when it gets to the end? When it is positioned at the last element of the list, then the `[pplIndex next]` command will return *nil*. The logical condition is set so that the program exits the while loop at that point.

If one inspects a number of Swarm examples, one will find the while loop is constructed in slightly different ways, but the effect is the same. For example, the logical condition is sometimes written simply as (`[pplIndex next]`). This is allowed because of the convention that, as long as this does not return *nil*, then the while loop will continue. If that approach is used, instead of using element in the while loop, we replace all occurrences of element with `[index get]`, like so:

```
id <Index> pplIndex    = nil;
int numberOfFriends;

pplIndex = [pplPresent begin: [self getZone]];
while (([pplIndex next]))
{
  numberOfFriends = [[pplIndex get] getNumFriends];
  if (numberOfFriends > 3)
    [popularPeople addLast: [pplIndex get]];
}
[pplIndex drop];
```

This last change would cause a performance penalty because the *pplIndex* object is asked to evaluate and return on object three times.

It is hard to overstate the value of the `Index` protocol in working with Swarm lists. One especially important feature of `Index` is that it can be used to manage items in the list itself. That is, the index can do more than just point to objects. If an index is positioned at an object, and one wants to cut that object from the list, then the command `[pplIndex remove]` will get the job done. The index will automatically reorient itself, so that the next time the index receives the **next** instruction, it will point to the next valid member of the list.

Watch out for nil objects when using "while" loops

If you loop through a list, checking only that the index is not positioned over a nil object, your loop might end before you expect if there is a nil object in your list.

A variable of type id might be unintialized, or nil. Suppose that, through intention or error, an object *person1* has been set to nil, as in

```
person1=nil;
```

This could happen if, for example, the object referred to by the name person1 has been dropped, and the user is careful to set the name equal to nil in order to be safe.

Now suppose the program adds person1 to a list, and other (nonnil) objects are added as well. If the program creates an index and tries to loop through this list with the while construction described above, there will be a major problem. The loop will be executed, until the index object arrives at person1. Since person1 is equal to nil, then [pplIndex next] will return nil, *and the program will exit the while list* and continue with the next commands. If there is a danger that some of the objects in a list might be nil, and the programmer wants the loop to continue after "skipping over" the nil objects, then the best approach is a for loop that takes advantage of some symbols defined in the Swarm libraries. For each object in a list, the Index protocol's method **`getLoc`** will tell us whether the index is positioned in the list on a "Member." If the [index next] message causes the index to "step off the last" object in a list, then the return from that message is "End."

```
{
id <Index> pplIndex = [pplPresent begin: aZone];
id member;

for (member = [pplIndex next]; [pplIndex getLoc] == Member; member = [pplIndex next])
   {
    // do something with member ...
    }
        [index drop];
}
```

When it is created, the index is automatically positioned at the Start. The first argument in the for statement positions the index on the first member of the collection. The second argument says that the for loop continues as long as the returned value from **`getLoc`** is equal to the symbol Member. And after the loop is complete, the third argument says that the index is supposed to step to the next object in the list.

Be sure to drop index objects when you are finished with them

It is important to **`drop`** the instance of `Index` when its use is completed. That's accomplished by the `[pplIndex drop];` command in the last example. If this is forgotten, the index will continue to occupy memory and waste resources.

Chapter 11. Checking on a Swarm's progress: The Observer

11.1. Monitoring a Swarm

When a Swarm program is running in the GUI mode, what the user sees is controlled by the top level Swarm that we often call the observer swarm. The observer swarm adopts the `GUISwarm` protocol, which means that it has all of the features of a Swarm plus some "optional added extras." The file that contains the source that controls the user interface for a specific project may be called simply `ObserverSwarm.m`. In many examples, authors have customized the name of the file to include the name of their project, as in `HeatbugObserverSwarm.m` or `ForestModelSwarm.m`

The most prominent of the extra features of the observer swarm is the control panel. The control panel is the familiar set of buttons that can Start and Stop a swarm model. The control panel also can "step" the simulation through its paces one time-unit at-at-time using the Next button. The Save button on the control panel is intended to save the window positions of objects that are able to do so.

Apart from the control panel, what the user sees at run-time is completely dependent on the particular example that is being considered. It is probably safe to say, however, that if one stays within the Swarm library, without adding external support from the Graph library or other toolkits, then there two especially important kinds of display objects that can be created in `ObserverSwarm.m`. These two are:

- **The `ZoomRaster`.** In just about any of the common swarm applications, there is some sense of geometry or spatial position. The `ZoomRaster` graph is the tool that is used to represent the positioning of agents and other objects in that space.
- **The Data Display Graphs.** For the visual presentation of summary information, Swarm provides a set of tools for presenting information in graphic format. Two of the most common sorts are the histogram, which shows the relative frequency of various values occurring in a stream of data, and a line graph which displays the changes over time in one or more variables as a simulation progresses. These capabilities are provided by the Swarm protocols `EZDistribution` and `EZGraph`, respectively.

The following sections discuss the achitecture of these two classes of displays in greater depth. Most of the examples for discussion are taken from the **Arborgames** code provided by Melissa Savage.

11.2. Making a clickable `ZoomRaster`

There is no doubt that one of the most impressive aspects of a Swarm presentation is the visually intriguing movement of agents on a landscape. The ability to stop a simulation from the control panel

and then click on objects, open up displays that reveal their internal variables and allow them to be changed, is one of the main strengths of the Swarm library.

In order to introduce the way in which these `ZoomRaster` displays are created, we have to introduce a number of inter-linked Swarm toolkit items. Before we are done, we have to talk about objects created using the `space` library, as well as objects from the `gui` library. In the **Arborgames** simulation, there is a set of standard examples that quite nicely illustrate the vital steps. For emphasis, we now consider these elements individually.

1. **Create a `ColorMap`.** Swarm was first developed for the Unix operating system. Programmers who have worked in X will probably already know that the X server offers a long list of possible colors. If we want to access those colors, we can build a `ColorMap` object in Swarm. After it is defined, and commands are executed which draw on the screen, then the `ColorMap` object will control which colors are displayed.

   Here is an excerpt from the file `ForestObserverSwarm.m` in which an object, called *`colormap`*, is created and then told to remember that the numbers 25, 26,and 27 refer to the colors "white","LightCyan1" and "PaleTurquoise" which is defined deep in the bowels of the video display.

   ```
   colormap = [Colormap create: [self getZone]];

   [colormap setColor: 25 ToName: "white"];
   [colormap setColor: 26 ToName: "LightCyan1"];
   [colormap setColor: 27 ToName: "PaleTurquoise"];
   ```

   `ColorMap`s can have fancier items. For example, colors need not be referred to by simple names. Rather, each color can be referred to in a numerical format. All colors can be referred to by the intensity of their red, blue, and green components, for example. If one needs to assign the many available shades of red to the numbers between 100 and 150, it can easily be done with commands that use the RGB format. There is an example of such a use of the `ColorMap` protocol in the **heatbugs** source code.

2. **Create a `ZoomRaster`.** A `ZoomRaster` is a visual placeholder, a rectangular entity of a certain size. After trimming out some of the detail, the steps that create the `ZoomRaster` called *`forestRaster`* in **Arborgames** look like this:

   ```
   forestRaster = [ZoomRaster createBegin: [self getZone]];
   SET_WINDOW_GEOMETRY_RECORD_NAME (forestRaster);
   forestRaster = [forestRaster createEnd];

   [forestRaster setColormap: colormap];
   [forestRaster setZoomFactor: 4];
   [forestRaster setWidth: [forestModelSwarm getWorldSize]
      Height: [forestModelSwarm getWorldSize]];
   [forestRaster setWindowTitle: "The Forest"];
   [forestRaster pack];
   ```

This code should be viewed as foundation-building. The `ZoomRaster` object is created, and the macro **`SET_WINDOW_GEOMETRY_RECORD_NAME`** is executed. This means that, when the user clicks save on the control panel, the window position of the *`forestRaster`* object will be saved in a file in the user's account.

To briefly summarize the effect of the other commands, we note the following. The fourth line tells the new raster object to use the colormap we just created. The fifth line controls the magnification of the display, which in this case is 4. The sixth line asks the *`forestModelSwarm`* object to report back the horizontal and vertical dimensions of the grid on which trees exist and then uses those to set the width and height of the `ZoomRaster` object's display. The eighth line gives the display window a name and the last line, which tells the *`forestRaster`* to **`pack`** itself, causes the display to be initialized according to the settings we just provided.

3. **Map a Swarm Space object onto the `ZoomRaster`.** By itself, a `ZoomRaster` is just a nice looking set of edges around a blank background. In order to display things inside that window, we need to create a connection between the agents who live in the model swarm (and lower level swarms) and then display them in the observer swarm. This is done most commonly by telling each agent that it lives in a Swarm object known as a `Grid2d`. As the agent goes through its lifetime, one of its activities is to put itself at a position in the grid and then (possibly) erase itself from the old spot and put itself in the new spot.

   The Swarm protocol `Object2dDisplay` can handle the work of drawing the positions of agents in a `Grid2d` object on a `ZoomRaster`. In the **Arborgames** example, the *`forestRaster`* is used by an object called *`treeDisplay`* which connects the agents in the `Grid2d` to the graphical display.

```
treeDisplay = [Object2dDisplay createBegin: [self getZone]];
[treeDisplay setDisplayWidget: forestRaster];
[treeDisplay setDiscrete2dToDisplay:
[[forestModelSwarm getTheForest] getTreeGrid]];
[treeDisplay setObjectCollection:
[[forestModelSwarm getTheForest] getTreeList]];
[treeDisplay setDisplayMessage: M(drawSelfOn:)];
treeDisplay = [treeDisplay createEnd];
```

   This example is slightly more complicated than most, because the `Grid2d` object is not retrieved directly from *`forestModelSwarm`* , but rather from another object that is defined in the *`forestModelSwarm`* . Except for that wrinkle, this is a standard example. The `Object2dDisplay` protocol is told to use the *`forestRaster`* as its "display widget." It is necessary to tell the *`treeDisplay`* which `Grid2d` to use, and this chore is accomplished by the setDiscrete2dDisplay command.

   Why the **`setObjectCollection`** message and the **`setDisplayMessage`** are used is interesting and important. The `Object2dDisplay` protocol has a method called **`display`**, which can be put in a schedule by the user. When the display method is executed, the *`treeDisplay`* (since it follows the `Object2dDisplay` protocol) will send each of the agent-objects in the `Grid2d` a message telling it to draw itself in the *`forestRaster`*. How does it tell the object to draw itself? We tell it

how by passing it the selector for the agent-object's **drawSelfOn:** method. Each agent must be able to respond to a message of this sort:

```
[anAgent drawSelfOn: aRaster];
```

The program will crash if each agent that is positioned in the `Grid2d` is not able to respond to **drawSelfOn:**.

The message `setObjectCollection: [[forestModelSwarm getTheForest] getTreeList]` is not strictly necessary and the program will run without it. It may not run so quickly, however. Without this command, the *treeDisplay* will respond to the **display** message by searching in each possible position of the `Grid2d` and sending each object it finds the **drawSelfOn:** message. If the grid is large relative to the number of agents, then this might be a very slow process. The **setObjectCollection** method eliminates the need for *treeDisplay* to search through the whole grid. When the object collection is set, then the *treeDisplay* will simply go through the list of objects and tell each one to display itself.

4. **Tell the `ZoomRaster` Where to Send Mouse Clicks.** A `ZoomRaster` object is highly self-aware. If you stop a simulation and right-click on an object, you may see a probe display pop up. That does not happen by magic, of course. It is necessary to tell the raster that, when there is a certain kind of click, that it is supposed to pass that click to some other object that knows what to do with it. That's why there is a command like this in the **buildObjects** phase:

   ```
   [forestRaster setButton: ButtonRight
                    Client: treeDisplay
                   Message: M(makeProbeAtX:Y:)];
   ```

   The *treeDisplay* is told to make a probe for the object that exists at a particular point in the grid.

5. **Schedule the Display.** This is one of the aspects of Swarm that could use some standardization. In the schedule, one generally includes steps that erase the raster, then the `Object2dDisplay` is told to update itself by the **display** command, and then that display is drawn to the screen by telling the `ZoomRaster` to **drawSelf**.

   In a simple model, one in which we only have one `ZoomRaster` to update, then the schedule could be as simple. In the **buildActions** part of the code, one could create an `ActionGroup` like this:

   ```
   displayActions = [ActionGroup create: self];
   [displayActions createActionTo: forestRaster message: M(erase)];
   [displayActions createActionTo: treeDisplay message:M(display)];
   [displayActions createActionTo: forestRaster message: M(drawSelf)];
   ```

   (Of course, that action group has to be put into a schedule, which will probably execute it at each time point.) The **buildActions** method in **arborgames** is a bit more complicated than that since a large number of displays are managed.

6. **Make sure the Agents Put Themselves in the Grid!** Inside the code that creates the individual agents who are to be drawn on the grid, one must be careful to accomplish two things. First, the

`drawSelfOn:` method must be created. Second, if one wants to have a clickable `ZoomRaster` that allows agents to be probed, it is also vital to have the agents report their positions.

It is fairly standard in Swarm models to manage this by creating a `Grid2d` object in the model swarm level and then, when an agent is created, use a **`setWorld`** method to notify the agent where it lives. In **heatbugs**, for example, each heatbug has a **`step`** method that controls how it searches for heat and moves to find a better spot. When it has decided where to go, the heatbug puts "nil" at it spot in the grid where it used to be and then it puts itself at the new coordinates. Here is the relevant code from `Heatbug.m`:

```
  [world putObject: nil atX: x Y: y];
 [world putObject: self atX: newX Y: newY];
```

In the **Arborgames** example, the trees don't consciously move themselves. Rather, they are created and destroyed according to a set of rules that put them in a spot for a while. When a tree is created, it is added to the grid with this command that is in the `Forest.m` file:

```
- addTree: aTree atX: (int) xVal Y: (int) yVal
{
  [treeList addFirst: aTree];
  [treeGrid putObject: aTree atX: xVal Y: yVal];
  return self;
}
```

Trees don't move (so far as we know), so we only need to update this tree's position arises when the tree dies. The `Forest.m` file creates a class of methods common to the different kinds of forests, and then the subclasses like `MatureForest` are created to provide additional detail. There are methods that remove a tree from the simulation and take it off the grid. The trees that are supposed to die are added to a Swarm list called the *`exitQ`*. For each timestep, the forest tells each kind of tree to do its **`step`** method, which adds trees to the *`exitQ`* list, and then the forest's **`step`** method removes those trees from the grid. In the `MatureForest.m` file,

```
- step
{
  id aTree, index;

  [treeList forEach: M(step)];

  index = [exitQ begin: [self getZone]];
  while( (aTree = [index next]) )
   {
    [treeList remove: aTree];
    [treeGrid putObject: nil atX: [aTree getX] Y: [aTree getY]];
    [index remove];
    [aTree drop];
  }
  [index drop];
  return self;
}
```

11.3. Displaying Results in Graphs

The most commonly used graphs in Swarm are histograms, which display the frequency distribution of a variable, and line plots, which show changes over time in real-valued numbers. There are some little details that arise in some applications, but for the most part creating graphs is easy.

The Swarm protocol that can create line plots is called `EZGraph`. The essential steps require the user to create a graph object, and optionally to assign labels for various display attributes. For example, returning to the **Arborgames** simulation, one can create a graph showing the numbers of trees of various sorts. The first step is to create the graph object, in this case called *popGraph*.

```
popGraph = [EZGraph createBegin: [self getZone]];
SET_WINDOW_GEOMETRY_RECORD_NAME (popGraph);
[popGraph setTitle: "population"];
[popGraph setAxisLabelsX: "time" Y: "population"];
popGraph = [popGraph createEnd];
```

After the `EZGraph` object is in existence, then it can be instructed to prepare itself to plot some lines. A stream of numbers is thought of as a sequence, and internal to the Swarm library there is an object type called sequence that is used by the graph tools to keep track of the numbers they are to present.

When the graph object is told to create the sequence, it can be told to formulate a summary statistic and plot it. In the **Heatbugs** simulation, the aim is to plot a summary of the unhappiness of all bugs. The average level of unhappiness of all bugs is the chosen indicator. Here is a code excerpt that shows how an object called *unhappyGraph* is told to create a sequence for plotting:

```
[unhappyGraph createAverageSequence: "unhappiness"
              withFeedFrom: [heatbugModelSwarm getHeatbugList]
               andSelector: M(getUnhappiness)];
```

This uses the **`createAverageSequence:withFeedFrom:andSelector`** method. Note that the sequence is assigned the name "unhappiness". The quotation marks are needed because the name of the sequence is a character string. The *unhappyGraph* is told to take data from the list of bugs, which is found by asking the *heatbugModelSwarm* to get the list. Each bug in the list responds to a method **`getUnhappiness`**. The combined effect of these elements is to create the sequence which will collect the average values.

We hasten to point out that not all sequences need be averages. Output from individual objects can be plotted as well. For an example, we return to the **Arborgames** `EZGraph` object called *popGraph*. The population graph is intended to show how numbers for each sort of tree. There is a Swarm list of all species called *speciesList*. The following code iterates through the list of all species and tells the *popGraph* to create a sequence for each one.

```
for (i = 0; i < speciesNumber; i++)
{
```

```
  id aSpecies;
  aSpecies = [speciesList atOffset: i];
  [popGraph createSequence: [aSpecies getSpeciesName]
              withFeedFrom: aSpecies  andSelector: M(getCount)];
}
```

Each species is able to give its name (respond to **`getSpeciesName`**) and provide a count of the number of trees (respond to **`getCount`**). If some kind of mistake occurs, say a different kind of object is added into the *`speciesList`*, then the program will crash during the run (and there probably will also be a compiler warning).

The work to this point has created the graph object, and told it what to graph, but it does not cause the graph to be presented as the simulation runs. In order to see the plots, the commands have to be part of the observerSwarm's scheduled activity. As it turns out, an `EZGraph` has a very simple method called **`step`** that can do the necessary work, so somewhere in the **`buildActions`** method, a command such as this is required:

```
[displayActions createActionTo: popGraph message: M(step)];
```

This is often part of an `ActionGroup` that is scheduled to update all graphs and `ZoomRasters`.

Chapter 12. Probing and Displaying the Contents of Swarm Objects

Probes allow the user to dynamically interact with the objects in their simulation. As the simulation progresses, the user can observe and adjust the values of the instance variables. Furthermore, the user can cause objects to execute their methods, taking parameter values or input specified by the user during the simulation. generating method calls. The main appeal of this approach is that these interactions are not hardwired into the program code, but occur due to user-generated requests. This interactive process is managed by objects and methods that are, for the most part, hidden from the user. Still, the interaction can be customized easily.

12.1. What's a Probe?

Anyone who has run **Heatbugs** (or any of the demo programs, for that matter) has seen a probe display. It is a rectangular window that has rows which list attributes of the object being displayed. The data being displayed may be gathered from a high level object, such as the observer swarm or the model swarm, or it may be collected from an individual agent. Almost all Swarm projects have a probe display for the observer and model swarms because starting values for the parameters can be set with those displays. Probe displays for individual agents are typically created during a run by user interaction with the Swarm program (for example, by clicking on a "clickable `ZoomRaster`", as discussed in the previous section).

The key to this capability is the probe. A probe is an object that can gather information from one object and relay it to other objects, including displays on the screen. Swarm provides two kinds of probes. The Swarm class `VarProbe` extracts the value of a specific instance variable from an object. The second kind of probe is provided by the `MessageProbe` class. The `MessageProbe`. A message probe gives the user the ability to access methods inside an object–to send messages to it, in other words:

- **`VarProbe`.** Probes an instance variable. A variable probe appears to the user in a window with the name of the instance variable and a space that may display the value of the variable (or show a blank or "nil"). Variable probes can display the values of integers and floating point numbers, as well as information about the identity of object variables. Variable probes do not display the contents of C arrays or structs.
- **`MessageProbe`.** Probes a method. In the same window where the Variable Probe is shown, there may be "buttons" that have the names of methods on them. These buttons will be executed when they are depressed. If a method takes arguments, there will be spaces in which the user can enter them. This can cause agents to change their course of action during a simulation run.

Figure 12-1. Combining two `varProbe` and one `messageProbeS` on a `probeDisplay`



There are two main uses for probes: they can be fed into data-collection objects and serve as interfaces to the objects about which data is being collected (thus keeping the data-collection objects as general as possible) - the `Averager` class, for example, directly subclasses `MessageProbe`. Or, they can be used in order to generate a GUI to the individual objects in the simulation (the more common usage).

There is a middle-level object between the probe display that appears on the screen and the individual probes. It is the `ProbeMap`. A probe map is a set that collects up all of the probes for a given object. The probe display does not manage individual probes, but rather it manages probe maps. As we shall see, then, most of the detail in tailoring probe displays ends up in steps that add or remove probes from the probe map.

12.2. Managing Probe Displays

The appearance of the probe display can be custom-tailored by the programmer. In order to understand the effect of customization, it is probably best to begin with an understanding of the "default" appearance.

The default probe displays for a simulation can be created quite easily. In the `HeatbugObserverSwarm.m` file, for example, one finds these lines:

```
CREATE_ARCHIVED_PROBE_DISPLAY (heatbugModelSwarm);
CREATE_ARCHIVED_PROBE_DISPLAY (self);
```

These are macro commands that cause actions inside the Swarm kernel to create the default probe displays for the model swarm and observer swarm, respectively. That is all that is required to create the default probe displays.

It might be a good exercise for the user to check this for herself. Leave those macro lines in `HeatbugObserverSwarm.m`, and comment out everything else to do with probes in that file and also in `HeatbugModelSwarm.m`. When heatbugs is executed, the user will see that the default probe display presents a list of the instance variables of the object and, if their values are set at start time, those values will be displayed as well.

This bare-bones setup will not automatically update the display as the simulation proceeds. It presents only a snapshot of the creation-time settings. Many variables that have no value set before time 0 will show blanks or the word *`nil`* and that will never change.

If one wants the probe pisplay to be updated, then an update command has to be included in the schedule. In the **`buildActions`** method of `HeatbugObserverSwarm.m`, this is the command that will cause the updating to occur (presumably, it was commented out in the bare-bones test described above):

```
[displayActions createActionTo: probeDisplayManager message:
M(update)];
```

The *`probeDisplayManager`* is a global object and when it is told to update in the observer swarm's schedule, it will update the probes of objects in all other levels of the simulation.

All of this works because the Swarm kernel provides a great deal of functionality that the user may never need to inspect or worry about. Most importantly, the object *`probeDisplayManager`* is not explicitly created by the user. Rather, it appears automatically in any Swarm program that has the GUI mode turned on in its `main.m`. The *`probeDisplayManger`* is the object that receives messages to create displays for various objects, such as the macro statements above.

The default probe display for an object includes only the probes for the instance variables of the object. It has no buttons to click and execute methods inside the object (i.e., it has no message probes). If one wants the message probes, there are two alternatives. While the program is running, a right-click on the object's name button in the top-left part of the display will cause the message probes to be displayed. A second alternative is to change the macro used to create the probe displays. Use these macro commands instead:

```
CREATE_ARCHIVED_COMPLETE_PROBE_DISPLAY (heatbugModelSwarm);
CREATE_ARCHIVED_COMPLETE_PROBE_DISPLAY (self);
```

This will cause the probe display to include all instance variables and methods.

12.3. How to Customize Probe Displays

Why might one want to customize the display? Well, frankly, the default probe display may look ugly. It may include lots of variables the user does not want to see. There are some instance variables, such as C arrays, that cannot be probed, and so their inclusion in a probe display is uninformative. Swarm is designed to allow the user to pick and choose which variables ought to be included in the display. There are a number of strategies for customizing, one of the standard strategiew uses an object called *probeLibrary*.

Like *probeDisplayManager*, the *probeLibrary* is a global object provided by the Swarm kernel. Customization is achieved by writing code that communicates back and forth from objects to the *probeLibrary*. In short, the programmer "checks out" a unique, shared copy of a `Probe`/`ProbeMap` from the *probeLibrary* object (of class `ProbeLibrary`) provided by the kernel. By shared we mean that a similar request made at a different point in the code, will return a reference to the very same probe instance.

Here is a skeleton example of the commands that can create a customized probe display using this approach.

Example 12-1. Generating a *probeMap*

To generate a *probeMap* for an instance of the class `Agent` called *agent*, which consists of two fields: one `VarProbe` for the instance variable *someIVar* and one `MessageProbe` for the message **someMessage**, use the following:

```
probeMap = [EmptyProbeMap createBegin: self];
[probeMap setProbedClass: [self class]];
probeMap = [probeMap createEnd];

[probeMap addProbe: [probeLibrary getProbeForVariable: "someIVar"
inClass: [agent class]]];
[probeMap addProbe: [probeLibrary getProbeForMessage: "someMessage"
inClass: [agent class]] setHideResult: 1]];

[probeLibrary setProbeMap: probeMap For: [agent class]];
```

Don't forget to execute the **CREATE_PROBE_DISPLAY** for this object in the observer swarm.

In the file `HeatbugModelSwarm.m`, one can find a fully fleshed out example of these steps.

```
probeMap = [EmptyProbeMap createBegin: aZone];
[probeMap setProbedClass: [self class]];
probeMap = [probeMap createEnd];
```

```
[probeMap addProbe: [probeLibrary getProbeForVariable: "numBugs"
           inClass: [self class]]];
[probeMap addProbe: [probeLibrary getProbeForVariable: "diffuseConstant"
           inClass: [self class]]];
[probeMap addProbe: [probeLibrary getProbeForVariable: "worldXSize"
           inClass: [self class]]];
[probeMap addProbe: [probeLibrary getProbeForVariable: "worldYSize"
           inClass: [self class]]];
[probeMap addProbe: [probeLibrary getProbeForVariable: "minIdealTemp"
           inClass: [self class]]];
[probeMap addProbe: [probeLibrary getProbeForVariable: "maxIdealTemp"
           inClass: [self class]]];
[probeMap addProbe: [probeLibrary getProbeForVariable: "minOutputHeat"
           inClass: [self class]]];
[probeMap addProbe: [probeLibrary getProbeForVariable: "maxOutputHeat"
           inClass: [self class]]];
[probeMap addProbe: [probeLibrary getProbeForVariable: "evaporationRate"
           inClass: [self class]]];
[probeMap addProbe: [probeLibrary getProbeForMessage:
                                    "toggleRandomizedOrder"
                                  inClass: [self class]]];
[probeMap addProbe: [probeLibrary getProbeForVariable: "randomMoveProbability"
           inClass: [self class]]];
[probeMap addProbe: [[probeLibrary getProbeForMessage: "addHeatbug:"
            inClass: [self class]]
       setHideResult: 1]];

[probeLibrary setProbeMap: probeMap For: [self class]];
```

As in the generic example, in the **heatbugs** case the user follows a three step procedure that puts a customized probe map in place of the standard "variable probes only" default.

1. A new object called *probeMap* is created. The *probeMap* is an instance of the the Swarm class EmptyProbeMap. Next we customize the probe map and pass it to the display mechanism.
2. One-by-one, tell *probeMap* to add probes for individual variables and messages, and those probes are retrieved from the *probeLibrary*.
3. Tell the *probeLibrary* that, when it creates a probe display for this object, to use this special object*probeMap* rather than the default.

It is important to understand how this customization fits in with the default probe map. The *probeDisplayManager* creates a widget for every object that you tell it to. Unless you tell it otherwise, it assumes that the widget for every object is be based on the "default probemap" which includes probes for all instance variables, no message probes. If you alter the probeMap by the methods we have been discussing, you are replacing the generic "has it all" probeMap with a customized probeMap. If you right-click on the object name button in a customized probeMap, what pops up is a probe display based on the complete probeMap specification, a map in which all variables and methods are listed.

The procedure outlined above is clear and methodical. It is also open to different kinds of customization. If there is no need for customization of individual probes, there is a "shortcut" that can be used to get most of this work done. Swarm has a class called `CustomProbeMap`. The `CustomProbeMap` can create the probeMap and fill it with the desired probes. Here is an example as it would appear in the **heatbugs** model.

Example 12-2. Non-verbose *probeMap* creation

```
probeMap = [CustomProbeMap create: aZone forClass: [self class]
                              withIdentifiers: "numbugs",
                              "diffuseConstant", "worldXSize",
                              "worldYSize","minIdealTemp",
                              "maxIdealTemp","minOutputHeat",
                              "maxOutputHeat", "evaporationRate",
                              "toggleRandomizedOrder"
                              "randomMoveProbability",":",
                              "addHeatbug:", NULL];

  [probeLibrary setProbeMap: probeMap For: [self class]];
```

The last argument to the method **`create:forClass:withIdentifiers:`** is basically a set of character strings that are strung together and used inside the Swarm library to do the work of creating the individual probes. The colon separates the variable probes from the message probes. Notice the inclusion of `NULL` at the end of the input, which signals the end of the input to the `CustomProbeMap`.

This method will not allow customization of individual probes, so the **`setHideResult:1`** command that appears in the **heatbugs** example cannot be included. In order to get specialized probes of that sort, we could break this into two steps, one that creates the *`probeMap`* with the default probes and then another which adds the special probes. Consider this:

```
probeMap = [CustomProbeMap create: aZone forClass: [self class]
                              withIdentifiers: "numbugs",
                              "diffuseConstant", "worldXSize",
                              "worldYSize","minIdealTemp",
                              "maxIdealTemp","minOutputHeat",
                              "maxOutputHeat", "evaporationRate",
                              "toggleRandomizedOrder"
                              "randomMoveProbability",
                               NULL];
   [probeMap addProbe: [[probeLibrary getProbeForMessage: "addHeatbug:"
      inClass: [self class]]
          setHideResult: 1]];

   [probeLibrary setProbeMap: probeMap For: [self class]];
```

12.4. Controlling Precision of Display

This section deals with the control of the precision of display of floating point number on `ProbeDisplay`s.

12.4.1. Global setting of precision

There are two types of global precision setting via :

- **`-setDisplayPrecision:`** `(int)` *`nSigFigsSaved`* Sets the number of significant figures for floating point (and double-floating) numbers diplayed on a GUI widget. Currently this is only implemented for VarProbes. The display uses the %*g sprintf-style formatting, which can vary slightly from implementation to implementation. If you set the number of significant figures to 3, then a float of value of 0.6344346 is displayed as 0.634 on the GUI widget.Note that this in no way affects the underlying stored value of the floating point number.
- **`-setSavedPrecision:`** `(int)` *`nSigFigsSaved`* Sets the global default for the saving of floats through `ObjectSaver`. All objects with floats and doubles as instance variables are saved with the precision specified by this method. This is *independent* of the displayed precision of the same instance variable on a GUI widget.

To actually initialise these defaults: in the top level swarm, you should add the calls to the global *`probelibrary`* instance (which is actually created by the **`initSwarm`** call in main) during the -createBegin method (this sets the precision in the global instance, *before* any probes are checked out of the instance. If neither method is called on *`probeLibrary`*, then the precision defaults to six significant figures in both cases.

Example 12-3. Global setting precision in `HeatbugObserverSwarm.m`

```
+ createBegin: aZone
{
   HeatbugObserverSwarm * obj;
   id <ProbeMap> probeMap;

   [...]

   probeMap = [EmptyProbeMap createBegin: aZone];
   [probeMap setProbedClass: [self class]];
   probeMap = [probeMap createEnd];
        // set the display defaults
   [probeLibrary setDisplayPrecision: 3];
        // typically saved precision would be higher than displayed precision
    // for statistical and data analysis purposes
   [probeLibrary setSavedPrecision: 10];
```

```
    // Add in a bunch of variables, one per simulation parameters
    [probeMap addProbe: [probeLibrary getProbeForVariable: "displayFrequency"
    inClass: [self class]]];
    [...]

    // Now install our custom probeMap into the probeLibrary.
    [probeLibrary setProbeMap: probeMap For: [self class]];
    return obj;
}
```

12.4.2. Setting Precision for Individual Probes

The formatting for an individual probe can be set directly, using a sprintf-style formatting string. Typically, `customProbeMaps` are created in the **`+createBegin`** factory method for a `Swarm` or a `SwarmObject`. To set the formatting for a floating point probe, the method from `VarProbe` is used:

- **`-setFormatFloat:`** `(const char *)` *`floatFormat`* is applied to the instance of the `VarProbe` "checked-out" of the global *`probeLibrary`* instance. The sprintf-formatting string can "over-ride" the "%g" format set by the global precision (as above) (Typically "%g" chooses between the "%f" and "%e", depending on the size of the exponent - which is implementation-dependent - this method allows you to explicitly set the type of display).

In the following example, it is desired that the number of significant figures for the floating point variable **`randomMoveProbability`** is three (3). Currently (Swarm 2.0.1) this is only works for `VarProbes` and not `MessageProbes`, as yet.

Example 12-4. Setting precision for individual probes in `HeatbugModelSwarm.m`:

```
+ createBegin: aZone
{
    HeatbugModelSwarm * obj;
    id <ProbeMap> probeMap;
    id floatProbe;

    [...]
         // the -setFloatFormat is applied to the probe which is
     // "returned" from the call to probeLibrary
    floatProbe = [[probeLibrary getProbeForVariable: "randomMoveProbability"
    inClass: [self class]]
    setFloatFormat: ".3f"];

    // now we have the probe - put it back into the customMap
    [probeMap addProbe: floatProbe];
```

```
    [...]
    return obj;
}
```

Or, more compactly:

```
+ createBegin: aZone
{
  HeatbugModelSwarm *obj;
  id <ProbeMap> probeMap;

  [...]

  [probeMap addProbe: [[probeLibrary getProbeForVariable: "randomMoveProbability"
  inClass: [self class]]
  setFloatFormat: "%.3f"]];
  [...]
  return obj;
}
```

Part III. Advanced Topics

Chapter 13. Anything C can do, Swarm Can Do Better

Any programming statements that will work in C can also be used in a Swarm program. Hence, if one needs access to a programming library that can be used in C, one can also access that library in Swarm. Furthermore, functions written for C programs can be integrated into Swarm code.

13.1. Managing command line parameters

One of the obscure and difficult parts of C programming is designing a program to handle command line arguments. The *argc* and *argv[]* approach is difficult to manage. Swarm has built-in tools to handle this problem.

If you compile a Swarm program, you "automatically" get some built-in command line parameters. You can see what they are when you type the program's name, followed by `-help`. Here is some output from the heatbugs program:

```
$ ./heatbugs -help
Usage: lt-heatbugs [OPTION...]

-s, -varyseed             Run with a random seed
-b, -batch                Run in batch mode
-m, -mode=MODE            Specify mode of use (for archiving)
-t, -show-current-time    Show current time in control panel
-no-init-file         Inhibit loading of ~/.swarmArchiver
-?, -help                 Give this help list
-usage                Give a short usage message
-V, -version              Print program version

Mandatory or optional arguments to long options are also mandatory or optional
for any corresponding short options.
```

If you type a command line like

```
$ ./heatbugs -s -t
```

then Swarm will use a random number seed that is based on the system's clock and the display of the control panel will show the time. As a result, the random number stream used in the program will be different each time you run the program.

A person might want to add command line parameters to their Swarm code if they want to automate the processing of many simulation runs. For example, if one wanted to make a simulation run 50 times for each setting of a particular parameter value, then one would need to design a way to pass that particular parameter value from the command line. The repetition of the program can be managed by a user-created

script (written in some language like Perl, for example), or with a simulation tool like Drone (http://drone.sourceforge.net), developed by Ted Belding of the Center for the Study of Complex Systems at the University of Michigan.

If the user wants to pass additional parameters in the command line, Swarm has built in procedures that make argument processing a bit easier than using the command line processing available in C. This functionality is found in Swarm's `Arguments` protocol. The details of the usage of `Arguments` are explained quite well in the *Reference Guide to Swarm*. Rather than explain every detail, we choose here to explain one worked example[1].

The first step is to edit the `main.m`. Add an import command for our object that will manage the parameters:

```
#import "MyParameters.h"
```

and then change the **`initSwarm`** command to this:

```
initSwarmArguments (argc, argv, [MyParameters class]);
```

This change tells the swarm kernel to look in your class called `MyParameters` for information about how to process the command line arguments.

Next, write the files `MyParameters.h` and `MyParameters.m`. Here they are:

```
//Parameters.h
#import <defobj/Arguments.h>

@interface MyParameters: Arguments_c
{
  int numBugs;
}

- (int)getBugArg;
@end

//Parameters.m

#import "MyParameters.h"
#import <stdlib.h>

@implementation MyParameters
```

1. This example is available in full in the package ParameterHeatbugs.tar.gz (http://lark.cc.ukans.edu/~pauljohn/Swarm/MySwarmCode/ParameterHeatbugs.tar.gz). All of the changes described here begin with the **Heatbugs** application distributed in the package swarmapps-2.1.tar.gz (ftp://ftp.swarm.org/pub/swarm/swarmapps-2.1.tar.gz).

```
+ createBegin: aZone
{
 static struct argp_option options[] = {
     {"numBugs",'n',"N", 0, "Set numBugs", 5},
     { 0 }
 };

 MyParameters *obj = [super createBegin: aZone];

 [obj addOptions: options];

 return obj;
}


- (int)parseKey: (int)key arg: (const char*)arg
{
  if (key == 'n')
  {
    numBugs = atoi(arg);
    return 0;
  }
  else
  return [super parseKey: key arg: arg];
}

- (int) getBugArg
{
 if (numBugs)
  return numBugs;
 else
  return -1;
}

@end
```

The **`parseKey:arg:`** method indicates that when the key is *n*, meaning the command line passed `-n` after the program name, then it the corresponding argument is taken and converted to an integer (by the **`atoi`** function, the reason for which the include of `stdlib.h` is needed). When another class tells our parameter manager class to **`getBugArg`**, then the command line argument will be returned if there was one, otherwise it will return -1.

The only interesting wrinkle arises when it is necessary to retrieve the value of *`numBugs`* from the parameter class. When the Swarm kernel is initialized, it creates an object called *`arguments`*. Any commands that one wants to address to the `MyParameters` class are instead addressed to *`arguments`*. For example, when we want the `HeatbugModelSwarm.m` class to set the initial values, we add an import statement for `MyParameters.h` and then we make calls against the arguments class. The syntax is like this:

```
+ createBegin: aZone
{
  HeatbugModelSwarm *obj; id
```

```
<CustomProbeMap> probeMap; obj = [super createBegin: aZone];

// Now fill in various simulation parameters with default values or
// grab values from MyParameters.

obj->numBugs = 10;
if (([arguments getBugArg] != -1))obj->numBugs=[arguments getBugArg];
   [and so forth]
```

This example sets the number of bugs equal to 10, but if the value is included in a command line option, then that value is incorporated.

Once the `Makefile` is touched up to include references to `MyParameters`, then the program compiles and hthe output from the help command indicates the new parameter is recognized:

```
$ ./heatbugs -help
Usage: lt-heatbugs [OPTION...]

-s, -varyseed             Run with a random seed
-b, -batch                Run in batch mode
-m, -mode=MODE            Specify mode of use (for archiving)
-t, -show-current-time    Show current time in control panel
-no-init-file             Inhibit loading of ~/.swarmArchiver
-n, -numBugs=N            Set numBugs
-?, -help                 Give this help list
-usage                    Give a short usage message
-V, -version              Print program version

Mandatory or optional arguments to long options are also mandatory or optional
for any corresponding short options.

Report bugs to bug-swarm@swarm.org.
```

It does not make any difference whether the user starts the program with the command:

```
$ ./heatbugs -n 444
or
$ ./heatbugs -numBugs=444.
```

In either case, the probe map will indicate the initial number of bugs is 444.

13.2. Using C Functions in Swarm

The fundamental rules of C programming apply in Swarm. Perhaps most importantly:

- **Use prototypes for functions used in many files.** If a function is defined in one file, and it is to be used in another, then there must be a prototype in the header file and that header must be included in each file that makes calls on the function.
- **Type functions as "static" if they are used only in one file.** When a function's use is confined to the file in which it is called, use static to type it in order to reduce the danger of confusion that might result if other files use functions of the same name.

If a function is defined at the top of a source code file–after the includes and imports but before the implemenation line, then that function can be called anywhere in that file. If the function is not used in any other files, then there is no need to put a prototype for it in the header file and the declaration of the function should start with "static".

A function can also be defined *inside a method!*. It looks a bit peculiar when functions crop up inside Objective C methods, but there is nothing wrong with doing so. Of course, when a function is defined inside a method, then its scope is sharply restricted. That function can be called only inside that method.

There are some occasions in which is is extremely handy to define functions inside methods. Two particulary useful aspects of this practice are as follows. First, Objective C calls to `self` can be made in such functions. If a function needs some value, and it intends to get it by calling a get method such as `[self getThatNumber]` it will work as long as the function is defined inside a legitimate Objective C method. If the function is located at the top of the file, before the implementation statement, then the term `self` will have no meaning and the program will not compile.

The second useful aspect is of this practice is that one can have several different functions with the same name if those functions are set inside Objective C methods. It may seem hard to imagine situations in which this would be useful, but they do arise.

Suppose inside a class there are two methods and each makes use of a function from the standard C libraries. If the function expects to have some other user-defined function available when it is run, then the user can customize that user-defined function inside each method. To be a bit more concrete, consider the GNU C library's binary search tree defined in the header file `search.h`. The function **`tsearch`** (version 2.1) has this prototype:

```
void * tsearch(const void *key, void ** rootp, int (*compar) (const void *, const void *) );
```

The **`tsearch`** function checks to see if a node already exists by using a comparison function. If an equal node exists, then tsearch returns that node. If no such node exists, **`tsearch`** adds the node to the tree. Note that the comparision function used in the tsearch must be included as the last argument.

The problem may arise that one wants to use different comparison functions when working with a single tree. Once a tree is created with a comparison function called **`compare_node`**, then all calls on the tree must use a comparison function with the same name. Perhaps there is some slight wrinkle to be introduced when deciding whether one node is equal to another when they are being inserted and when they are being printed out or removed. By defining several compare functions, one inside each method that makes use of the tree, one can acheive the desired level of specialization.

13.3. Examples of Useful Functions: `getInt` and `getDouble`

Functions can come in handy in many cases, but let's begin with a particularly useful example that continues with the project of managing parameters. Suppose you have a Swarm file `MyParameters.m` that sets the values of many parameters. Suppose there are 50 ints and 40 doubles. You may go insane writing methods to get each parameter specifically by name.

There is no need to write specific get methods for each variable because a combination of methods from Swarm and C can be used to create "generic" get functions that will retrieve the values. In the top part of the `MyParameters.m` file, between the include statements and the implementation statement, the functions are defined thus:

```
//MyParameters.m
[import statements here]

id
makeProbe (id obj, const char *ivarName)
{
  id probe = [VarProbe createBegin: [obj getZone]];

  [probe setProbedClass: [obj getClass]];
  [probe setProbedVariable: ivarName];
  return [probe createEnd];
}

double
getDouble (id obj, const char *ivarName)
{
  id probe = makeProbe (obj, ivarName);
  double ret = [probe probeAsDouble: obj];
  [probe drop];
  return ret;
}

int
getInt (id obj, const char *ivarName)
{
  id probe = makeProbe (obj, ivarName);
  int ret = [probe probeAsInt: obj];
```

```
  [probe drop];
  return ret;
}

@implementation MyParameters
[and so forth...]
```

These functions are made available to calls in other files by declaring them in the header file, `MyParameters.h`. The declarations are inserted between the import statements and before the interface declaration.

```
//MyParameters.h
[import statements here]
id
makeProbe (id obj, const char *ivarName);

double
getDouble (id obj, const char *ivarName);

int
getInt (id obj, const char *ivarName);

@interface MyArguments: Arguments_c
[And so forth...]
```

In any file that includes `MyParameters.h`, one can retrieve the value of a parameter by using the **`getInt`** and **`getDouble`** functions. For example, if there is an instance variable defined in `MyParameters` called *`maxHeat`*, it can be retrieved by the following call to the function:

```
getInt(arguments, "maxHeat");
```

This call is made against the object called *`arguments`* because, as mentioned in the previous section, the instantiation of `MyParameters` is named *`arguments`* inside the Swarm kernel.

13.4. Dynamic Memory Allocation and Swarm Zones

Veteran C programmers have no doubt tangled with the problem of dynamic memory allocation using **`malloc`** or **`calloc`**. In its `Zone` protocol, Swarm has methods that can be used in place of these functions. While there is nothing inherently wrong with using the built-in C functions to allocate memory, there are some advantages in the Swarm methods that may reduce the danger of memory leaks.

Swarm users who are not familiar with dynamic memory allocation may wish to consult a C manual. In a nutshell, the problem is this. If one wants to create an array, the elementary way to do so is to declare the array like so:

```
int array[5];
```

This creates an array of 5 integers. When the program runs, memory is set aside where values can be placed into and retrieved from the array.

This standard approach only works when the user knows that there will be exactly 5 elements in the array. What if some calculations are done during the run of the program and then it is necessary to create an array that depends on that calculated number? This is the kind of case for which dynamic memory allocation is needed. If, during a run, some number N is calculated, and then one needs to have an array of length N, then the program can grab some of the system's physical memory and use it.

Dynamic memory in Swarm can be accessed by the methods **`alloc:`** and **`allocBlock:`** in Swarm's `Zone` protocol. First, it is necessary to declare a pointer that will serve as the address of the dynamically allocated memory. Second, the memory is allocated to that pointer. Here is an example from a class called Point, which is used to dynamically allocate space for arrays of real numbers.

```
//Point.h
@interface Point: SwarmObject {
        double * position;
        int spaceSize;
 }

-buildObjects;
-(void) drop;
-setSpaceSize:(int) size;


//Point.m
#import Point.h

@implementation Point

- buildObjects
{
  //position = xmalloc(spaceSize * sizeof(double));
  //Test to make sure the memory was allocated. If not, exit immediately
  //if(position==NULL) exit(8);
   position = [[self getZone] allocBlock: spaceSize * sizeof(double)];
   return self;
}
- (void)drop
{
  //free(position);
  [[self getZone] freeBlock: position blockSize: spaceSize * sizeof(double)];
  [super drop];
}

- setSpaceSize: (int)size
{
  spaceSize=size;
  return self;
```

```
}
```

Note that for the C programmer's information there are commented-out versions of **malloc** and **free** calls.

When a user wants to use the `Point` class to create a new `Point`, which has an array of doubles inside it, then an instance of the `Point` class is created in the usual Swarm way. Then the size is set, and then the `Point` is told to build its objects, which allocates the dynamic memory. For example:

```
id  newPoint;

newPoint=[Point createBegin: [self getZone];
newPoint= [newPoint createEnd:];
[newPoint setSize: N];
[newPoint buildObjects];
```

After that space is allocated, then it can be used by methods in the `Point` class as if it were an array. The reason that one can treat the pointer to the dynamically allocated memory as if it were an array is found in the fundamental similarity of pointers and arrays in C. Interested research should consult the C manuals for a comparision of pointers and arrays. To consider a usage example, a method could be written to fill the array with random numbers between 1 and 5.

```
- fillRandomly
{
  int i;

  for(i = 0, i < spaceSize; i++)
  {
    position[i]=[uniformDblRand getDoubleWithMin: 1 withMax: 5];
    return self;
  }
}
```

A memory leak is a flaw in a program which causes it to access dynamic memory and then "waste" it by dropping all references to it without letting the operating system know that the memory is no longer needed. In C, the **free()** function tells the operating system that the memory can be reallocated to other purposes. If the programmer forgets to free memory that is no longer needed, then the memory demands of the program will expand with each new allocation, taking memory that might be used by other applications and eventually causing the program to crash.

In Swarm, memory allocated with **allocBlock:** can be freed explicitly with the **freeBlock:** method. The usage of **freeBlock:** is illustrated in the **drop** method of the `Point` class. This **drop** method is used only to free the dynamic memory, but it would also explicitly drop any Swarm objects that were created inside the object. The topic of designing programs to avoid memory leaks is discussed further in the next section.

13.5. Dropping Unused Objects

Most Swarm objects will respond to the **drop** message. This message causes them to execute whatever commands are necessary to remove themselves from memory. When objects created by user-created classes are no longer needed, they should be dropped as well. It is vital, therefore, to customize the drop method of a user-defined class so that all objects created within the object are explictly dropped.

In the `Point` class, the super class's **drop** method is inherited from `SwarmObject`. However, if we were to tell a `Point` object to drop, it would not automatically drop the dynamically allocated memory referred to by the pointer *position*. Similarly, any other Swarm objects allocated in the `Point` object would not be dropped. In order to be sure these are dropped, the drop method should be overridden and customized. When that method is overridden, it is vital to make sure the super class's drop method is executed. That is the reason that the `Point` class's drop method begins with [super drop]. Any objects that have been allocated in `Point`, such as the memory devoted to the variable *position*, should be taken care of at that stage. Any Swarm objects that have been created, such as lists, list indexes, or other objects should be dropped in the drop command.

Many users think that there ought to be an "automatic" way to drop all objects that exist inside an object. This would certainly be convenient, since rewriting a drop method to make sure all objects are correctly disposed of can be tedious and possibly error-prone. While there is no such automatic object-dropping facility, there is a way to design Swarm code that comes close.

To make sure that all objects inside another object are dropped, users might consider a strategy that uses `Zone`s more carefully. Instead of following the `Zone` usage examples provided by most Swarm applications, consider instead creating agents inside separate memory zones. When a zone gets the drop method, *it does drop all objects inside it!*

Here is how such a program might be designed. Suppose that agents are to be created in the model swarm by a for loop. The usual approach would create the objects in the model swarm itself, using the `Zone` of the model swarm.

```
//in the buildObjects method of ModelSwarm.m
for(i=0;i < numAgents;i++)
 {
   id agent;
   agent=[Agent createBegin: self];
   agent=[agent createEnd];
   [agentList addLast: agent];
 }
```

Suppose that instead of creating the instances of the class `Agent` inside the model swarm itself, we create a `Zone` object each time through the loop, and then create the agent inside that zone. For example,

```
//in the buildObjects method of ModelSwarm.m
for(i = 0;i < numAgents; i++)
{
  id agent, newZone;
```

```
  newZone=[Zone create: self];
  agent=[Agent createBegin: newZone];
  agent=[agent createEnd];
  [agentList addLast: agent];
}
```

The `Agent` class might create all kinds of objects, and we could use the method described above to write a drop method for the `Agent` class. However, this second approach has simplicity on its side. If it is necessary to drop an agent, instead of using the command `[agent drop]`, we instead find out what the agent's zone is, and drop that:

```
 //first, suppose you want to remove an agent named "agent".
//Remove references to agent from the list
 [agentList remove: agent];
 //Then drop that agent's zone
 {
   id agentZone;
   agentZone=[agent getZone];
   [agentZone drop];
 }
 //This could be achieved with a single line: [[agent getZone] drop];
```

This `Zone`-oriented approach might bring a bit of peace of mind because it eliminates the danger of a memory leak that may result when an agent is dropped but the objects inside it are not.

Chapter 14. The Swarm Collections Library

14.1. Overview: the `List`, `Map` and `Array` Protocols

The most frequently used kinds of collections are the `List`, `Map` and `Array` protocols. They have some elements in common. They all comply with the `Collection` protocol, most importantly, which means they have methods with which items can be added, retrieved, and removed. Also, each can be used to create an index object, which can make management of lists an easier chore.

It is very important to note that these collections are primarily intended to manage objects, not integers or floating point values. [1] If you need an array of integers (or floats or chars or whatever else), just use an ordinary C array. When it is necessary to use strings, integers, or floating point values in a Swarm collection, there are two workarounds. One is to use typecasting to put those other values inside the space allocated for a pointer to an object. For various reasons, that approach is not as desirable as the alternative of creating "wrapper objects" that can contain those other types of variables. In short, while typecasting will often work, it is generally a better strategy is to design more carefully the objects you want to keep in Swarm collections and use recommended procedures for retrieving them.

Some commands that work in Swarm collections are:

- **`getCount`**: Returns the number of members in the collection
- **`atOffset: i`**: Retrieves the *i*th member of the collection
- **`atOffset:i put: obj`**: Inserts obj at location i
- **`contains: obj`** Returns 1 if obj is member
- **`remove: obj`**: Removes object obj
- **`removeAll`**: Removes all objects from collection, but leaves the objects in memory
- **`deleteAll`**: Removes all objects from collection and deletes them from memory
- **`forEach:M(message)`**: Sends message to all members

1. Type casting for both storage of variables in collections as well as usage of non-object values for keys was discussed in the original Swarm design. Roger Burkhart defined a protocol `MemberType` which would have been adopted by the `Collection` protocol: “The MemberType option may be used to declare the type of member which a collection contains. Its value must be an object having one of the ValueType types defined in defobj. (..Currently no ValueType objects are implemented, so MemberType is not supported.)” This protocol was to have two methods: **`-setMemberType: aDataType`** and **`-getMemberType`**.

This chapter does not discuss the Swarm `Set` protocol because, at the current time, it has no functionality beyond the regular Swarm `List` protocol.

14.2. Choosing between `List`s, `Map`s, and `Array`s

The different kinds of collections objects are useful for different purposes. The `List` class can be used to create easy-to-use containers that make it relatively simple to manage iterative chores. Use a Swarm `List` when you intend to have all objects processed in order, for example. (`List`s can also be processed in a randomized order). The `Map` and `Array` classes are intended for more structured maintenance of collections.

Because they serve these specialized objectives, there are some commands uniquely available to each of the Swarm container classes. For example, as we saw in an earlier chapter, the `List` class can respond to methods like **`addFirst:`**, **`addLast:`**, removeFirst, and removeLast. A `List` object can be used in a flexible way, objects can be thrown onto the end or the beginning of the list with these methods. These are not available in `Map` or `Array`, because `Map` and `Array` objects have more intricate internal structure.

A Swarm `Array` object is used when it is necessary to store objects in a specific order. The Swarm `Array` is somewhat similar to a C array, in the sense that objects can be inserted at a particular position and their values can be retrieved from that position. A Swarm `Array` can be processed iteratively, as a `List` can.

A Swarm `Map` is used when objects are not stored according to their numerical position in a list, but rather according to the value of some object. For example, a `Map` can store objects that have rankings of favorite foods for each of several people. If each person is an object, then the person's identity works as a "key" that controls the insertion and removal of the object from the `Map`.

Enhancement and streamlining of the Swarm Collections library is an ongoing chore, but at the current time the user's choice of `List`, `Map`, or `Array` is partly driven by the way these classes are implented in Swarm. The `List` and `Map` classes are comparatively slow. If one needs to make repeated accesses to a `List` or `Map` from randomly selected positions, the program will run comparatively slowly. Here's why:

1. Suppose you have a `Map` and you have entered objects that represent food tastes for each of 500 people.
2. If you then tell your `Map` object to retrieve the food preference of the person "Bart", for example, then the `Map` will be processed from the beginning (the first inserted object) and each will be checked to see if its key (its "owner," as it were) is "Bart."
3. If Bart's object happens to be at the end of the `Map`, then a lot of objects will be checked.
4. Then, when you ask for the object of person "Fred", it begins at the start of the `Map` and checks, one-by-one, until it finds the object whose key is Fred.

At the time of writing, the `Map` object, has no way to go straight to the one you want[2], so it goes through this repetitive checking process. The same is true of the `List` class. As a result, if there are many objects, programs will run slowly when they try to insert and retrieve data for specific objects when using Swarm `List`s or `Map`s.

In contrast, the processing of a Swarm `Array` can be quite fast because the elements are entered with integer keys. A Swarm `Array` can quickly retrieve item number ten. Unlike a `Map`, it does not start at the beginning and go through a sequence of checks until it comes to the tenth item. Because of the internal structuring of the Swarm `Array`, the tenth item is retrieved without checking the first nine.

As a result of the aforementioned issue about the speed of the program, there is going to be a judgment call. A `Map` will work fine and quickly if there are just a few items stored, but the time wasted looking for a specific item increases with the length of the list. An `Array` might be a good choice, except allocating space for an array may waste memory. For example, suppose we are preparing to survey 20 people out of a population of 100,000. If each person is assigned a number, and then numbers are chosen at random, we might end up with people in our sample that are numbered {44, 63, 555, 4432, 6689, 21001, 44934, 78343, 99921}. If we use a `Map`, we could just add the 10 objects. On the other hand, if we wanted to use an `Array` with the person's number serving as the `Array` index, we would have to allocate an `Array` with 100,000 elements in order to store these ten items. This wastes memory, but objects can indeed be retrieved quickly. Most people would prefer a `Map` for this purpose. If there were 10,000 people being sampled, however, the `Array` might work best.

14.3. Using Swarm `Array`s

The Swarm `Array` is the easiest to use of the Swarm collections. At create-time, the size of the `Array` is set. For example, to create an `Array` called *`foods`* that has 15 elements, this code will get the job done:

```
id <Arraya> foods;
food=[Array create: [self getZone] setCount: 15];
```

If it is necessary to add elements to the `Array`, then the **`setCount:`** method of the `Array` class can be used to increase the size ofthe `Array`.

Entries are inserted, accessed, and removed from the `Array` in a rather obvious way. As in C, the numbering of the `Array` elements begins with 0, so the last element in the `Array` has the index value 14. To insert an object called *`steak`* into the foods `Array` at index value 6, the appropriate command is:

2. a potential enhancement to the collections library is an option that would allow the user to select a hash-table implementation of the `Map` protocol, which would effectively allow this kind of random-access

```
[foods atOffset: 6 put: steak];
```

When it is necessary to retrieve the *steak* object, this will do:

```
retrievedObject=[foods atOffset: 6];
```

A Swarm `Array` object will allow quick access of any particular object because the objects are indexed by an integer.

An `Array` will work like a Swarm `List` for the purposes of repetitive processing. Since an `Array` includes a fixed number of objects, they can easily be accessed with for loops, but while loops will work just as well. An `Array` object can be told to create an index object for itself, and that index can be used in the way that we described in the chapter on `List`s.

There is only one surprise awaiting users of the `Array` protocol: objects cannot be removed from `Array`s. Since the `Array` protocol's major strength is its speed, and the speed depends on maintaining a fixed list of items, the remove method of the Collections protocol is disabled in `Array`. Rather than remove an item from an `Array`, one must put *nil* at a position in the `Array`. This achieves the same effect as remove, but it preserves the `Array` "placeholder" so that future objects can be inserted at that spot.

14.4. Swarm `Map`s

Experienced programmers are familiar with the term "key" as it refers to management of collections. People who are new to programming and Swarm often find this idea quite confusing. Hence, we will explain.

Think of a `Map` as two rows of objects. The bottom row contains the objects you want to store and retrieve. The top row contains the names of the objects. If you put an object into a `Map`, you tell the `Map` its name and the `Map` handles the problem of inserting the object into the bottom row and putting the name in the top row. When an object is removed from a `Map`, its name is also removed from the top row. If you need to get an object, you tell the `Map` its name and the `Map` then goes to the right position in the top row and then it gives back the corresponding object in the bottom row.

The names of the objects are called "keys" in Swarm (and other programming languages). The usage of keys is somewhat confusing and difficult for newcomers because the keys should be Swarm objects.

Example 14-1. Maps and keys

Here is a simple example. Suppose we are creating a series of objects in a for loop. In each step, we tell the class Person, which is subclassed from `SwarmObject` to create an instance *aFriend* and we add that Person to a *listOfPeople*. Then we tell the class Preferences to create an instance and we insert the

instance into a `Map`, using the Person object as the key. Note that the `Map` and `List` are declared before the loop.

```
id <List> listOfPeople;
id <Map> mapOfPreferences;
listOfPeople=[List create: [self getZone]];
mapOfPreferences=[Map create: [self getZone]];

for(i=0; i < 50; i++)
{
id aFriend, aPreference;
aFriend = [Person createBegin: [self getZone]];
aFriend = [aFriend createEnd];

[listOfPeople addLast: aFriend];

aPreference = [Preferences createBegin: [self getZone]];
aPreference = [aPreference createEnd];

[mapOfPreferences at: aFriend insert: aPreference];
}
```

To retrieve a preference object, it is first necessary to figure out which person you want and then tell the `Map` to return that person's preference. For example, suppose you decide to grab the 6th person and find out what their preferences are. Then try this:

```
id aParticularPerson, thePreference;
aParticularFriend=[listOfPeople atOffset: 6];
thePreference=[mapOfPreferences at: aParticularFriend];
// here you can do anything you want to with thePreference you get back.
```

Similarly, you could cycle through the *`listOfPeople`* by creating a Swarm index for the *`listOfPeople`* and then use the returned value from `[index next]` as the key:

```
id index, aPerson;
index= [listOfPeople begin: [self getZone]];
while( (aPerson=[index next])!=nil )
{
  id thePreference;
thePreference = [mapOfPreferences at: aPerson];
// here you insert some code that does something with the retrieved preference!
}
```

This example works because the `Map` object automatically compares the objects acting as keys to see if they are identical. This is the default compare: method of the class `SwarmObject`. If one wishes to compare the objects by another criterion, then a comparison function can be declared when the `Map` is created. Lacking a user-defined comparison function, the `Map` will always use the **`compare:`** that is defined in the key object. Lacking such a function, the program should not run.

When an object that is being used as a key has a **compare:** function, then the Map will use that function to decide if the two objects are equal. If a comparison function is declared when the Map is created, then that comparison function will be used instead. Swarm includes some built-in comparison functions, but, as we will see, the usage of customized functions is quite easy and convenient. If no comparison function is declared, then the fall-back approach checks for a **compare:** method in the key object itself. Since all objects that are based on Swarm inherit from the defined object class, all such objects have (at least) access to the bare minimum **compare:** that checks to see if two objects are identical. Classes from which key objects are created can, of course, create more informative comparison methods.

Lets begin with the problem of using integers as keys. There are two possible approaches, typecasting and the creation of "integer wrappers." The typecasting approach is used in many Swarm applications. The essence of this approach is to use type casting to trick the Swarm library to make it treat an integer *as if* it were an object. Without going too deeply into the computer science of the issue, it may not be possible to explain this, but we will take a stab at it. On many computer systems, a pointer uses the same amount of space as an integer. Hence, it is possible to cast an integer as a pointer to "fool" the compiler, and then to retrieve the value of the integer from the place in memory where the pointer was supposed to be. (Confusing? Many users say, yes!) Instead of inserting objects into a Map with objects as keys, using this casting trick, one can insert objects at integer values that are cast as objects of type id. For example:

```
[mapOfPreferences at: (id) 13 insert: aFriend]
```

In order for this to work, the *mapOfPreferences* has to be created so that it knows integers are going to be passed through in this way. At create time, the Map must be told to use the built-in comparison function that will uncast the pointers and compare them.

```
mapOfPreferences  = [Map createBegin: aZone];
[mapOfPreferences  setCompareFunction: compareIntegers];
mapOfPreferences = [mapOfPreferences createEnd];
```

The GridTurtle code example grid3b.m uses this appoach.

This "casting" approach to creating a keys has some serious shortcomings. Most importantly, it is severely nonportable. Code written in this way on a Linux system might not work on a DEC Unix system. Why? On DEC Unix, an integer and a pointer do not have the same size.

What is the alternative if one wants to enter objects into a Map using integers as keys? The answer is: create an "integer wrapper" class. This integer wrapper can store and retrieve the values of integers, and these objects can be used as keys in Swarm Maps.

Here is the integer wrapper class [3], which is called Integer:

3. There is an example of a program by Marcus Daniels that uses integer wrappers at MapIntegerIndex.txt (http://lark.cc.ukans.edu/~pauljohn/SwarmFaq/WorkingExampleCode/MapIntegerIndex.txt).

```
//Integer.h
#import <defobj/Create.h>

@interface Integer: CreateDrop
{
 int value;
 member_t link;
}
- setValue: (int)value;
- (int)getValue;
@end

//Integer.m
@implementation Integer
- setValue: (int)theValue
{
 value = theValue;
 return self;
}

- (int)getValue
{
 return value;
}

@end
```

In order to use the `Integer` class keys, the `Map` has to be told how to compare them, so it knows when it has found a key that matches what it is searching for. In the example, the comparison function is called **`compareIntegerObjects ( )`** and it takes two objects, and it then retrieves the value from each object, and returns the difference of the two. When 0 is returned, it is treated as a "match". The following code snip creates 50 `Preference` objects and it creates an `Integer` object for each one. Each time the user wants to insert an object into a `Map`, an `Integer` wrapper is created.

```
#include Integer.h
#include Preference.h

// Here is a "comparison function"
int
compareIntegerObjects (id obj1, id obj2)
{
return ((Integer *) obj1)->value - ((Integer *) obj2)->value;
}

id <List> listOfPeople;
id <Array> arrayOfIntegers;
id <Map> mapOfPreferences;

mapOfPreferences = [[[Map createBegin: [self getZone]]
    setCompareFunction: compareIntegerObjects]
   createEnd];
```

```
for (i = 0; i < 50; i++)
{
  id aPreference;

  aPreference = [Preference createBegin: [self getZone]];
  aPreference = [aPreference createEnd];

  anInteger = [[Integer createBegin: [self getZone] setValue: i] createEnd];

  [mapOfPreferences at: anInteger insert: aPreference];
}
```

After the *mapOfPreferences* is filled with objects, then they can be retrieved by their key values. One can create a single `Integer` object, and then insert a value into it, and then use it as the key. The following will work to retrieve the `Preference` object corresponding to the `Integer` key with value 23. Supposing the `Preference` class has a method *outputVitalInfo*, this will retrieve those objects and tell them to execute that method.

```
id desiredPreferenceObject;

Integer * key = INTEGER(0);
key->value =23;   //same as [key setValue: 23];
desiredPreferenceObject= [mapOfPreferences at: key];
printf("The preference Object gives this output \n");
[desiredPreferenceObject outputVitalInfo];
```

This is written out this way to make the code as clear as possible. The example program cited above includes a number of macro definitions that can be used to make working with the `Integer` class more elegant (and less tedious).

The same kind of approaches can be used if one wants to use strings as keys in a `Map`. The easiest way to use strings as the keys is to use the Swarm `String` protocol to create objects that act as "wrappers" for the string names. In the Swarm Documentation, one can find the GridTurtle test programs for the Collections library. The file `grid3.m` contains an example that does exactly this. The code in `grid3.m` creates a string, equal to the index variable i, and then sets that string into a `String` object, which is in turn used as the key. Of course, there is no reason that the chosen character string had to be a simple number. If you want to, you can create strings for all your friends and wrap them inside `String` objects.

Unless you define a comparison function, the String objects are compared according to the **`compare:`** method that is defined for Swarm `String`s. This function is defined in the Swarm library in the file `StringObject.m`. The comparison uses the C function strcmp to find out if the object's own string is the same as the string retrieved from the other object (which is called *aString*):

```
- (int)compare: aString
{
  return strcmp (string, ((String_c *) aString)->string);
}
```

As in the case of integers, the built-in compare: method can be over-ridden by a customized comparison function declared by the user.

14.5. Accessing Collections with Indices

Any collection can generate an `Index` that can be used to access its members. The command to create an `Index` for a given collection is **`begin:`**. The type of `Index` created by a collection depends on the type of collection being indexed. If one desires an index of randomly shuffled members of a collection, then **`beginPermuted:`** is the necessary command.

An `Index` object will understand messages like **`get`**, which will return the object at which the `Index` is currently positioned, **`next`**, which will move the `Index` object to the next object in the collection and return that object, and **`findNext:`** objectName, which will cause the `Index` object to search forward into the collection until it finds an object that is the same as objectName.

The usage of indexes can make some code work more smoothly. For example, as we noted in our discussion of `List`s, the `Index` can be used to orchestrate the repetitive processing of a `List` object in the following way:

```
id aCollection;
id <Index> index;
aCollection = [List create: [self getZone]];
index =  [aCollection begin: [self getZone]];5

while( (anObject=[index next]) != nil )
{
  //write code that does something to anObject
}
```

This code will cycle through the `List`. Because the `Index` object remembers its position in the `List`, the processing is efficient in the sense that the **`next`** command causes just one step to be taken. This is a sharp contrast with the usage of collections methods like `[aCollection atOffset: i]`, which cause the `List` to begin at the beginning and count up to the *`i`*th object.

Perhaps the most significant advantage of indices is that they can be used manage collections. If items are removed from a collection by its `Index` object, then the `Index` object is automatically kept up to date. On the other hand, if items are removed directly by collections methods, such as `[aCollection remove: thisObject]`, then the indexes that had been previously created for that `List` will be damaged and they must be dropped and recreated. On the other hand, if an `Index` is positioned on the desired member, and then the index is told to remove that object, then the change will be made in the collection and the index will automatically be adjusted.

In order to make an index remove objects correctly, the fundamental problem is to correctly position the index within the collection. To make an index object reposition itself at the beginning of the collection, the command `[index setLoc: Start]` can be used. `Index` objects can be manually positioned with

methods like `[index findNext: targetObject]` or `[setOffset: i]`. These will, respectively, move to the next object which, according to the comparison function, matches the target object, or move the index to the *i*th object in the collection. Once the index is positioned, then the object can be removed with `[index remove]`.

The Swarm `List` class creates `Index` objects that have more functionality than the other classes. The `Index` of a `List` class collection can be used to insert objects as well as delete them. For example, `[index addAfter: newObject]` can set a new object into a collection after the object currently under the index. The addition of objects by the index is not allowed in Swarm `Array`s or `Map`s because of the internal structure of those classes.

Chapter 15. Using the Random Library

The creation of random numbers is a surprisingly complicated affair. It is also vital to the success of a simulation exercise. Sooner or later you will want to simulate some real-life stochastic phenomenon which occurs in a manner resembling an identifiable statistical distribution, for example (to take the canonical simulation example) the time intervals between customers arriving to join a queue in front of a bank teller. Or perhaps you just want to add some controlled unpredictability to the behavior of your agents. One of the strengths of Swarm, as a simulation framework, is that it includes a number of methods for the creation of streams of random numbers that meet exacting standards.

Before we step in to the details of the Swarm random library, there is one point that needs to be made. There is no such thing as a random number, at least as far as a computer is concerned. Every number a computer creates comes from a formula. The challenge is to find a formula that makes the numbers sufficiently unpredictable that we can proceed as if they are random numbers that satisfy statistical requirements, like statistical independence of successive draws. This means that the device puts out numbers so that, even knowing all previous values, one is not able to predict the next number to come out without looking inside the program to steal the algorithm that is generating the numbers. The procedures we describe here might are more correctly be called pseudo-random number generators. With that point being clear, we often refer to them as random number generators.

In his section of the Swarm User Guide, we provide a survey of the basics of using the Swarm Random Library. A detailed technical manual has been prepared and it is included as an appendix to this guide. It goes into considerably greater depth on the technical issues that arise in generating random numbers.

15.1. Built-in Random Number Distributions

Since not all users want to become experts in random (well, pseudo-random) numbers, we will start with the easy alternative. In the Swarm kernel–the code that executes at the beginning of any swarm program–there are three objects that can give useful random number streams. These objects are initialized and structured according to built-in assumptions that reflect the state-of-the-art in the creation of random number streams. The first two supply integers at random, the last one supplies numbers on a continuum.

The three built-in random number distributions are:

- **`uniformUnsRand`** This object will draw a positive integer at random within a user specified interval. To get a random integer between 3 and 47, this command will work:

```
myUnsigned = [uniformUnsRand getUnsignedWithMin: 3 withMax: 47];
```

The object *`uniformUnsRand`* is an instance of the Swarm class `UniformUnsignedDist`. Readers can consult the documentation for a full explanation of all available options.

- **`uniformIntRand`** This object will draw an ingeger at random from an interval that may include negative or positive numbers. A usage example would be:

  ```
  myInteger = [uniformIntRand getUnsignedWithMin: -44 withMax: 47];
  ```

  This object is an instance of the Swarm `UniformIntegerDist`, which is fully documented in the Swarm documentation.

- **`uniformDblRand`** This object will draw a real number from a user-specified interval. Unlike the previous two, this distribution is not restricted to integers. If a random number from the interval [1,5] is needed, this command will work:

  ```
  myDouble   = [uniformDblRand getDoubleWithMin: 1 withMax: 5];
  ```

  This object is an instance of the Swarm `UniformDoubleDist`.

These are global objects that can be used in any file that is part of a Swarm program.

When a Swarm program starts, it initializes these random number creators. *They will deliver the same stream of numbers every time the program is run* unless the user adds the "vary seed" parameter when the program is run. This parameter is `-s` and is added on the command line. For a full list of possible options, type the name of the application followed by `-help`.

These built-in random distribution objects use another built-in Swarm object that is called "randomGenerator". The object "randomGenerator" feeds input into each distribution. The meaning of the term "random generator" is explored in the next sections.

15.2. Overview of the Random Library

Suppose you want to draw random numbers from a Normal Distribution with a mean of 33 and variance of 10. There is no "normal distribution object" created automatically in the Swarm kernel, you have to create that in your code. In order to explain how this is done, it is important to understand the two-step nature of the process of creating random numbers from a distribution.

Mathematically speaking, numbers are created as draws from a particular distribution through a two-step process. First, one or more numbers on a given interval are drawn. If one is creating a continuous distribution, the interval is usually [0,1). Then using various formulae from the field of statistics, a draw from a particular distribution is created that depends on the draw(s) in the first step. This two-step process is documented in the literature on simulation. (A very readable and complete treatment is found in Averill M. Law and W.David Kelton, Simulation Modeling and Analysis, New York: McGraw Hill.)

The first stage in the process uses an object called a *random number generator*. A random number generator is a component that can generate unpredictable numbers within some interval that are "equally likely" to occur. There have been many kinds of procedures proposed for creating numbers that appear to

be random. Swarm includes a great many of these. The default random generator, the one that Swarm uses to generate its built-in random number objects, is MT19337. The generator has a period close to 219937 (1 x 106001), so there is no danger of running a simulation long enough for the generator to repeat itself. At one microsecond per call, it would take about 3.2 x 105987 years to exhaust this generator. For comparison, the age of the Universe is 'only' 2 x 1010 years! This generator can be asked either for a real number (a variable of type double) between [0,1) or for an integer, which will be uniformly distributed on the range [0,4294967295] = [0,232-1].

In the second stage, the output from the random number generator is used to create a random variate that meets the specificiations of a particular distribution. Of course, some are done more easily than others. If one needs a draw from a Uniform distribution, then the output of the random number generator itself can be used. On the other hand, some distributions require complicated transformations in order to create numbers that appear as if they were generated from the distribution. For many common statistical distributions, the code to transform the uniformly distributed random numbers into other distributions are provided in the Swarm library. While there are some distributions that are not currently supported, they can typically be constructed by users with the existing distributions as building blocks.

The Swarm Random library can be divided into two parts, which parallel the two-stage process we have described. There are

- Generators
- Distributions

The following sections will dig into the details of these libraries, but first we will offer a couple of simple usage examples.

Suppose one wants to draw numbers from a normal distribution. The normal is a well known distribution and it has known statistical properties. The object "randomGenerator" is created when the Swarm kernel is initialized, so it can be used in any distribution as the random number generator. To create a `NormalDist` distribution object and connect it to the predefined `MT19937` generator, this code will suffice:

```
 #import <random.h>   //This includes the Swarm random library
       id <NormalDist> myNormalDist;  //This names your object and adopts the NormalD-
ist protocol
       myNormalDist = [NormalDist create: [self getZone]
       setRandomGenerator: randomGenerator];
```

If for some reason, one does not want to use `MT19937` as the generator, then one of the other Swarm generators can be selected and explicitly created. The next code example uses a generator called `RWC8gen`. This code will first create an instance of that generator, then it will create an object to draw normally distributed observations.

```
       int mySeed = 123776;
```

```
id myGenerator;
id <NormalDist> myNormalDist;
myGenerator = [RWC8gen create: [self getZone]
setStateFromSeed: mySeed];

myNormalDist = [NormalDist create: [self getZone]
setRandomGenerator: myGenerator];
```

The random library is designed in a highly versatile way. Each generator must have a "seed" value, a starting place from which to spin out the random numbers. As long as one leaves the seed at the same value, then the stream of random numbers will be replicated each time the program is run. If one does not want to specify a seed, then that chore can be left up to Swarm, which will insert a seed on behalf of the user. The way to create a generator that uses the system default value for the seed is shown here:

```
myGenerator = [RWC8gen createWithDefaults: [self getZone]];
```

Another example of the versatility of the Swarm random library is in the design of the distribution classes themselves. We have already seen examples in which random numbers are drawn according to user specified requirements. In the case of the Normal distribution, one can draw from a distribution with a mean of 0 and variance of 1.3 with this command:

```
double sample;
sample = [myNormalDist getSampleWithMean: 0.0 withVariance: 1.3];
```

If one expects to want many draws from a distribution with that same set of parameters, then the distribution object can be told to set those values as the defaults. After the default values of the mean and variance are set, then values retrieved from that distribution object can be retrieved with the simpler method **`getDoubleSample`**. For example:

```
[myNormalDist setMean: 0.0 setVariance: 1.3];
sample = [myNormalDist getDoubleSample];
```

Of course, each distribution will have its own parameters and particular methods for setting them. These parameters can be reset at any time.

15.3. The Random Number Generators

Recall that computers can’t create real random numbers, just streams of numbers that appear random to the outside observer. As a rule of thumb, users are well advised to choose a well tested generator which has a long period, which is the number of draws that can be made before the sequence repeats. We also want a generator that runs fast and uses little memory. (These wishes are of course in conflict with each

other, so choice involves compromise.) And the generator should perform 'acceptably' in a statistical sense. Readers who wish to pursue what this might mean are referred to the bibliography.

15.3.1. How to use the default random generator

Suppose you want to draw some random numbers with the default random generator. When a swarm program runs, it creates a globally available object called randomGenerator that can be used in any part of the program to draw random numbers.

If you want to draw unsigned integers, try this:

```
unsigned int myUnsigned;
myUnsigned = [randomGenerator getUnsignedSample];
```

The values returned will be uniformly distributed in the range [0,4294967295] = [0,2^{32}-1].

Or, if you need floating-point values instead, you can say

```
double myDouble;
myDouble = [randomGenerator getDoubleSample];
```

The returned values will be uniformly distributed in the range [0.0,1.0), i.e. they may be equal to 0.0 but never 1.0.

15.3.2. A list of generators in Swarm

The default generator used in Swarm is `MT19337`, but there are a number of others that are provided to suit the needs of experimentation and replication of previous studies. These generators have been subjected to various statistical tests, and the results of these tests are described in Advanced Usage Guide.

The current generators in Swarm are:

- ACGgen: Additive Congruential Generator
- C2LCGXgen: A short component based generator. This is considered a high quality generator
- C2MRG3gen: Combined Multiple Recursive Generator
- C2TAUSUS*x*gen: A Family of Combined Trausworthe generators
- C3MWCgen: Combined Multiply With Carry Generator
- C4LCGXgen: Combined random generator using 4 (PMM)LGC generators
- LCG*x*gen: Family of Linear Congruential Generators

- MRG*x*gen: Family of Multiple Recrusive (LCG) Generators
- MT19937gen: 'Mersenne Twister' Twisted GFSR generator. The Swarm default
- MWC*x*gen: Family of Multiply-With Carry generators
- PMMLCG*x*gen: Family of Prime Modulus Multiplicative Linear Congruential Generators
- PSWBgen: Subract-With-Borrow Congruential Generator with prime modulus
- RWC2gen: 2-lag Recursion With Carry generator
- RWC8gen: Multiply With Carry generator
- SCG: Subtractive Congruential Generator
- SWB*x*gen: Family of Subtract-With-Borrow Congruential Generators
- TGFSRgen: Twisted GFSR generator
- TT403gen: A single long generator recommended for use
- TT775gen: A single long generator recommended for use
- TT800gen: A single long generator recommended for use

All the Swarm generators except two conform to the 'SimpleRandomGenerator' protocol. The two 'split' generators that do not, C2LCGX and C4LCGX, are described in the Generator Usage Guide.

15.3.3. A note on starting seeds

Whenever a random generator is created, its state has to be initialized. It uses a "seed", a positive integer, as its starting place. To make life easy for the user, the Swarm generators can be initialized to a predictable and repeatable state. Every time you initialize a given generator with a particular seed, you should get the same sequence of numbers from it.

You create and initialize a generator with a specific seed this way:

```
#import <random.h>
id <SimpleRandomGenerator> myGenerator;
unsigned int mySeed;
mySeed = 123776;
myGenerator = [RWC8gen create: [self getZone]
setStateFromSeed: mySeed];
```

If it is necessary to set or reset the seed after the generator has bene created, it can be done with the **`setStateFromSeed:`** method:

```
  mySeed = 4532657;
[randomGenerator setStateFromSeed: mySeed];
```

You may do this any time during a simulation, not just at the start.

If you start your simulation with the command line option -s, which is short for –varyseed, then the seed will be chosen at random on the basis of the system clock. If you do not add that command line option, your simultion *will use the exact same stream of random numbers* every time you run it. This makes replication easy.

15.4. The Distributions in Swarm

All distributions are created through the two-step process outlined above. First one needs a random number generator. Then one initializes the distribution, optionally setting its parameters at the time of creation.

15.4.1. Classes that adopt the ProbabilityDistribution Protocol

The distributions currently offered in the Swarm library are

- BernoulliDist: Bernoulli distributions describes the number of "successes" in a fixed number of trials
- ExponentialDist: Exponential distribution
- GammaDist: Gamma distribution
- LogNormalDist: log-Normal distibution
- NormalDist: Normal distribution
- RandomBitDist: Random Bit Distribution: returns YES or NO with equal likelihood
- UniformDoubleDist: Uniform continuous distribution on a range
- UniformIntegerDist: Equally likely integers in a range
- UniformUnsignedDist: Equally likely integers in a positive range

15.4.2. Matching generator and distribution objects

Each distribution object must have a generator associated with it. You may create a new generator for each distribution. Or, you may connect multiple distribution objects to one generator, so that they end up drawing output from the generator in an interleaved fashion. (This is what has been done with the predefined distributions.)

There is a method called createWithDefaults that can be uses to streamline the creation process. Here is a usage example:

```
myNormalDist = [NormalDist createWithDefaults: [self getZone]];
```

If you create distribution objects using the **`createWithDefaults`** method Distribution Usage Guide, each distribution object is assigned its own, newly created, private random generator. Each distribution class uses a different class of default random generator, just to keep things as statistically independent as possible.

You can assign a seed for the private generator with code like this:

```
[[myNormalDist getGenerator] setStateFromSeed: 9874321];
```

The usage of createWithDefaults is not without its dangers, however. If createWithDefaults is used to create two distributions of the same type, say two NormalDistributions, then (obviously) then each will have the same kind of private generator created for it. And, unless the simulation is started with the –varyseed option, then both private generators will start with the same seed and the two distributions will generate identical numbers.

15.4.3. Setting numerical parameters of distribution objects

Each distribution has its own set of key parameters. You may deal with these parameters in three different ways:

1. Assign "default parameter values" when the distribution object is created For example:

```
#import <random.h>
id <NormalDist> myNormalDist;
double sample;

myNormalDist = [NormalDist create: [self getZone]
setGenerator: randomGenerator];
[myNormalDist setMean: 0.0 setVariance: 2.1];
sample = [myNormalDist getDoubleSample];
```

2. Specify parameters when random numbers are drawn. These values do not override or change the defaults that were set when the distribution was created.

```
#import <random.h>
id <NormalDist> myNormalDist;
double sample;

myNormalDist = [NormalDist create: [self getZone]
setGenerator: randomGenerator];
sample = [myNormalDist getSampleWithMean: 0.0 withVariance: 1.3];
```

3. Re-set the parameters anytime. For example,

```
[myNormalDist setMean: 0.0 setVariance: 2.1];
sample = [myNormalDist getDoubleSample]; // from N[0.0,2.1]
```

For a more detailed description of the methods available from distribution objects, see the Distribution Usage Guide.

15.5. How to Create Other Random Number Distributions

Suppose one wants to draw numbers according to a distribution that is not offered in Swarm. For example, the Beta distribution is a distribution that has two parameters. The Beta distribution can take on almost any unimodal shape, ranging from uniform, to highly skewed to the left or right (see Law and Kelton, p. 166). The Beta distribution can be produced by taking two draws from a particular Gamma distribution and transforming them. For example, one can first create the *gammaDist1* and then put it to use:

```
- initializeRNGs
{
  [randomGenerator setStateFromSeed: 34733];
  gammaDist1= [GammaDist  create: self  setGenerator: randomGenerator setAlpha: 2 set-
Beta: 1];
  return self;
}

-(double) getBetaVariateAlpha1: (double) alpha1 Alpha2: (double) alpha2
{
   double y1, y2;
   y1=[gammaDist1 getSampleWithAlpha: alpha1  withBeta: 1];
   y2=[gammaDist1 getSampleWithAlpha: alpha2 withBeta: 1];
```

```
    return y1/(y1+y2);
}
```

With these methods defined, then the code must simply execute the **`initializeRNGs`** and then grab a Beta variate by specifying the two parameters, alpha1 and alpha2:

```
id gammaDist1;
double aDrawFromBeta;
[self initializeRNGs];
aDrawFromBeta = [self getBetaVariateAlpha1: .8  Alpha2: 2 ];
```

Chapter 16. Serialization

The term *serialization* refers to the ability to save more than one related object to either persistent data storage (such as a file) or to send an object over a network stream, such as TCP/IP. When an object is saved to disk (or sent over a 'wire') we record a reference to the saved object, so that the original object can be restored at a later date. This reference is referred to as a 'serial number', hence the term 'serialization'.

Swarm has two forms of support for serialization:

- **Lisp.** Lisp serialization reads and generates human readable text-file in Lisp format. This form of serialization is well-suited to applications that require either a human generated text file to create object parameters (such as simulation parameter files), or require a human-readable output.
- **HDF5.** HDF5 (http://hdf.ncsa.uiuc.edu/HDF5/) is high density binary data storage format created by NSCA (http://www.ncsa.uiuc.edu/). HDF5 serialization is well-suited to applications that involve reading and/or saving large data sets. It is a database-oriented format which a number of third-party tools (such as the **R (http://www.ci.tuwien.ac.at/R/)** statistical package which is a freely-available clone of **SPlus (http://www.mathsoft.com/splus/)**) can read.

16.1. Using the `LispArchiver` to manage simulation parameters

Earlier versions of Swarm used the protocols `ObjectSaver` and `ObjectLoader` to read/write object state to disk using an ad-hoc file format. These protocols only partially implemented the saving of certain types and the continued use of these protocols is now officially deprecated and may go away in future releases.

16.1.1. Using the Standard *`lispAppArchiver`*

Every Swarm application comes with a singleton [1] instance variable for reading object data formatted in Lisp. This instance is called *`lispAppArchiver`*. Like the *`probeLibrary`* and *`arguments`* instances, it is global to your entire application. This instance expects to find a file called **appName**`.scm` [2]:

1. A singleton class is a class that is designed to have only one global instance per application

2. `.scm` is the standard suffix for Scheme (a dialect of Lisp) files

, in either the current datapath for the application (SWARMHOME/share/swarm/**appName**) or in the local directory. Using this variable obviates the need for hand creation of LispArchiver instances. It permits one datafile (which can contain as many keys to objects as is required), and imposes a naming convention for that datafile.

Example 16-1. Using a standard *lispAppName* instance

The **heatbugs** application uses this global singleton class. The datafile heatbug.scm looks like this:

```
(list
 (cons 'batchSwarm
       (make-instance 'HeatbugBatchSwarm
                      #:loggingFrequency 1
                      #:experimentDuration 200))
 (cons 'modelSwarm
       (make-instance 'HeatbugModelSwarm
                      #:numBugs 200
                      #:minIdealTemp 10000
                      #:maxIdealTemp 20000
                      #:minOutputHeat 10000
                      #:maxOutputHeat 20000
                      #:randomMoveProbability 0.0)))
```

The Lisp file consists of two 'keys' or 'serial' numbers batchSwarm and modelSwarm for the parameters for two different objects. These keys are completely at the discretion of the user to choose. (Note also that the file syntax allows Lisp-style comments: a ';' colon followed by any text).

This input file would correspond with the following interface files, for the HeatbugBatchSwarm class we have HeatbugBatchSwarm.h

```
@interface HeatbugBatchSwarm: Swarm
{
  int loggingFrequency;           // Frequency of fileI/O

  int experimentDuration;                 // When to Stop the Sim

  id displayActions;   // schedule data structs
  id displaySchedule;
  id stopSchedule;

  HeatbugModelSwarm *heatbugModelSwarm;   // the Swarm we're observing

                                          // The EZGraph will be used
  id unhappyGraph;                        // in FileI/O mode rather
                                          // than the usual Graphics
                                          // mode...
}
// omitting methods
```

For the `HeatbugModelSwarm` class, `HeatbugModelSwarm.h`:

```
@interface HeatbugModelSwarm: Swarm
{
  int numBugs;   // simulation parameters
  double evaporationRate;
  double diffuseConstant;
  int worldXSize, worldYSize;
  int minIdealTemp, maxIdealTemp;
  int minOutputHeat, maxOutputHeat;
  double randomMoveProbability;

  BOOL randomizeHeatbugUpdateOrder;
  id modelActions;   // scheduling data structures
  id modelSchedule;

  id heatbugList;   // list of all the heatbugs
  id <Grid2d> world;   // objects representing
  HeatSpace *heat;   // the world
}
// omitting methods
```

Note that for each instance variable name of the form `#:ivarname somevalue` in the Lisp parameter file there exists a corresponding instance variable in the class header file. *However, not* all instance variables in the header file have corresponding entries in the Lisp parameter file. This is because the other instance variables are either unimportant as parameters (i.e. they can be regenerated by other parameters), or they are instance variables that pertain to the running model itself (such as *`modelSchedule`*, which is a `Schedule` instance).

To generate the objects with these corresponding parameters set in each object, you need the request the global *`lispAppArchiver`* archiver to 'generate' an instance of the object using the appropriate 'key'. So here's an excerpt from `main.m`:

```
if (swarmGUIMode == 1)
  {
      // Do GUI mode creation (omitted)
  }
else
  // No graphics - make a batchmode swarm (using the key
  // 'batchSwarm' from the default lispAppArchiver) and run it.
  if ((theTopLevelSwarm = [lispAppArchiver getWithZone: globalZone
                                                key: "batchSwarm"]) == nil)
    raiseEvent(InvalidOperation,
               "Can't find the parameters to create batchSwarm");

[theTopLevelSwarm buildObjects];
```

Note that you still pass the *`globalZone`* `Zone` instance to the **`getWithZone:key:`**, as you would if you were using the standard **`create:`** functions.

The key thing to realize here is that the **`getWithZone:key:`** call actually *instantiates* the object (i.e. automatically runs the **`createBegin`**/**`createEnd`** apparatus internally[3]). This has implications for the design of parameter files, since it means, for one thing, that all the appropriate instance variables necessary for a complete creation of an object *must* be present in the input Lisp file. It is possible to have a subset of ivars, but that subset should be sufficient to completely specify the object, i.e. no CREATE time messages can be sent to the object once it has been created. (Of course you can still send SETTING or USING messages to instance once it has been created).

The `HeatbugModelSwarm` is created in a similar way, from the **`buildObjects`** method in `HeatbugBatchSwarm.m`:

```
// Create the model inside us - no longer create 'Zone's explicitly.
// The Zone is now created implicitly through the call to create the
// 'Swarm' inside 'self'.

// But since we don't have any graphics, we load the object from the
// global 'lispAppArchiver' instance which is created automatically
// from the file called 'heatbugs.scm'

// 'modelSwarm' is the key in 'heatbugs.scm' which contains the
// instance variables for the HeatbugModelSwarm class, such as
// numBugs etc.

if ((heatbugModelSwarm = [lispAppArchiver getWithZone: self
                                          key: "modelSwarm"]) == nil)
  raiseEvent(InvalidOperation,
             "Can't find the parameters to create modelSwarm");

// Now, let the model swarm build its objects.
[heatbugModelSwarm buildObjects];
```

Note that *after* the creation of the *`heatbugModelSwarm`* instance, it responds in the normal way to valid methods, such as **`buildObjects`**.

16.1.2. Using Custom `LispArchiver` Instances

This section addreses those situations that require custom creation of multiple data files or alternate data filenames.

3. Note that this is in contrast to the obsolete `ObjectLoader` method, which required the user to create the object and then make a call to an `ObjectLoader` instance with the appropriate filename.

Example 16-2. Creating a Lisp parameter file with an alternate name

Here is a sample Lisp input parameter for the **Mousetrap** simulation, `batch.scm`.

```
(list
 (cons 'batchSwarm
       (make-instance 'MousetrapBatchSwarm  ; parameters for the batchSwarm
                      #:loggingFrequency 1))
 (cons 'modelSwarm
       (make-instance 'MousetrapModelSwarm  ; parameters for the modelSwarm
                      #:gridSize 40
                      #:triggerLikelihood 1.0
                      #:numberOutputTriggers 4
                      #:maxTriggerDistance 4
                      #:maxTriggerTime 16
                      #:trapDensity 1.0)))
```

The Lisp file consists of 'keys' or 'serial' numbers `batchSwarm` and `modelSwarm` identical to **heatbugs**

This Lisp input file has variables listed the following interface files (not shown) `MousetrapBatchSwarm.h` and `MousetrapModelSwarm.h`, for the `MousetrapBatchSwarm` and `MousetrapModelSwarm` classes.

The only difference with the previous example, is that we *explicitly* create an instance of the `LispArchiver` with the named file, and then ask the archiver to 'generate' an instance of the object using the appropriate 'key' as per the previous example. So here's the relevant excerpt from `main.m`:

```
// create an instance of the LispArchiver to retrieve the file
// set the path to 'batch.scm'
id archiver =  [LispArchiver create: globalZone setPath: "batch.scm"];

// retrieve the object from the archiver, if it can't be found
// just raise an event; note that the call to the
// archiver will actually *instantiate* the object if the
// parameters are found in the Lisp file
if ((theTopLevelSwarm =
      [archiver getWithZone: globalZone key: "batchSwarm"]) == nil)
  raiseEvent(InvalidOperation,
             "Can't find archiver file or appropriate key");
[archiver drop];
```

The `MousetrapModelSwarm` is created in a similar way, from the **`buildObjects`** method in `MousetrapBatchSwarm.m`:

```
  // create the instance to read the file
  archiver =  [LispArchiver create: self setPath: "batch.scm"];

  // * 'modelSwarm' is the key for the instance of the MousetrapModelSwarm
  //   with parameter values for the model instance variables: gridSize
  //   triggerLikelihood, numberOutputTriggers, maxTriggerDistance,
  //   maxTriggerTime, trapDensity

  // if we can't find the right key from the LispArchiver, raise an event
```

```
if ((mousetrapModelSwarm =
     [archiver getWithZone: self key: "modelSwarm"]) == nil)
  raiseEvent(InvalidOperation,
             "Can't find archiver file or appropriate key");

// don't need the archiver instance anymore
[archiver drop];
```

Note that when you have called the archiver instance to instantiate all the objects of interest, you have no need of the archiver instance and you can safely **`drop`** it.

Note also that, although the only difference from the previous example, is the name of the file does not conform to the **appName**`.scm` convention, but in principle the two keys could have been in different files, in which case in would have not been possible to use the global *`lispAppArchiver`* instance.

Appendix A. Swarm Tools

A.1. Web Resources for Object-Oriented Languages

The main technical skill currently [1] required of a Swarm user is the ability to write in at least one of following object oriented languages: Java or Objective C. Other recommended skills include the ability to use tools such as **gdb** and **emacs**. For the record, if you know C and have some form of experience in either C++ or Smalltalk, then learning Objective C should take no more than a day or so.

Here are some Objective C resources:

- Objective C references (http://www.swarm.org/resources-objc.html) List of Objective C references on the Web. Includes a 10 minute overview to Objective C that is most of what you need to know about Objective C. Originally contributed by Nelson Minar
- *Object-Oriented Programming and the Objective-C Language* (http://developer.apple.com/techpubs/macosxserver/ObjectiveC/index.html) An excellent (online!) book on Objective C. This is for generic NeXT Objective C: Swarm uses GNU Objective C in addition to our defobj extensions (see defobj library in : *Reference Guide to Swarm* (http://www.santafe.edu/projects/swarm/swarmdocs/refbook/refbook.html))

Unlike Objective C, the market is literally bursting at the seams with books on Java, so we merely point out a few relevant sites:

- GNU and the Java language (http://www.gnu.org/software/java/java.html) is a page run by the Free Software Foundation (http://www.gnu.org) that details many free/open source Java tools, most notably the reimplementation of Sun's JDK: **Kaffe** (http://www.kaffe.org).
- JavaSoft (http://java.sun.com), Sun Microsystems main Java page, and a new users section: New-to-Java Programming Center (http://developer.java.sun.com/developer/onlineTraining/new2java/)

A.2. Debugging Tips for Swarm

Debugging software is an art, perhaps even more so than writing the software itself. All software we write will have bugs: it is important to know how to diagnose a bug when it happens and how to write code defensively so you have less bugs in the first place.

1. As we continue extend Swarm's multilanguage features, further language bindings may become available.

A.2.1. Finding bugs

Bugs come in two categories: those that crash your program and those that don't. Bugs that crash your program are friendlier because they're obvious. Bugs that you don't notice are much more dangerous: one nagging question in every programmer's mind should be "is the program doing what I think it is doing?"

gdb. By far the most useful tool for finding bugs is a good debugger, a shell you can run a program under and set breakpoints, inspect the values of variables, etc. The best free debugger for Unix is probably gdb, available from the GNU ftp site (ftp://prep.ai.mit.edu/pub/gnu/). gdb seems unfriendly and confusing at first, but it is definitely worth your time to learn it.

The most important gdb commands are `help`: browse online help, `where`: show me a stack trace, where did we crash?, `list`: show me the source code where we are, `break`, set a breakpoint, and `print`: show me the value of of some expression. If your program is crashing on you, run it under gdb and look at the stack trace. If it looks to be buggy but you don't know where, start setting breakpoints and see when things go awry.

gdb and Objective C. Unfortunately, at this time gdb does not directly support Objective C. There are some workarounds (http://www.cons.org/cracauer/objc-hint-gdb.html) that make debugging Objective C programs possible. They are based on the knowledge that Objective C is little more than a glorified syntax for structs (objects) and strange function names (methods).

defobj: xprint(), xprintid(), xfprint(), xfprintid(), xexec(), and xfexec(). Swarm also has a few functions defined that can be used to make debugging easier. In particular, the function xprint(object) prints out the class of an object, and xexec(object, "message") calls the message specified on the object. These can be invoked under gdb as `call xprint(aHeatbug)`. Note that you can't pass arguments to a message, nor can you see the return value. There are also methods xfprint(collection) and xfexec(collection, "message") that print or exec foreach member of a collection.

gdb and Java. Swarm models written in Java will ultimately use the Swarm libraries which are still written in Objective C. The Java Native Interface (JNI) is the magic glue that binds these languages together. Thus if the crash occurs is the user (Java) portion of the code then the user is advised to use the standard Java debugging tools **jdb** and the like. (If a crash happens in the Java virtual machine (JVM), it should generally be clear from the error message that it is a Java-related problem). gdb is only useful when the crash occurs inside the Swarm libraries (i.e. outside the user's Java code). In this case you can invoke gdb in the following way:

```
$JAVASWARMGDB=gdb javaswarm StartModelName
```

From then on the preceeding information on the use of gdb in the Objective C context, continues to apply.

A.2.2. Preventing Bugs: Objective C

Defensive programming can help prevent a good number of bugs. When writing code, try to test it incrementally: make small changes whose effects you think you can predict and then test them. Don't outsmart yourself with cleverness: write code correctly first, then go in and hack it up if you need it to be more efficient. Put in sanity checks for conditions that shouldn't go wrong in normal usage, but might if you make a mistake.

-Wall. Swarm currently compiles all code with "gcc -Wall", which tells gcc to emit warnings for a lot of things that it wouldn't normally complain about. Warnings are not (necessarily) errors - warnings will be generated for legal code if gcc thinks that what you're doing could easily be a mistake. You might find this frustrating at first, but it helps catch a lot of common errors, including forgetting to include a prototype or forgetting to return a value from a function. Passing -Wall is good discipline.

nil_method. Objects in Objective C are essentially pointers to structs. So what happens if you send an object to the pointer 0x0, "nil" in Objective C parlance? Unfortunately, most implementations of Objective C, including gcc, define methods to nil as having no effect. The code:

```
aHeatbug = [Heatbug create: aZone];
aHeatbug = 0; // oops! bug.
[aHeatbug setIdealTemperature: idealTemp];
```

will *not* generate any errors.

The reason this is unfortunate is that it's a common bug to trash a pointer accidentally, set it to 0. It would be nice if your program then crashed when you tried to send a message to that mangled object: instead, the message send will fail silently and the program will continue to execute. This can make it hard to find bugs.

There are two ways to make messages sent to nil crash your program. The simplest is to put a breakpoint on `nil_method` under gdb: nil_method is invoked every time a message is sent to nil. Alternately, you can make a copy of the libobjc runtime source and edit nil_method to do whatever you want. The source code in `src/defobj` contains a file `objc.patch` that patches the runtime from gcc 2.7.2.

A.2.3. Preventing Bugs: Java

The good news for Java programmers is that since Java is a strongly typed language, many of the pitfalls that beset Objective C programmers, never materialize in the Java context. Nevertheless the reader is cautioned to use as many of the standard defensive programming techniques as possible.

A.3. Emacs and Swarm

Emacs is the world's best editor, infinitely configurable and powerful and free. If you're not used to a Unix text editor and want to write programs, emacs is probably best to learn. The information here will show you how to set up emacs to use an Objective C or Java specific mode for editing source code and how to get emacs to colour your source code for you nicely. Emacs can also help you find compilation errors, run a debugger, and even act like a class browser. Documentation for those things are not here, see the Emacs documentation itself.

A.3.1. Objective C

objc-mode. One of the best things about emacs is that one can load different "major modes" to edit types of files. Major modes making editing files easier by providing structure to your editing. In particular, there are programming language modes that do nice things like indentation for you.

Starting with emacs-19.30, the default C mode is `cc-mode.el`, a nice rewrite of the original c-mode.el. Luckily for us, `cc-mode.el` supports Objective C directly. The basic function to invoke it is `objc-mode`. The following bit of code in your .emacs will cause emacs to automatically enter objc-mode on all files that end in `.m` or `.h`:

```
(setq auto-mode-alist
(append '(("\\.h$" . objc-mode)
("\\.m$" . objc-mode))))
```

Highlighting code. Emacs running under X has the ability to colour your source code according to syntax. There are two packages to do this: `font-lock` and `hilit19`.

font-lock. emacs-20 and later also has a font-lock mode for Objective-C that supports the method syntax unique to Objective-C. We recommend the use of font-lock, over hilit19, now that the identification of Objective C syntax in emacs is better supported, as font-lock supports 'lazy-fontification' (i.e. as you type fontification), a feature that hilit19 never offered. See the manual provided with emacs for how to turn on this feature to highlight .h and .m files in 'objc-mode' automatically.

A.3.2. Java

jde. The aforementioned `cc-mode.el` also supports Java directly. But in the Java case we can go one better, with the complete free/open source Integrated Development Environment (IDE) known as the Java Development Environment (**jde**). It's available from the Sunsite (http://sunsite.auc.dk/jde/) in Denmark

Appendix B. Objective C - Swarm Style

The Swarm system provides a few extensions to the syntax/style of Objective-C. This note describes those features which are important to know as a beginner and those which can be ignored. This is also peripherally relevant for Java programmers.

B.1. Non-Conventional Techniques, And The Libraries In Which They're Used

When building some of the internals of the Swarm system, we found that there was a need to add a certain amount of machinery to the conventional Objective C language. In particular, we found that the system used for object creation needed to be expanded. The main goal of this document is to explain very briefly what those changes are, and why the user need never know about them...

Even within the Swarm libraries, only the most fundamental ones require the usage of some of the magic described below. Essentially, only Defobj, Collections and Activity use the features described below. Nevertheless, there are some minor conventions, which as a consequence, must be used throughout the code.

B.2. Zones

B.2.1. Zones in Principle

Perhaps the most visible change from normal Objective C is the use of Zones within which objects are allocated. We have requiered that objects be allocated within specific Zones for two main reasons:

- **Probing.** Zones will be used to facilitate the process of Probing.
- **Garbage Collection.** In later versions of Swarm, the Zones will be used to coordinate garbage collection.
- **Parallelism.** In Swarm 2.0 we hope to use the Zone system to facilitate the management of distributed memory.

B.2.2. Zones in Practice

As a beginning user, when required to provide a Zone, you can simply use the globalZone variable which is global and is already initialised to a valid zone. But, this is discouraged because the things in that Zone

are expected to be resident throughout the entire execution of the program and can lead to inefficient use of memory. Also, you should always attempt to allocate memory from Zones rather than using malloc. And when allocating a temporary object that won't be needed past the current scope, a scratchZone is provided.

B.3. Create Phase

B.3.1. The Create Phase in Principle

One of the more surprising mechanisms used in Swarm is the Create Phase protocol. The idea behind the protocol is that when you create an object, you are not really getting the final object - only a "proto-object". This "proto-object" is then sent a sequence of "create phase" messages which are meant to provide hints to the system about the way in which the object is going to be used.

So, for example, when creating a List object you may declare that you will only access the list from either end, never from an arbitrary location. By doing so you allow the "proto-object" to provide you with a tailored implementation which attempts to meet your specific usage patterns. This sort of approach is crucial for the performance-critical libraries in Swarm (such as the Activity library). Here is a schematic of what sometimes occurs in these libraries:

Figure B-1. Schematic of proto-object creation



B.3.2. The Create Phase in Practice

Since this form of object creation is still quite rare in the object oriented community, we do not expect the users to write code which actually implements this sort of technique. However, we do advise the users to try and split those messages which are supposed to be sent only once in the lifetime of an object (just after the object is created) from the ones that are sent multiple times.

For example, if your object has a variable which will never change and furthermore should be set at the very early stages of its lifetime (say, Color), then you should declare the message which sets this variable before the createEnd message:

```
-setColor: (int) aColor ; // createPhase message -createEnd ;
```

```
-(int) getColor ; // normal message
```

The only other requirement is that whenever you create any object in Swarm, you should always *re-assign* the object, when createEnd is called.

```
anObject = [anObject createEnd] ;
```

This is because certain proto-objects in the swarm library will not return themselves at createEnd time. In fact, they may return a completely different class of object, which happens to satisfy the needs of the user. We therefore suggest that even when createEnding your own classes you should stick to this standard creation format.

In some classes, you will see that some "convenience methods" for object creation have been provided. These are basically parametrized constructors that the author of the class felt would be handy. However, the objects that result from the use of these "convenience methods" should not differ in any way from an object created via a sequential set of separate methods called during the create phase (as long as each of the appropriate parameters are set). It is important to retain the "null constructor" for a couple of reasons: 1) it allows the interface for a class to *grow* without breaking legacy code and 2) it facilitates the use of development and design tools in handling objects. JavaBeans is one example where this particular constraint (the requirement of a null constructor) is in use and necessary, today.

B.4. Collections and Defobj

Two last pieces of advice:

1. When using the Collections library, if you want to create your own versions of the collections, don’t do it by subclassing the collections themselves. Instead, create a different class of object which contains inside it, an instance of the appropriate class (this is called delegation in the OOP community). You should do this because the actual subclassing of objects which actively use the createPhase stuff (by actively I mean ones that don’t return self on a createEnd), is not well supported.
2. Defobj is the most basic library in Swarm. It provides the foundation on which the system builds schedules, collections and swarmObjects. It is therefore quite involved and you should not feel disheartened if the concepts embodied within it seem unfamiliar, or if the code seems a bit cryptic.

You should now be ready to use Objective C in a more or less Swarm compliant way. Theoretically, all you need to do is follow these standards. In particular, you should be able to code your simulations without needing to know anything else about the language extensions (you still need to learn about the

libraries and tools provided by Swarm, but their interface is written in straight Objective C, so there should be no language barrier).

Appendix C. Random Library Appendix

C.1. Supplemental comments on random number generators

Please consider some additional warnings about the usage of random number generators

1. DO NOT use generators with bad statistical properties. See Advanced Usage Guide for a discussion of the generators implemented in this library.
2. DO NOT use generators whose maximum cycle length is too short for the intended application; you don't want your generators to start repeating themselves. Be especially aware of this if you use the PMMLCGgen class of generator; these have good properties but a fairly short cycle. See Advanced Usage Guide to read more about how to select a generator.
3. AVOID having generators in your simulation run in 'lock-step', producing output that is statistically correlated. This may happen if you have several generators of the same class, all started with the same default seed.
4. Be aware that even the best generators can have unexpected correlations with particular implementations of some models. As a result, in some cases using a "better" random number generator can result in worse (less correct) model behavior than one could obtain when using a "bad" generator. If you suspect your model may have this kind of problem, you probably should re-run some experiments using a different underlying generator, to make sure the results are (statistically at least) the same. (For examples of this, see the references [Ferrenberg et al 1992] and [Nature 1994].)

C.2. Usage Guide

C.2.1. Usage Guide for Generators

A note on 'simple' vs. 'split' generators

Most of the generators supplied are of the 'simple' variety. Think of these as supplying a single, long stream of pseudorandom numbers. The description in the introduction of how to obtain generator output assumed a simple generator.

There are also two generators, C2LCGXgen and C4LCGXgen, which are of the 'split' variety. Think of them as consisting of a number of virtual generators, each supplying an independent stream of numbers which we can divide up into a number of segments of a given length. To obtain output from such a generator, we need to specify what virtual generator to draw from:

```
myUnsigned = [mySplitGenerator getUnsignedSample: virtualgen];
```

Read more about how to manage split generators below.

I shall first discuss 'simple' generators, and then discuss how 'split' generators differ from 'simple' ones. In the following text, wherever I use `PSWBgen` as an example you may substitute any other generator.

Note: any name that starts with `my` is meant to designate a variable of the appropriate type which you have defined in your own program.

Note: on defining variables that hold (pointers to) generators: it is now a convention in the rest of Swarm that if you want to specify what type of object a pointer should point to, you say:

```
id <protocolname> varname;
varname = [classname create: aZone];
```

instead of

```
classname *varname;
varname = [classname create: aZone];
```

Although it is usually the case that the `protocolname = the classname`, in some cases it is not. And publishing the protocols allows the programmers to keep unpublished what should remain internal private class methods.

The generators are different from other Swarm objects, in that they all perform the same function; they are drop-in replacements for each other. The 'split' generators (`C2LCGXgen`, `C4LCGXgen`) all conform to the same protocol, `<SplitRandomGenerator>`. The 'simple' (non-split) generators all conform to the same protocol, `<SimpleRandomGenerator>`.

Thus, when defining generators in your own program, you should say

```
id <SimpleRandomGenerator> varname;
```

```
varname = [classname create: aZone];
```

(Though see below for the different create methods available.)

For backward compatibility, protocols <LCG1gen>, <TT800gen> etc. are still defined, *but their use is deprecated and they may disappear later.*

C.2.1.1. Simple generators

You create a generator in one of 3 ways:

C.2.1.1.1. the lazy way

```
id <SimpleRandomGenerator> myGenerator;
myGenerator = [ PSWBgen createWithDefaults: [self getZone] ];
```

This allocates the object and initializes it with STARTSEED, which equals NEXTSEED if -varyseed was not specified, or RANDOMSEED if it was. (These macros are defined in the file 'randomdefs.h' in the source directory.)

C.2.1.1.2. using a single seed value

```
id <SimpleRandomGenerator> myGenerator;
myGenerator = [ PSWBgen create: [self getZone]
setStateFromSeed: mySeed ];
```

This allocates the object and initializes it with your seed value. If the object actually requires a vector of seed values to fill the state, this method generates the rest of the values needed using an inline PMMLCG generator.

You can find out later what seed value was used to initialize the generator:

```
myUnsigned = [ myGenerator getInitialSeed ];
```

And you can find out what the largest valid seed value is by calling

```
myUnsigned = [ myGenerator getMaxSeedValue ];
```

(In the current version of the library, the largest valid seed value is 2^{32}-1 for all the generators. The seed may not be 0.)

You may reset the generator's state at any time using this method:

```
[ myGenerator setStateFromSeed: mySeedValue ];
```

This will also reset to 0 the `currentCount` variable.

Alternatively, you may use the new -reset method [myGenerator reset], which resets the generator its state at startup, or its state at the point when -setStateFromSeed(s) was last used. Counters are zeroed.

C.2.1.1.3. using a vector of seed values

Assume we have defined a fixed array at compile time:

```
unsigned  int mySeedVector [vectorLength];
```

Then we can do this:

```
  id <SimpleRandomGenerator> myGenerator;
  myGenerator = [ PSWBgen create: [self getZone]
setStateFromSeeds: mySeedVector ];
```

You can find out how many seed values are required by asking

```
myUnsigned = [ myGenerator lengthOfSeedVector ];
```

(Obviously, you must first successfully have created the object to do this, for example using createWithDefaults! Or, see data in Generator Data Table)

And we allocate the seed vector dynamically this way:

```
unsigned int *mySeedVector;
mySeedVector = [[self getZone] alloc: [ myGenerator lengthOfSeedVector]];
```

You can find out what vector of seed values was used to initialize the object:

```
unsigned int *myVector;
myVector = [ myGenerator getInitialSeeds ];
```

And you can find out the largest seed values that are allowed for the particular generator:

```
unsigned int *myVectorToo;
myVectorToo = [ myGenerator getMaxSeedValues ];
```

(These values vary from generator to generator, and they may not be the same for all elements of the vector for a given generator. Valid seeds never take the value 0.)

NOTE: in the above two calls, the variable myVector is set to point to an array internal to the generator. If you want to preserve the array's values outside the generator, you need to allocate space in your

program either statically or dynamically, and use a for-loop to copy data from myVector[i] to myAllocatedVector[i].

You may reset the generator's state at any time by using the method

```
[ myGenerator setStateFromSeeds: (unsigned *) mySeedVector ];
```

This will also reset to 0 the currentCount variable.

NOTE: if you set a generator's state from a vector of seeds, the call:

```
myUnsignedValue = [ myGenerator getInitialSeed ];
```

will return a value of 0 (an invalid seed). On the other hand, if you initialize the generator with a single seed value, the call

```
mySeedVector = [ myGenerator getInitialSeeds ];
```

will return the seed vector that would produce identical output to what you obtained using the single seed.

C.2.1.1.4. antithetic values

You can make the generator serve up antithetic values by setting:

```
[ myGenerator setAntithetic: YES ];
```

If thus set, this makes -getUnsignedSample return (unsignedMax-x) instead of x, and the floating point methods return (1.0 - y) instead of y. The default for this parameter is that it is not set.

You can ascertain if this flag is set by calling

```
myBooleanValue = [ myGenerator getAntithetic ];
```

C.2.1.1.5. generator output

You obtain successive pseudorandom numbers from a generator by calling:

```
myUnsignedValue = [ myGenerator getUnsignedSample ];
```

The largest value that may be returned can be found by asking

```
myUnsignedValue = [ myGenerator getUnsignedMax ];
```

(The smallest value returned is always 0.)

If you would rather have floating point output in the range [0.0,1.0), you call one of these:

```
// Using 1 unsigned value to fill the mantissa:
myFloatValue  = [ myGenerator getFloatSample ];
myDoubleValue = [ myGenerator getThinDoubleSample ];

// Using 2 unsigned values to fill the mantissa:
myDoubleValue     = [ myGenerator getDoubleSample ];
myLongDoubleValue = [ myGenerator getLongDoubleSample ];
```

NOTE that the last method is not portable, because the size of a long double varies and hence the precision varies between architectures.

Finally, you can obtain a count of how many variates have been generated:

```
myLongLongInt = [ myGenerator getCurrentCount ];
```

(currentCount is an unsigned long long int, which counts up to 2^{64}.)

C.2.1.2. Split generators

A split generator is a generator for which we are able to split the output stream into arbitrary non-overlapping segments, which we can access directly and easily. Such segments are statistically independent streams of (pseudo)random numbers.

We configure a split generator as consisting of a number (A) of "virtual generators", each of which has access to a number (2^v) of segments of length 2^w. The parameters A,v,w are specified when the generator is created. For example, for the C4LCGXgen generator, the default creation values are A=128, v=31, w=41. The only limitation is that $A*(2^v)*(2^w)$ must not exceed the generator's cycle length, which is 2^{60} for C2LCGXgen and 2^{120} for C4LCGXgen.

We specify the configuration (A,v,w) at create time this way:

```
  id <SplitRandomGenerator> myGenerator;
  myGenerator = [ C4LCGXgen create: [self getZone]
setA: 64 setv: 20 setw: 76
setStateFromSeed: mySeedValue ];

  id <SplitRandomGenerator> myGenerator;
  myGenerator = [ C4LCGXgen create: [self getZone]
setA: 32 setv: 25 setw: 60
setStateFromSeeds: (unsigned *) mySeedVector ];
```

(In both cases, the only limitation is that $A * 2^v * 2^w$ must be less than the generator's period, 2^{60} for C2LCGX and 2^{120} for C4LCGX.)

For obtaining output, we need to specify which of the A 'virtual' generators we want to draw from:

```
myUnsignedValue   = [ myGenerator getUnsignedSample: 12 ];
myFloatValue      = [ myGenerator getFloatSample: myVirtualGenerator ];
```

```
myDoubleValue     = [ myGenerator getThinDoubleSample: someUnsignedValue ];
myDoubleValue     = [ myGenerator getDoubleSample: 32 ];
myLongDoubleValue = [ myGenerator getLongDoubleSample: 0 ];
```

Virtual generators are numbered from 0 to (A-1).

Obtaining the current count of variates generated likewise:

```
myLongLongInt = [ myGenerator getCurrentCount:   myVirtualGenerator ];
myLongLongInt = [ myGenerator getCurrentSegment: myVirtualGenerator ];
```

The latter call indicates what segment number the specified virtual generator is currently drawing numbers from.

Other than these methods, the methods discussed above under 'simple' generators are the same for 'split' generators.

In *addition* to this, 'split' generators have the following methods to manage the virtual generators:

```
// Place all virtual generators at the start of the first segment:
[ myGenerator initAll ]; // done automatically at creation

// Place all virtual generators back to the start of the current segment:
[ myGenerator restartAll ];

// Place all virtual generators at the start of the next segment:
[ myGenerator advanceAll ];

// Place all virtual generators at the start of the indicated segment:
[ myGenerator jumpAllToSegment: myLongLongIntValue ];
```

You may also address individual virtual generators:

```
[ myGenerator initGenerator:    myVgen ];
[ myGenerator restartGenerator: myVgen ];
[ myGenerator advanceGenerator: myVgen ];
[ myGenerator jumpGenerator:    myVgen    toSegment: myLongLongIntValue ];
```

InternalState methods common to simple and split generators:

```
// Print (most of) the object's state data to a stream:
[ myNormalDist describe: myStream ];
```

The stream myStream may be created thus:

```
id myStream = [ OutStream create: [self getZone] setFileStream: stdout ]; or
id myStream = [ OutStream create: [self getZone] setFileStream: stderr ];

   // Get the (class) name of the object:
   myString = [ myNormalDist getName ];
```

```
// Get the object's 'magic number', used by putStateInto / setStateFrom:
myUnsigned = [ myNormalDist getMagic ];
```

C.2.1.3. Saving and Resetting State

You may save, and later restore, the internal state of a generator using these methods:

```
// Get the size of the memory buffer needed by putStateInto / setStateFrom:
myUnsigned = [ myGenerator getStateSize ];

// Extract the generator's state data into your memory buffer:
[ myGenerator putStateInto: myBuffer ];

// Set the generator's state from data in a memory buffer:
[ myGenerator setStateFrom: myBuffer ];
```

To illustrate, assume the following data definitions:

```
FILE * myFile;
const char * myFileName = "MyGenFile.bin"; // or whatever
int stateSizeG;
id stateBufG;
int status;
```

The following code shows how to save an object's state to disk: (You should add your own code to deal with disk file errors, either aborting or printing out error messages.)

```
// Ask how big a buffer we need:
stateSizeG = [ myGenerator getStateSize ];

// Allocate memory for the buffer:
stateBufG  = [[self getZone] alloc: stateSizeG];

// Ask the generator to put state data into the buffer:
[ myGenerator putStateInto: (void *) stateBufG ];

// Open a disk file for output:
myFile = fopen(myFileName, "w");
if (myFile == NULL) { }; // error on open: disk full, or no permissions

// Write the state buffer to disk in binary form:
status = fwrite(stateBufG, stateSizeG, 1, myFile);
if (status < 1) { }; // error on write: disk full?

// Close the file
status = fclose(myFile);
if (status) { }; // error on close ?
```

```
// Free the memory allocated to the buffer:
[[self getZone] free: stateBufG];

// Or, for test purposes, just zero the buffer data instead:
// memset(stateBufG, 0, stateSizeG);
```

This code shows how to set an object's state from a disk file:

```
// Ask how big a buffer we need:
stateSizeG = [ myGenerator getStateSize ];

// Allocate memory for the buffer:
stateBufG  = [[self getZone] alloc: stateSizeG];

// Open a disk file for input:
myFile = fopen(myFileName, "r");
if (myFile == NULL) { }; // error on open: file not found

// Read state data into the memory buffer:
status = fread(stateBufG, stateSizeG, 1, myFile);
if (status < 1) { }; // error on read

// Close the file:
status = fclose(myFile);
if (status) { }; // error on close

// Ask the generator set its state from the buffer data:
[ myGenerator setStateFrom: (void *) stateBufG ];

// Free the memory allocated to the buffer:
[[self getZone] free: stateBufG];
```

C.2.2. Usage Guide for Distributions

Where I use `NormalDist` in examples below, substitute any other distribution and its parameters as needed.

NOTE: any name that starts with `my` is meant to designate a variable of the appropriate type which you have defined in your own program.

C.2.2.1. Creating distributions

You create a distribution in one of several ways:

C.2.2.1.1. the lazy way:

```
    id <NormalDist> myNormalDist;
    myNormalDist = [ NormalDist createWithDefaults: [self getZone]];
```

This method will create a distribution object with no default statistical parameters set, as well as a fresh generator object connected to it. The generator object is initialized with STARTSEED (see the discussion above). Different distribution classes use different generators for this purpose.

C.2.2.1.2. Without default parameters, using a simple generator

```
    id <NormalDist> myNormalDist;
    myNormalDist = [ NormalDist create: [self getZone]
  setGenerator: mySimpleGenerator ];
```

`myGenerator` must of course first have been set to point to a random generator of the 'simple' type. Note that you cannot assign a different generator to a distribution after it has been created.

You can create the generator at the same time as the distribution:

```
    id <NormalDist> myNormalDist;
    myNormalDist = [ NormalDist create: [self getZone]
  setGenerator: [TT800gen create: [self getZone]
  setStateFromSeed: 34453]         ];
```

C.2.2.1.3. Without default parameters, using a split generator

```
    id <NormalDist> myNormalDist;
    myNormalDist = [ NormalDist create: [self getZone]
  setGenerator: mySplitGenerator
  setVirtualGenerator: 7 ];
```

or perhaps

```
    id <NormalDist> myNormalDist;
    myNormalDist = [ NormalDist create: [self getZone]
  setGenerator: [C4LCGXgen createWithDefaults: [self getZone]]
  setVirtualGenerator: 99 ];
```

A split generator can be thought of as comprising a set of virtual generators (streams of random numbers), and a distribution object must be 'connected' to one of these streams. You cannot re-assign the generator or the virtual generator after a distribution object has been created.

In all these cases, when we want to obtain a random variate from this distribution object we need to specify the statistical parameters:

```
myDouble = [ myNormalDist getSampleWithMean: 3.3 withVariance: 1.7];
```

You can use different parameters for every call. (And you can use this call even if default parameters have been set.)

C.2.2.1.4. With default parameters, using a simple generator

```
  id <NormalDist> myNormalDist;
  myNormalDist = [ NormalDist create: [self getZone]
setGenerator: mySimpleGenerator
setMean: 7.6 setVariance: 1.2 ];
```

C.2.2.1.5. With default parameters, using a split generator

```
  id <NormalDist> myNormalDist;
  myNormalDist = [ NormalDist create: [self getZone]
setGenerator: mySplitGenerator
setVirtualGenerator: 33
setMean: 3.2 setVariance: 2.1 ];
```

In these cases, we do not need to specify parameters to get a random number:

```
myDouble = [ myNormalDist getDoubleSample ];
```

However, you *are* allowed to specify parameters even if default parameters have been set.

(Of course, different distributions have different parameters: RandomBitDist has none, the Uniform objects have minimum and maximum limit values, NormalDist and LogNormalDist use Mean and Variance, ExponentialDist only Mean, and GammaDist used alpha and beta. See the individual distribution protocols or the file `random/distributions.h` for the specific methods available.)

C.2.2.1.6. You may reset the default parameters this way, as often as you like

```
[ myNormalDist setMean: 3.3 setVariance: 2.2 ];
```

C.2.2.1.7. You can obtain the current values of parameters

```
// Default parameters:
myDouble1 = [ myNormalDist getMean ];
myDouble2 = [ myNormalDist getVariance ];
myDouble3 = [ myNormalDist getStdDev ];

// Get a pointer to the generator object:
myOtherGenerator = [ myNormalDist getGenerator ];

// Get the number of the virtual generator (if a split generator is used):
myUnsignedValue  = [ myNormalDist getVirtualGenerator];

// Find out if default parameters have been set:
myBoolean        = [ myNormalDist getOptionsInitialized ];

// Find out how many variates the object has delivered so far:
// (The counter is an unsigned long long int, which goes up to 2^64.)
myLongLongInt    = [ myNormalDist getCurrentCount ];
```

C.2.2.1.8. You can reset the variate counter and other state variables this way

```
[ myNormalDist reset ];
```

This is most likely done in conjunction with resetting the connected generator, using

```
[ myGenerator setStateFromSeed: mySeedValue ]
```

or simply

```
[ myGenerator reset ];
```

C.2.2.1.9. Finally, we have the InternalState protocol methods

```
// Print (most of) the object's state data to a stream:
[ myNormalDist describe: myStream ];
```

The stream myStream may be created thus:

```
id myStream = [ OutStream create: [self getZone] setFileStream: stdout ]; or
id myStream = [ OutStream create: [self getZone] setFileStream: stderr ];

// Get the (class) name of the object:
myString = [ myNormalDist getName ];
```

```
// Get the object's 'magic number', used by putStateInto / setStateFrom:
myUnsigned = [ myNormalDist getMagic ];
```

C.2.2.2. Saving And Restoring State

You may save, and later restore, the internal state of a distribution object using InternalState methods.

- See the Generator Usage Guide, which describes how to do this. The code for saving/restoring distributions would be similar.
- Note that saving the state of a distribution object will NOT automatically save the state of the attached generator; you are responsible for doing so. (Since it is possible, even encouraged, to use a single generator to feed several distribution objects, this is the only sane way of doing it.)

C.3. Advanced Usage Guide

This section amplifies the Usage Guide with material on how to choose a random generator for your simulation, what default generators have been implemented for the distribution objects, and information on the set of test programs used.

C.3.1. Choosing a Generator

C.3.1.1. Choosing A Generator

In this version of Random for Swarm there are a total of 36 different generators implemented. If you are a serious simulationist you need to select which one(s) to use for your model.

Here are some factors to consider:

a. We want a generator to have as good statistical properties as possible. We measure this by subjecting the generators to various tests. I have subjected the implemented generators to two sets of tests, Diehard and ENT. (Look in directory /testR6 of the test package.) (The Generators quality table summarizes the test results. The highlights are:

   i. The LCG and SCG generators are of *very* poor quality (they fail many of the tests), and should never be used. [They are likely to disappear in the next release.]

ii. The lagged-Fibonacci generators (ACG, SWBi, PSWB) all fail the Diehard 'Birthday Spacings Test', and are therefore only conditionally recommended for use.

iii. The other 32-bit generators pass all tests, and I therefore have no reason not to recommend them all for use.

iv. The 31-bit generators all fail certain tests because one bit has a constant value. Beyond that they all seem to be ok.

b. We want a generator to have a long enough period for our purpose, and in general the longer the period the better. (However, note that to generate 2^{64} random numbers from a fast generator like MT19937 would take 2.1 million years on a 486/66, so in practice any generator with a period close to 2^{60} or larger will be acceptable.) The PMMLCG generators, although they are of acceptable quality otherwise, have a period less than 2^{31} which we can exhaust in under 3 hours. So use those only for quick 'toy' applications.

c. We want a generator to execute efficiently, the faster the better. The Generators data table indicates the execution times for the generators as implemented.

d. We want a generator to take as little resources (memory) as possible. The Generators data table indicates the size of each generator's state in bits.

e. Other things being equal, we want our generator to have a single full period rather than a number of shorter periods, since we may not know whether a particular starting seed will put us into a long or a short subcycle. This disqualifies SWB, and possibly the new MWC and RWC generators (Marsaglia does not say how many periods these generators have, but only gives the period length.)

C.3.1.2. Strategy For Using Random Generators

There are 3 possible strategies for using random generators:

a. Use one single generator for your whole simulation, and have all 'users' of randomness (distributions and other objects) call this single generator in an interleaved fashion. For this purpose, generators such as MT19937, TT800, TT775, TT443 (and possibly PSWB and SWB) seem particularly well suited since they have immense periods. The code in `random/random.m` shows how to connect several distribution objects to a single random generator. The generator `randomGenerator` supplied there is of class MT19937.

b. Use a single generator of long period, but divide this long period up into a number of non-overlapping (hence statistically independent) segments, and let each 'user' of randomness draw their random numbers from separate segments. Doing this requires that we be able to quickly access these separate segments. The 'split' generators C2LCGX and C4LCGX implement such a scheme.

You can specify at creation how you want the period of these generators subdivided. (See the source code for details.)

c. Use a separate random generator for each 'user' of randomness. In this case, you need to make sure that two or more generators of the same type are not started with the same seed, since in this case their output will be highly correlated. Provide your own seeds, or use RANDOMSEED or NEXTSEED.

The distribution objects, if created with the 'createWithDefault: aZone' method, will create for themselves a fresh generator, with each class of distribution using a different class of generator. All the generators in this case are initialized with NEXTSEED (or RANDOMSEED, if you start the program with `-varyseed`).

C.3.1.3. Generator Quality

These tables shows the results of testing the generator objects statistically:

Table C-1. Random Library: Generator Statistical Tests

Generator	timing uS (unsigned)	bits state	period (s) # length	tests failed (x)
				abcdefghijklmnopqrstuvwx
30-bit output				
SCG	3.328	1650	1 2_{55}	x.xx2xxxxxxx..x..xx.xx..
32-bit output				
LCG1	2.564	32	1 2_{32}	x...xxxxxxx.........x...
LCG2	2.564	32	1 2_{32}	x...xxxxxxx.........x...
LCG3	2.564	32	1 2_{32}	x...xxxxxxx.........x...
ACG	2.702	1760	1 2_{55}	x.....
SWB1	3.285	1185	64 2_{1178}	x.....
SWB2	3.285	769	1536 2_{757}	x.....
SWB3	3.285	673	192 2_{664}	x.....
PSWB	3.452	1377	1 2_{1376}	x.....
MWCA	3.399	64	?? 2_{59}	.....
MWCB	3.420	64	?? 2_{59}	.....
MT19937	3.698	19968	1 2_{19937}	.....

Generator	timing uS (unsigned)	bits state	period (s) # length	tests failed (x)
TT800	4.654	800	1 2_{800}	.....
C3MWC	6.387	192	?? 2_{118}	.....
RWC2	7.445	96	?? 2_{92}	.....
RWC8	14.649	288	?? 2_{250}	.....
31-bit output				
C2TAUS1	4.078	62	1 2_{60}	1..-1x111x1.....x...
C2TAUS2	4.078	62	1 2_{60}	1..-1x111x1.....x...
C2TAUS3	4.078	62	1 2_{60}	1..-1x111x1.....x...
TT775	4.654	775	1 2_{775}	1..-1x111x1.....x...
TT403	4.670	403	1 2_{403}	1..-1x111x1.....x...
PMMLCG1	4.715	31	1 2_{31}	1..-1x111x1.....x...
PMMLCG2	4.715	31	1 2_{31}	1..-1x111x1.....x...
PMMLCG3	4.715	31	1 2_{31}	1..-1x111x1.....x...
PMMLCG4	4.715	31	1 2_{31}	1..-1x111x1.....x...
PMMLCG5	4.715	31	1 2_{31}	1..-1x111x1.....x...
PMMLCG6	4.715	31	1 2_{31}	1..-1x111x1.....x...
PMMLCG7	4.715	31	1 2_{31}	1..-1x111x1.....x...
PMMLCG8	4.715	31	1 2_{31}	1..-1x111x1.....x...
PMMLCG9	4.715	31	1 2_{31}	1..-1x111x1.....x...
C2LCGX	7.029	62	1 2_{60} (Split)	1..-1x111x1.....x...
MRG5	9.674	155	1 2_{155}	1..-1x111x1.....x...
MRG6	10.449	186	1 2_{186}	1..-1x111x1.....x...
MRG7	10.913	217	1 2_{217}	1..-1x111x1.....x...
C4LCGX	11.688	124	1 2_{210} (Split)	1..-1x111x1.....x...
C2MRG3	13.459	186	1 2_{185}	1..-1x111x1.....x...

Test code	Test suite	Explanation of test codes
a	Diehard	Birthday Spacings Test
b	Diehard	Overlapping 5-permutation Test
c	Diehard	Binary Rank Test (31x31)
d	Diehard	Binary Rank Test (32x32)

Test code	Test suite	Explanation of test codes
e	Diehard	Binary Rank Test (6x8)
f	Diehard	Bitstream Test (overlapping 20-tuples)
g	Diehard	OPSO (Overlapping Pairs, Sparse Occupancy)
h	Diehard	OQSO (Overlapping Quadruples, Sparse Occupancy)
i	Diehard	DNA Test
j	Diehard	Count-the-1's Test (integers)
k	Diehard	Count-the-1's Test (specific bytes)
l	Diehard	Parking Lot Test
m	Diehard	Minimum Distance Test
n	Diehard	3D Spheres Test
o	Diehard	Squeeze Test
p	Diehard	Overlapping Sums Test
q	Diehard	Runs Test
r	Diehard	Craps Test
s	ENT	Entropy Test
t	ENT	Compression test
u	ENT	Chi-Square Test
v	ENT	Arithmetic Mean
w	ENT	Monte Carlo value for Pi
x	ENT	Serial Correlation Coefficient

Indication	Explanation of indications
.	The generator passed this test
1	The generator passed this test, except for the lowest bit
2	The generator passed this test, except for the 2 lowest bits
x	The generator failed this test completely
-	This test cannot be passed by this generator (too few bits)

Notes.

- For 31-bit generators, it is normal to fail 1 part of these tests:a,e,g,h,i,k. This is because we left-shift the output of these generators by 1 bit, so that the lowest bit is always 0.
- For 31-bit generators, it is normal to fail test d (32x32 rank test).
- All 31-bit generators also fail tests f, j, and u (and most others don't.) This is *likely* due to the constant low bit.

Choosing A Generator.

- Clearly unacceptable generators: LCG1, LCG2, LCG3, SCG.
- Conditionally recommended generators: ACG, SWB1, SWB2, SWB3, PSWB.
- Use with caution: the PMMLCGx generators (due to their very short period 2^{31}).
- All other generators are recommended at this time.

C.3.1.4. More generator data

And this table gives further data about the generators:

Table C-2. Random Library: Generator Data

Generator	Seeds	Modulus	Cycles (length)	Bits	Speed	State
(a) Simple Short Generators						
LCG1	1	2_{32}	1 m	32	1.442	32
LCG2	1	2_{32}	1 m	32	1.442	32
LCG3	1	2_{32}	1 m	32	1.442	32
PMMLCG1	1	2_{31-1}	1 m-1	31	0.784	31
PMMLCG2	1	2_{31-1}	1 m-1	31	0.784	31
PMMLCG3	1	2_{31-1}	1 m-1	31	0.784	31
PMMLCG4	1	2_{31-1}	1 m-1	31	0.784	31
PMMLCG5	1	2_{31-105}	1 m-1	31	0.784	31

Generator	Seeds	Modulus	Cycles (length)	Bits	Speed	State
PMMLCG6	1	2_{31-225}	1 m-1	31	0.784	31
PMMLCG7	1	2_{31-325}	1 m-1	31	0.784	31
PMMLCG8	1	2_{31-85}	1 m-1	31	0.784	31
PMMLCG9	1	2_{31-249}	1 m-1	31	0.784	31
(b) Simple Long Generators						
ACG	55	2_{32}	1 2_{55}	32	1.369	760
SCG	55	10_{9}	1 2_{55}	30	1.111	650
SWB1	37+c	2_{32}	64 2_{1178}	32	1.126	185
SWB2	24+c	2_{32}	1536 2_{757}	32	1.126	769
SWB3	21+c	2_{32}	192 2_{664}	32	1.126	673
PSWB	43+c	2_{32-5}	1 2_{1376}	32	1.070	1377
TT403	13	2_{31}	1 2_{403}	31	0.792	403
TT775	25	2_{31}	1 2_{775}	31	0.795	775
TT800	25	2_{32}	1 2_{800}	32	0.795	800
MT19937	624	2_{32}	1 2_{19937}	32	1.000	19937
MRG5	5	2_{31-1}	1 2_{155}	31	0.382	155
MRG6	6	2_{31-1}	1 2_{186}	31	0.354	186
MRG7	7	2_{31-1}	1 2_{217}	31	0.339	217
MWCA	2	2_{32}	? 2_{59}	32	1.088	64
MWCB	2	2_{32}	? 2_{59}	32	1.088	64
RWC2	3	2_{32}	? 2_{92}	32	0.497	96
RWC8	18s	2_{32}	? 2_{250}	32	0.252	288
(c) Long Generators with Splitting Facilities: (none)						
(d) Combined Generators						
C2TAUS1 (M)	2	2_{31-1}	1 2_{60}	31	0.907	62
C2TAUS2 (M)	2	2_{31-1}	1 2_{60}	31	0.907	62
C2TAUS3 (M)	2	2_{31-1}	1 2_{60}	31	0.907	62
C2MRG3 (M)	6	2_{31-1}	1 2_{185}	31	0.275	186

Generator	Seeds	Modulus	Cycles (length)	Bits	Speed	State
C3MWC (M)	6	2_{32}	? 2_{118}	32	0.570	192
(e) Combined Generators with Splitting Facilities						
C2LCG (M,S)	2	2_{31-85}	1 2_{60}	31	0.526	62
C4LCG (M,S)	4	2_{31-1}	1 2_{120}	31	0.316	124

Generator	Calculating cycle lengths
LCGi	cycle = m = 2_{32}
PMMLCGi	cycle = m-1 < 2_{31}
ACG	cycle = 2_r
SCG	cycle = 2_r
SWBi	cycle = ($2_{32r - 232s}$) / #cycles
PSWB	cycle = $m_{r - ms}$
TGFSRi	cycle = $2_{w*N - 1}$
MRGi	cycle = $m_{i - 1}$
C2MRG3	cycle = $(m1_{3 - 1)*(m23 - 1)/2}$
C2TAUSi	cycle = Mask1 * Mask2
C2LCG	cycle = (m1 * m2) / 2
C4LCG	cycle = (m1 * m2 * m3 * m4) / 8
MWCA, MWCB	cycle = ? (not specified by Marsaglia)
C3MWC	cycle = ? " "
RWC2	cycle = ? " "
RWC8	cycle = ? " "

C.3.2. Default Generators for the Distributions

C.3.2.1. Random Library: Default Generators

When distributions are created using the **`createWithDefaults: aZone`** method, they create their own generator and initialize it with NEXTSEED (or with RANDOMSEED, if you started the program with the `-varyseed` switch).

The generators used are as follows:

Table C-3. Random Library: Default Generators

Distribution		Generator
RandomBitDist	uses	C2TAUS1gen
BernoulliDist	uses	C2TAUS2gen
UniformIntegerDist	uses	TT403gen
UniformUnsignedDist	uses	TT775gen
UniformDoubleDist	uses	TT800gen
NormalDist	uses	MWCAgen
LogNormalDist	uses	MWCBgen
ExponentialDist	uses	C2TAUS3gen
GammaDist	uses	PSWBgen

These generators were chosen on the basis of quality and execution speed.

C.3.2.2. Utility Generator And Distributions

There are 4 default random objects defined in `random/random.m`. These are:

```
id <MT19937gen>          randomGenerator;
id <UniformIntegerDist>   uniformIntRand;
id <UniformUnsignedDist>  uniformUnsRand;
id <UniformDoubleDist>    uniformDblRand;
```

These objects may be called from anywhere in your program. Note (a): the generator is initialized with NEXTSEED or RANDOMSEED depending on the use of the `-varyseed` command line option. Note (b): the distribution objects are created *without* default statistical parameters.

C.3.3. Random Library Test Programs

1. In a separate tar file (ftp://ftp.swarm.org/pub/swarm/RandomTests-0.81.tgz), available at the SFI ftp site, there are a set of programs which exercise aspects of the generator objects' functionality. The

following (very utilitarian) programs are available:

- **testR0.** a program which exercises every generator and distribution, verifying correct operation and comparing output to that obtained on the author's system.
- **testR1.** a program which prints out diagnostic output for code in random.m.
- **testR2.** a program which asks each distribution and generator to describe itself using the Swarm xprint method.
- **testR3.** a program which asks each distribution and generator to describe itself using the objects' 'describe' method.
- **testR4.** a program that performs timing tests on each generator and distribution, computing the time it takes to call each object 10,000,000 times.
- **testR6.** a program that generates a binary file containing 2.5M variates from a specified generator, for purposes of statistical testing (e.g. with ENT or Diehard.)
- **testR7.** a program which records, for each generator, the value of unsignedMax, the number of output bits, and the value of lengthOfSeedVector.
- **testR9.** a program which records, for each generator and distribution, the object's 'magic number' and the buffer size needed for getState/setState.

2. Statistical testing: the generators have been put through the tests in the `/testR6/ENT` and `/testR6/Diehard` directories. The raw data can be found there. The results are summarized in the test log files found in the same test distribution. The distribution objects have not been tested statistically yet.

The code here represents an effort to implement several efficient, reasonably safe generators. The algorithms come from reading the literature (Bibliography). These algorithms have been implemented as accurately as possible and run through some simple tests. Some generators, included here for historical reasons only, are known to have bad statistical properties, and their use is deprecated. See Advanced Usage Guidefor information on the quality of the included generators.

While the objects in this library are believed to function correctly, the prudent and paranoid modeller would do well testing them in some domain-specific way. One easy way to do this is to run an experiment twice: once with one class of generator (say, PMMLCG), and once with another (say, SWB). If the results differ radically, then you can suspect one of the generators. If they don't, well, the generators still might be faulty!

The generators supplied with this release have been subjected to statistical testing using George Marsaglia's *Diehard* tests as well as John Walker's entropy tests (ENT). The results of these tests are summarized in Generator quality table. Other data on the properties of the generators are found there as well. These data support a discussion of how to choose one or more generators for your simulation.

The ENT test is included in the tarball of test programs mentioned above. The Diehard tests are copyright and hence are not, but they can be downloaded from the web at: ftp://ftp.csis.hku.hk/pub/random (ftp://ftp.csis.hku.hk/pub/random).

The distribution objects have not been statistically tested.

C.4. Resources for random number generation

This section lists some of the source reference material used in programming the random generators and distributions. The following is a list of source articles or books from which the generator and distribution objects were implemented

C.4.1. Generators

- **LCG.** a golden oldie; see [Knuth 1981] or [Numerical Recipes].
- **PMMLCG.** see [Park & Miller 1988], [L'Ecuyer & Cote 1991] and [L'Ecuyer & Andres 1997].
- **ACG.** a golden oldie; see [Knuth 1981] or [Numerical Recipes].
- **SCG.** a golden oldie; see [Knuth 1981] or [Numerical Recipes].
- **SWB.** see [Marsaglia & Zaman 1991]
- **PSWB.** see [Marsaglia & Zaman 1991]
- **MRG.** see [L'Ecuyer et al 1993]
- **C2MRG3.** see [L'Ecuyer 1996(a)] and [L'Ecuyer 1999(a)]
- **C2TAUS.** see [Tezuka & L'Ecuyer 1991], [L'Ecuyer 1996(b)] and [L'Ecuyer 1999(b)]. Also [Tausworthe 1965].
- **TGFSR (TT800, TT775, TT403).** see [Matsumoto & Kurita 1992] and [Matsumoto & Kurita 1994].
- **MT19937.** see [Matsumoto & Nishimura 1998].
- **MWCA, MWCB, C3MWC, RWC2, RWC8 ("Mother").** See [Marsaglia 1994(a)] and [Marsaglia 1994(b)].
- **C2LCGX.** See [L'Ecuyer & Cote 1991]
- **C4LCGX.** See [L'Ecuyer & Andres 1997]

C.4.2. Distributions

- **RandomBitDist.** Code contributed by Nelson Minar. (mailto://nelson@media.mit.edu)
- **BernoulliDist.** Code contributed by Barry McMullin (mailto://mcmullin@santafe.edu).
- **UniformIntegerDist.** Code contributed by Nelson Minar (mailto://nelson@media.mit.edu).
- **UniformUnsignedDist.** Code contributed by Nelson Minar (mailto://nelson@media.mit.edu).
- **UniformDoubleDist.** Code contributed by Nelson Minar (mailto://nelson@media.mit.edu).
- **NormalDist.** See [Numerical Recipes].
- **LogNormalDist.** See [Numerical Recipes].
- **ExponentialDist.** See [Russell 1992].
- **GammaDist.** See [Watkins 1994].

C.4.3. Useful Web Sites

- Pierre L'Ecuyer maintains a personal web site (http://www.iro.umontreal.ca/~lecuyer). He has many of his own papers there, as well as further links. He has papers both on generating random numbers and on testing random number generators.
- George Marsaglia has a personal web site (http://stat.fsu.edu/~geo). His battery of tests for random generators, called Diehard, is not available there, but rather from Hong Kong (ftp://ftp.csis.hku.hk/pub/random). A GUI version of Diehard has been under development for some time, but is not yet ready.
- The pLab (http://random.mat.sbg.ac.at) project in Salzburg, Austria, also has much useful information.

Bibliography

[Ferrenberg et al 1992] Alan M. Ferrenberg, D. P. Landau, and Y. Joanna Wong, *"Monte Carlo Simulations: Hidden Errors from "Good" Random Number Generators": Physical Review Letters*, no. 23, vol. 69, December, 1992.

[Knuth 1981] Donald Knuth, *The Art of Computer Programming*, 2nd ed., vol. II, *Seminumerical Algorithms*, Addison-Wesley, Reading, 1981.

[L'Ecuyer et al 1993] Pierre L'Ecuyer, F. Blouin, and R. Couture, *"A Search for Good Multiple Recursive Random Generators.": ACM TOMACS*, vol. 3, pp. 87-98, 1993.

[L'Ecuyer 1996(a)] Pierre L'Ecuyer, *"Combined Multiple Recursive Generators.": Operations Research*, no. 5, vol. 44, pp. 816-822, 1997.

[L'Ecuyer 1996(b)] Pierre L'Ecuyer, *"Maximally Equidistributed Combined Tausworthe Generators": Mathematics and Computation*, no. 65, vol. 213, pp. 203-213, 1996.

[L'Ecuyer 1999(a)] Pierre L'Ecuyer, *"Good Parameter Sets for Combined Multiple Recursive Random Number Generators": Operations Research*, no. 1, vol. 47, pp. 159-164, 1999.

[L'Ecuyer 1999(b)] Pierre L'Ecuyer, *"Tables of Maximally-Equidistributed Combined LFSR Generators": Mathematics and Computation*, no. 225, vol. 68, pp. 261-269, 1999.

[L'Ecuyer & Andres 1997] Pierre L'Ecuyer and Terry H. Andres, *"A Random Number Generator Based on the Combination of Four LCGs.": Mathematics and Computers in Simulation*, vol. 44, pp. 99-107, 1997.

[L'Ecuyer & Cote 1991] Pierre L'Ecuyer and Serge Cote, *"Implementing a Random Number Package with Splitting Facilities": ACM TOMACS*, no. 1, vol. 17, pp. 98-111, March, 1991.

[Marsaglia 1994(a)] George Marsaglia, *"The Mother of All Random Generators": Posted by Bob Wheeler to sci.stat.consult (news://sci.stat.consult) and sci.math.num-analysis (news://sci.math.num-analysis) on behalf of George Marsaglia on October 28, 1994. The code is available at ftp.taygeta.com (ftp://ftp.taygeta.com/pub/c/mother.c)* .

[Marsaglia 1994(b)] George Marsaglia, *"Multiply-With-Carry Generators": File "mwc1.ps" on Marsaglia's Diehard CD-ROM, available online at ftp.csis.hku.hk (ftp://ftp.csis.hku.hk/pub/random)*.

[Marsaglia & Zaman 1991] George Marsaglia and Arif Zaman, *"A New Class of Random Number Generators.": Annals of Applied Probability*, no. 3, vol. 3, pp. 462-480.

[Matsumoto & Kurita 1992] M. Matsumoto and Y. Kurita, *"Twisted GFSR generators": ACM TOMACS*, vol. 2, 1992, pp. 179-194.

[Matsumoto & Kurita 1994] Makoto Matsumoto and Yoshiharu Kurita, *"Twisted GFSR Generators II": ACM TOMACS (Amended by K. Matsumoto, 8 July 1996).*, no. 3, vol. 4, pp. 254-266.

[Matsumoto & Nishimura 1998] M. Matsumoto and T. Nishimura, *"Mersenne Twister: A 623-dimensionally Equidistributed Uniform Pseudorandomnumber Generator": ACM TOMACS*, no. 1, vol. 8, pp. 3-30, 17 December 1998.

[Nature 1994] *"News and Views": Nature*, vol. 372, December, 1994.

[Numerical Recipes] W. H. Press, S. A Teukolsky, W. T. Vetterling, and B. P. Flannery, *Numerical Recipes in C*, 2nd ed., Cambridge University Press, 1992.

[Park & Miller 1988] Stephen K. Park and Keith W. Miller, *"Random Number Generators: Good Ones Are Hard to Find.": CACM*, no. 10, vol. 31, pp. 1192-1201, October 1988.

[Tausworthe 1965] R.C. Tausworthe, *"Random Numbers Generated by Linear Recurrence modulo 2": Math. Comput.*, vol. 19, pp. 201-209, 1965.

[Tezuka & L'Ecuyer 1991] Shu Tezuka and Pierre L'Ecuyer, *"Efficient and Portable Combined Tausworthe Random Number Generators.": ACM TOMACS*, no. 2, vol. 1, pp. 99-112.

[Russell 1992] Edward C. Russell, *"Building Simulation Models With SIMSCRIPT II.5"*, CACI Products Company, La Jolla, 1992, *The company's web site is: http://www.caciasl.com*.

[Watkins 1994] Kevin Watkins, *Discrete Event Simulation in C*, McGraw-Hill, 1994.

Bibliography

A short bibliography of books, articles, papers useful for learning to program with the Swarm libraries.

Books

[Goldberg & Robson, 1989] *Smalltalk 80 : The Language*, Adele Goldberg and David Robson, 0201136880, June 1989, Addions-Wesley.

Abstract. Classic Smalltalk reference.

[Kernighan & Ritchie, 1988] *The C Programming Language*, K & R, , 2, Brian Kernighan and Dennis Ritchie, 0-13-110370-9, Revised, 1988, Prentice Hall, 1988.

Prentice Hall Software Series.

Abstract. The definitive reference on the C programming language by its inventors.

[NeXT, 1993] *Object Oriented Programming and the Objective C Language*, NeXT Computer, 0-201-63251-9, 1993, Addison-Wesley.

Abstract. This book describes the Objective-C language as it is implemented for NeXTSTEP. While clearly targeted at NeXTSTEP, it is a good first-read to get to learn Objective-C

This book is out of print, but availble at the : Apple website (http://developer.apple.com/techpubs/macosxserver/ObjectiveC/index.html)

[Van der Linden, 1994] *Expert C Programming: Deep C Secrets*, Peter van der Linden, 0-13-177429-8, 1994, SunSoft Press: Prentice Hall.

Abstract. A book for more advanced Swarm users: excellent for information on more abstruse matters of memory-management, linker issues and pointers. Covers much UNIX and C arcana which is difficult to find documented anywhere else (obscure man pages notwithstanding) in an engaging and humourous style.

[DiBona et. al. 1999] *Open Sources: Voices from the Open Source Revolution*, Edited by Chris DiBona, Edited by Sam Ockman, Edited by and Mark Stone, 1-56592-582-3, 1999, O'Reilly & Associates Inc., Sebastopol.

Papers

[Daniels, 1999] Marcus Daniels, *Integrating Simulation Technologies with Swarm (http://www.swarm.org/intro-papers.html)*, Agent Simulation: Applications, Models and Tools, October 1999, Argonne National Laboratory, University of Chicago.

Index

A

ActionGroup, 68
activateIn, 36, 69
Activity, 70
  starting and stopping, 71
agent-based, 16
agents
  auxiliary , 33
  primary , 33
arborgames, 35
Archiver
  application
    global, **129**
Arguments protocol, 99
Array
  (See collections)
atOffset:, 109

B

buildActions
  (See Schedule)
buildObjects
  (See object creation)

C

collections
  arrays
    contrast with maps, 110
    usage, 111
  index usage, 77, 117
  lists, 73
    adding and removing objects, 74
    looping through members, 77
  maps
    contrast with arrays, 110
    keys, 112
    usage, 112
  nil objects in, 79
  wrapper usage in, 109
complex systems, 16
control panel, 81
CREATABLE, 54
createActionForEach:
  usage in schedules, 65
createActionTo:
  usage in schedules, 64
createBegin
  (See object creation)
Creating
  (See phases)

D

deleteAll, 109
Drone, 99
drop, 52, 57, **107**
dynamic scheduling
  (See Schedule)

E

EZDistribution, 81
EZGraph, 81, 86

F

forEach:, 109
function
  C, 101

G

get methods, 59
getActivity
  (See Activity)
getCount, 76, 109
graphical interface
  (See GUISwarm)
GUISwarm, 50, 81
  data display graphs, 86
  graph types, 38

H

HDF5, **129**
heatbugs
  command-line parameters, 98
  creating objects in, 49
  parameter files, 130

I

Index Protocol
  (See collections)
instance variables
  intitialization, 59
instantiation
  (See object creation)

J

Java, **21**
  constructor
    (See object creation)

L

Lisp, **129**
LispArchiver
  application
    custom, 132
List Protocol
  (See collections)

M

M()
  (See selector)
Map
  (See collections)
memory allocation
  dynamic, 104
  Swarm Zones, 34, 52
mousetrap
  parameter files, 133

O

object creation, **28**
  buildObjects method, 34
  CREATABLE protocol, 31
  create, 51
  createBegin, 50
  createBegin/createEnd, 29, 49
  createEnd, 50
  in Java, 30
  in Objective C, 29
  object recycling, 57
object-oriented programming, **21**
Object2dDisplay
  usage example, 66
Objective C, **21**
  protocols
    usage inSwarm, 30
objects
  getting information from, 61
OO

(See object-oriented programming)

P

parameter
command-line, 98
files, 129
phases, 49
ProbabilityDistribution Protocol
(See random numbers)
probe displays, 40
programming
object-oriented programming, 16
encapsulation, 18
inheritance, 19
protocols
(See Objective C)

R

random numbers
built-in distributions, 119
creatable distributions, 125
generators, 122
removeAll, 109

S

Schedule
buildActions method, 35
creating, 64
dynamic, 71
selector
adding arguments to, 65
defined, 65
in schedules, 65
justification for usage, 66
nonobject arguments to, 68
usage in display objects, 66
serialization, **129**
set methods, 59
Setting
(See phases)
simulation
agent-based, 16
discrete event, 20
stopping a simulation
(See Activity)
Swarm, **33**
agents
(See agents)
common syntax, 33
described, 12
tutorial, 46
using Swarm library objects , 53

U

Using
(See phases)

V

variable declarations
protocol usage in, 31

W

wrapper, 68, 109
integer wrapper as map key, 114

Z

ZoomRaster, 81, 81

Colophon

This book is generated entirely from a single SGML source document marked up in the DocBook 3.1 DTD (http://www.oasis-open.org/docbook/). To generate the resultant output, we use the Modular DocBook stylesheets (http://www.nwalsh.com/docbook/dsssl/index.html) provided by Norman Walsh (http://www.nwalsh.com).